SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-01-FP	MCHENRY	236	4
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO: 63266

				ROADWAY 80% FED 20% COUNTY	TRAFFIC SIGNALS 80% FED 20% COUNTY	RETAINING WALL 80% FED 20% COUNTY	WATERMAIN 78% COUNTY 22% CRYSTAL LAKE	COUNTY 100%
ITEM NO	DESCRIPTION	UNIT	URBAN TOTAL	CONSTRUCTION TYPE CODE				
				1000-2A	Y031-1F	Y007	Y060	1000-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	832	832				
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1207	1207				
20101000	TEMPORARY FENCE	FOOT	345	345				
20101100	TREE TRUNK PROTECTION	EACH	36	36				
20101200	TREE ROOT PRUNING	EACH	50	50				
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	25	25				
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	25	25				
20200100	EARTH EXCAVATION	CU YD	12755	12755				
20200300	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	7	7				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	12983	12941				42
20400800	FURNISHED EXCAVATION	CU YD	5710	5710				
20700220	POROUS GRANULAR EMBANKMENT	CU YD	343			343		
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	3217	3217				
20800150	TRENCH BACKFILL	CU YD	4380	4330			50	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1333	1333				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	55707	55055				652
21101630	TOPSOIL FURNISH AND PLACE, 8"	SQ YD	342	342				
* 21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	342	342				
* 25000210	SEEDING, CLASS 2A	ACRE	8.75	8.5				0.25
* 25000312	SEEDING, CLASS 4A	ACRE	2	2				
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1085	1062				23
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1085	1062				23
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1085	1062				23
* 25002024	SEEDING, CLASS 4B (MODIFIED)	ACRE	0.25	0.25				
* 25100630	EROSION CONTROL BLANKET	SQ YD	35493	35493				
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	17747	17747				
* 25100900	TURF REINFORCEMENT MAT	SQ YD	72	72				
* 25200110	SODDING, SALT TOLERANT	SQ YD	23948	23948				
* 25200200	SUPPLEMENTAL WATERING	UNIT	239	239				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1158	1158				
28000400	PERIMETER EROSION BARRIER	FOOT	14900	14900				
28000500	INLET AND PIPE PROTECTION	EACH	4	4				
28000510	INLET FILTERS	EACH	133	133				
28001000	AGGREGATE (EROSION CONTROL)	TON	1	1				
28100105	STONE RIPRAP, CLASS A3	SQ YD	19	19				
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1147	1147				
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	20570	20570				
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	8179	8179				

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SUMMARY OF QUANTITIES
1 OF 6

SCALE: N.T.S. DRAWN BY: MCD
DATE: 12/01/09 CHECKED BY: KA

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000

..\SU0004RG.DGN,..\SU0004RGJOIN,..\TTBOXY.VDGN
1:28:2010,15:48:34 I:\DOCUMENT\P3900003\CIVIL\DGN\SU0004RT.DGN
KRAUTLA 630 659 6061 6263