

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-01-FP	MCHENRY	236	9
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
CONTRACT NO: 63266				

ITEM NO	DESCRIPTION	UNIT	URBAN TOTAL	CONSTRUCTION TYPE CODE				
				ROADWAY 80% FED 20% COUNTY	TRAFFIC SIGNALS 80% FED 20% COUNTY	RETAINING WALL 80% FED 20% COUNTY	WATERMAIN 78% COUNTY 22% CRYSTAL LAKE	COUNTY 100%
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	6	1000-2A	Y031-IF	Y007	Y060	1000-2A
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1			
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1			
* 89502380	REMOVE EXISTING HANDHOLE	EACH	11		11			
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9		9			
X0321598	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1				
X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	39	39				
* X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	25	25				
X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	4080			4080		
X2010400	STUMP REMOVAL ONLY	UNIT	414	414				
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	27	27				
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2				
X4023000	TEMPORARY ACCESS (ROAD)	EACH	10	10				
X5121800	PERMANENT STEEL SHEET PILING	SQ FT	5060			5060		
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	4		4			
* X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	4		4			
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	2089		2089			
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1128		1128			
* XX003519	DUCTILE IRON WATER MAIN FITTING - 12" X 6" TEE	EACH	2				2	
* XX004731	CONNECTION TO EXISTING WATERMAIN	EACH	2				2	
XX005400	RESTRICTED DEPTH MANHOLES, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3				
* XX005723	VIDEO DETECTION SYSTEM COMPLETE INTERSECTION	EACH	4		4			
* XX005776	DUCTILE IRON WATER MAIN FITTINGS 45 BEND 12"	EACH	4				4	
XX006746	RUSTICATION FINISH TYPE 1	SQ FT	2274			2274		
XX007103	RESTRICTED DEPTH MANHOLES, 5'-DIAMETER, 2-TYPE 1 FRAME & LID, RESTRICTOR PLATE	EACH	3	3				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	10	10				
Z0019500	DRYWELL	EACH	1	1				
Z0022800	FENCE REMOVAL	FOOT	1376	1376				
Z0066400	STABILIZED DRIVEWAYS 6"	SQ YD	1511	1511				
Z0066600	STABILIZED DRIVEWAYS 8"	SQ YD	551	301				250
△ Z0076600	TRAINEES	hour	2000	2000				
XX008290	TEMPORARY DITCH CHECKS, SPECIAL	EACH	213	213				
550A5100	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 30"	FOOT	9	9				
550A5110	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 48"	FOOT	497	497				
51215460	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 60"	EACH	1	1				
* X8730180	ELECTRIC CABLE IN CONDUIT, SIGNAL NO 18 3C	FOOT	2865		2865			
XX002173	TREATED TIMBER RAIL	FOOT	490	490				
XX008337	SIGHT SCREEN (WOODEN FENCE), TYPE P 4', MODIFIED, ATTACHED TO STRUCTURE	FOOT	75	75				
64100115	SIGHT SCREEN (WOODEN FENCE), TYPE P 6'	FOOT	74	74				

* SPECIALTY ITEM
△ Y080

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SUMMARY OF QUANTITIES
6 OF 6

SCALE: N.T.S. DRAWN BY: MCD
DATE: 12/01/09 CHECKED BY: KA



C:\SUDOPR\DESIGN\...SUDOPR\DESIGN\...ATTORNEY WORK
 12-28-2009 15:47:42
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63