F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-01-FP	MCHENRY	236	18
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO: 63266

SCHEDULE OF QUANTITIES

EARTHWORK SCHEDULE

WALKUP ROAD STATION	TO STATION	EARTH EXCAVATION STAGE I CYD	EARTH EXCAVATION STAGE II CYD	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (TOPSOIL & UNDERCUT) STAGE I CYD	REMOVAL STAGE II CYD	EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) STAGE I CYD	EXCAVATION STAGE II CYD	EMBANKMENT STAGE I CYD	EMBANKMENT STAGE II CYD	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) STAGE I CYD	EARTHWORK BALANCE STAGE II CYD	POROUS GRANULAR EMBANKMENT SUBGRADE STAGE I CYD	POROUS GRANULAR EMBANKMENT SUBGRADE STAGE II CYD
67+36.36	67+50.00	0.4	0.0	5.0	0.0	0.3	0.0	10.8	0.0	-10.5	0.0	0.0	0.0
67+50.00	68+00.00	0.0	0.0	23.9	0.0	0.0	0.0	80.3	0.0	-80.3	0.0	0.0	0.0
68+00.00	69+00.00	5.1	0.0	50.5	0.0	4.3	0.0	100.6	0.0	-96.3	0.0	0.0	0.0
69+00.00	70+00.00	9.7	0.0	50.9	0.0	8.2	0.0	54.0	0.0	-45.8	0.0	0.0	0.0
70+00.00	71+00.00	9.4	0.0	44.7	0.0	8.0	0.0	48.5	0.0	-40.5	0.0	0.0	0.0
71+00.00	72+00.00	9.6	0.0	44.6	0.0	8.1	0.0	63.6	0.0	-55.5	0.0	0.0	0.0
72+00.00	73+00.00	9.6	0.0	50.3	0.0	8.1	0.0	110.7	0.0	-102.6	0.0	0.0	0.0
73+00.00	74+00.00	9.7	0.0	25.6	0.0	8.3	0.0	78.7	0.0	-70.5	0.0	0.0	0.0
74+00.00	75+00.00	10.1	0.0	21.0	0.0	8.6	0.0	49.3	0.0	-40.8	0.0	0.0	0.0
75+00.00	76+00.00	11.1	0.0	47.6	0.0	9.4	0.0	115.2	0.0	-105.8	0.0	0.0	0.0
76+00.00	77+00.00	28.8	0.0	49.0	0.0	24.4	0.0	89.0	0.0	-64.6	0.0	0.0	0.0
77+00.00	78+00.00	31.3	0.0	45.8	0.0	26.6	0.0	8.4	0.0	18.2	0.0	0.0	0.0
78+00.00	79+00.00	38.4	0.0	46.2	0.0	32.6	0.0	4.8	0.0	27.9	0.0	0.0	0.0
79+00.00	80+00.00	30.0	0.0	46.9	0.0	25.5	0.0	23.7	0.0	1.8	0.0	0.0	0.0
80+00.00	81+00.00	0.1	0.0	24.1	0.0	0.0	0.0	23.4	0.0	-23.3	0.0	0.0	0.0
81+00.00	82+00.00	0.0	0.0	17.9	0.0	0.0	0.0	40.7	0.0	-40.7	0.0	0.0	0.0
82+00.00	83+00.00	0.0	0.0	36.6	0.0	0.0	0.0	93.4	0.0	-93.4	0.0	0.0	0.0
83+00.00	84+00.00	0.0	0.0	36.4	0.0	0.0	0.0	107.5	0.0	-107.5	0.0	0.0	0.0
84+00.00	85+00.00	0.0	0.0	34.9	0.0	0.0	0.0	87.3	0.0	-87.3	0.0	0.0	0.0
85+00.00	86+00.00	7.8	0.0	40.6	0.0	6.6	0.0	39.4	0.0	-32.8	0.0	0.0	0.0
86+00.00	87+00.00	85.2	0.0	48.6	0.0	72.4	0.0	7.4	0.0	65.0	0.0	0.0	0.0
87+00.00	88+00.00	87.3	0.0	41.6	0.0	74.2	0.0	2.2	0.0	72.0	0.0	0.0	0.0
88+00.00	89+00.00	79.4	0.0	38.1	0.0	67.4	0.0	2.1	0.0	65.3	0.0	0.0	0.0
89+00.00	90+00.00	89.6	0.0	39.8	0.0	76.2	0.0	1.4	0.0	74.7	0.0	0.0	0.0
90+00.00	91+00.00	20.1	0.0	18.1	0.0	17.1	0.0	1.0	0.0	16.1	0.0	0.0	0.0
91+00.00	92+00.00	0.0	0.0	21.2	0.0	0.0	0.0	80.6	0.0	-80.6	0.0	0.0	0.0
92+00.00	92+30.00	1.3	0.0	13.0	0.0	1.1	0.0	43.7	0.0	-42.7	0.0	0.0	0.0
92+30.00	93+00.00	6.6	0.0	26.3	0.0	5.6	0.0	72.7	0.0	-67.2	0.0	0.0	0.0
93+00.00	94+00.00	10.4	0.0	31.1	0.0	8.8	0.0	88.8	0.0	-80.0	0.0	0.0	0.0
94+00.00	95+00.00	9.9	0.0	31.2	0.0	8.4	0.0	71.1	0.0	-62.7	0.0	0.0	0.0
95+00.00	95+10.00	0.9	0.0	3.2	0.0	0.8	0.0	4.3	0.0	-3.5	0.0	0.0	0.0
95+10.00	96+00.00	25.3	0.0	31.4	0.0	21.5	0.0	21.1	0.0	0.4	0.0	0.0	0.0
96+00.00	97+00.00	187.7	0.0	52.3	0.0	159.6	0.0	3.7	0.0	155.9	0.0	0.0	0.0
97+00.00	98+00.00	527.1	0.0	81.3	0.0	448.0	0.0	4.3	0.0	443.7	0.0	0.0	0.0
98+00.00	99+00.00	575.4	0.0	82.8	0.0	489.1	0.0	6.8	0.0	482.2	0.0	0.0	0.0
99+00.00	100+00.00	566.8	0.0	75.7	0.0	481.8	0.0	5.1	0.0	476.7	0.0	0.0	0.0
100+00.00	101+00.00	588.9	0.0	76.5	0.0	500.5	0.0	1.3	0.0	499.2	0.0	0.0	0.0
101+00.00	102+00.00	278.1	0.0	60.6	0.0	236.4	0.0	1.3	0.0	235.2	0.0	0.0	0.0
102+00.00	102+70.00	40.5	0.0	27.7	0.0	34.4	0.0	1.3	0.0	33.1	0.0	0.0	0.0
102+70.00	103+00.00	4.1	0.0	4.6	0.0	3.5	0.0	0.4	0.0	3.2	0.0	0.0	0.0
103+00.00	103+27.00	5.8	0.0	5.2	0.0	4.9	0.0	0.5	0.0	4.4	0.0	0.0	0.0
103+27.00	103+45.00	22.4	0.0	8.9	0.0	19.0	0.0	0.4	0.0	18.7	0.0	0.0	0.0
103+45.00	104+00.00	76.7	0.0	31.2	0.0	65.2	0.0	0.5	0.0	64.7	0.0	0.0	0.0
104+00.00	104+50.00	29.2	0.0	26.3	0.0	24.8	0.0	0.9	0.0	23.9	0.0	0.0	0.0
104+50.00	105+00.00	22.4	0.0	26.8	0.0	19.0	0.0	1.8	0.0	17.3	0.0	0.0	0.0
105+00.00	105+55.00	38.1	0.0	30.2	0.0	32.4	0.0	1.7	0.0	30.7	0.0	0.0	0.0
105+55.00	106+00.00	44.8	0.0	25.1	0.0	38.0	0.0	0.7	0.0	37.4	0.0	0.0	0.0
106+00.00	106+60.00	96.2	0.0	35.6	0.0	81.8	0.0	0.8	0.0	81.0	0.0	0.0	0.0
106+60.00	107+00.00	75.9	0.0	24.2	0.0	64.5	0.0	0.4	0.0	64.1	0.0	0.0	0.0
107+00.00	107+65.00	100.3	0.0	37.3	0.0	85.2	0.0	0.9	0.0	84.4	0.0	0.0	0.0
107+65.00	108+00.00	42.9	0.0	19.4	0.0	36.5	0.0	0.6	0.0	35.9	0.0	0.0	0.0
108+00.00	108+65.00	34.6	0.0	33.2	0.0	29.4	0.0	5.4	0.0	24.0	0.0	0.0	0.0
108+65.00	109+00.00	0.9	0.0	16.8	0.0	0.8	0.0	14.0	0.0	-13.2	0.0	0.0	0.0
109+00.00	109+35.00	0.1	0.0	16.1	0.0	0.1	0.0	20.6	0.0	-20.5	0.0	0.0	0.0
109+35.00	109+80.00	0.1	0.0	29.2	0.0	0.1	0.0	46.4	0.0	-46.3	0.0	0.0	0.0
109+80.00	110+00.00	0.0	0.0	16.0	0.0	0.0	0.0	25.5	0.0	-25.5	0.0	0.0	0.0
110+00.00	111+00.00	0.0	0.0	56.6	0.0	0.0	0.0	90.7	0.0	-90.7	0.0	0.0	0.0
111+00.00	112+00.00	0.0	0.0	53.4	0.0	0.0	0.0	155.3	0.0	-155.3	0.0	0.0	0.0
112+00.00	113+00.00	7.3	0.0	67.0	0.0	6.2	0.0	168.2	0.0	-161.9	0.0	0.0	0.0
113+00.00	114+00.00	9.0	0.0	57.9	0.0	7.7	0.0	121.0	0.0	-113.4	0.0	0.0	0.0
114+00.00	115+00.00	4.4	0.0	47.3	0.0	3.8	0.0	112.1	0.0	-108.3	0.0	0.0	0.0
115+00.00	116+00.00	2.9	0.0	45.7	0.0	2.5	0.0	92.6	0.0	-90.1	0.0	0.0	0.0
116+00.00	117+00.00	0.2	0.0	47.3	0.0	0.1	0.0	117.5	0.0	-117.4	0.0	0.0	0.0
117+00.00	118+00.00	0.0	0.0	48.0	0.0	0.0	0.0	138.6	0.0	-138.6	0.0	0.0	0.0
118+00.00	119+00.00	0.0	0.0	50.3	0.0	0.0	0.0	156.7	0.0	-156.7	0.0	0.0	0.0
119+00.00	120+00.00	0.0	0.0	56.0	0.0	0.0	0.0	201.0	0.0	-201.0	0.0	0.0	0.0
120+00.00	121+00.00	0.0	0.0	57.5	0.0	0.0	0.0	232.8	0.0	-232.8	0.0	0.0	0.0
121+00.00	122+00.00	0.0	0.0	58.2	0.0	0.0	0.0	258.6	0.0	-258.6	0.0	0.0	0.0
122+00.00	123+00.00	0.0	0.0	61.4	0.0	0.0	0.0	281.7	0.0	-281.7	0.0	0.0	0.0
123+00.00	124+00.00	0.0	0.0	62.7	0.0	0.0	0.0	298.0	0.0	-298.0	0.0	0.0	0.0
124+00.00	125+00.00	0.0	0.0	63.8	0.0	0.0	0.0	324.9	0.0	-324.9	0.0	0.0	0.0
125+00.00	126+00.00	0.0	0.0	61.4	0.0	0.0	0.0	294.1	0.0	-294.1	0.0	0.0	0.0
126+00.00	126+55.00	0.0	0.0	33.0	0.0	0.0	0.0	179.2	0.0	-179.2	0.0	0.0	0.0
126+55.00	126+85.00	0.0	0.0	17.0	0.0	0.0	0.0	95.9	0.0	-95.9	0.0	0.0	0.0
126+85.00	127+00.00	0.0	0.0	7.8	0.0	0.0	0.0	30.0	0.0	-30.0	0.0	0.0	0.0
127+00.00	128+00.00	3.9	0.0	31.1	0.0	3.3	0.0	82.6	0.0	-79.4	0.0	0.0	0.0
128+00.00	129+00.00	3.9	0.0	25.4	0.0	3.3	0.0	35.6	0.0	-32.3	0.0	0.0	0.0

REVISIONS NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SCHEDULE OF QUANTITIES
3 OF 5

SCALE: N.T.S. DRAWN BY: MZD
DATE: 12/01/09 CHECKED BY: MCD

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000

..\SCD00@F.DGN,..\TTB00Y_V.DGN,..\SCD00@F.DGN
18-30-2009, 3:23:40 T:\DOCUMENT\93000\CIVIL\DGN\SCD00@58.DGN
STANKIRJ