F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0085	00-00246-01-FP	MCHENRY	236	127
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO: 63266

SIGN ID	ROAD	EXISTING LOCATION STATION	EXISTING LOCATION OFFSET	RELOCATED STATION	RELOCATED OFFSET	SIGN DESCRIPTION	GROUND MOUNTING TYPE	HEIGHT FT	WIDTH FT	AREA SQ. FT	PROP. ACTION	PANEL TYPE	REMOVE SIGN PANEL TY 1 72400310	REMOVE SIGN PANEL TY 2 72400320	RELOCATE SIGN PANEL TY 1 72400710	RELOCATE SIGN PANEL TY 2 72400720
S-2	WALKUP RD	76+85	38.0	76+78	40.0	WARNING: FIBER OPTIC CABLE	TELESCOPING	1.00	0.30	0.30	RELOCATE	1	0.30		0.30	
S-3	WALKUP RD	77+41	28.0			THRU/ RIGHT TURN ONLY	WOOD POST	2.50	2.50	6.25	REMOVE	1	6.25			
S-4	WALKUP RD	79+05	34.0			SPEED LIMIT 40	TELESCOPING	3.50	2.50	8.75	REMOVE	1	8.75			
S-5	BURNING BUSH	80+96	48.0			STOP SIGN	TELESCOPING	3.00	3.00	7.45	REMOVE	1	7.45			
S-7	WALKUP RD	86+17	27.0			LEFT TURN ONLY/ RIGHT TURN&THRU	WOOD POST	2.50	2.50	6.25	REMOVE	1	6.25			
S-9	INDIAN HILL TR	91+01	55.0			STOP SIGN	TELESCOPING	3.00	3.00	7.45	REMOVE	1	7.45			
S-10	WALKUP RD	93+27	36.0			SPEED LIMIT 40	TELESCOPING	3.00	2.50	7.50	REMOVE	1	7.50			
S-11	WALKUP RD	96+71	36.0			STOP LIGHT HILLSIDE RD	TELESCOPING	1.50	5.00	7.50	REMOVE	1	7.50			
S-12	WALKUP RD	98+20	35.0			LEFT TURN ONLY/ THRU/ RIGHT TURN ONLY	TELESCOPING	2.50	3.50	8.75	REMOVE	1	8.75			
S-14	WALKUP RD	104+26	40.0			SPEED LIMIT 40	TELESCOPING	3.00	2.50	7.50	REMOVE	1	7.50			
S-15	WALKUP RD	106+46	37.0	106+54	36.0	MCHENRY COUNTY "ADOPT A HIGHWAY"	TELESCOPING	2.50	2.50	6.25	RELOCATE	1	6.25		6.25	
S-15A	WALKUP RD	106+46	37.0	106+54	36.0	YOUR GROUP NAME HERE	TELESCOPING	2.50	1.50	3.75	RELOCATE	1	3.75		3.75	
S-16	WALKUP RD	108+32	36.0			LEFT TURN ONLY/ THRU	WOOD POST	2.50	2.50	6.25	REMOVE	1	6.25			
S-17	WALKUP RD	120+18	26.0	120+08	41.0	PRAIRIE RIDGE HIGH SCHOOL 2008 IHSA CHAMPION	TELESCOPING	2.50	4.00	10.00	RELOCATE	2		10		10
S-18	WALKUP RD	122+04	28.0			SCHOOL SPEED LIMIT AHEAD	TELESCOPING	3.00	3.00	9.00	REMOVE	1	9.00			
S-19	WALKUP RD	124+22	30.0			SCHOOL	TELESCOPING	3.00	3.00	9.00	REMOVE	1	9.00			
S-19A	WALKUP RD	124+22	30.0			AHEAD	TELESCOPING	1.00	2.00	2.00	REMOVE	1	2.00			
S-20	WALKUP RD	125+95	28.0			SCHOOL SPEED LIMIT 20 WHEN CHILDREN PRESENT	METAL POST	4.00	2.00	8.00	REMOVE	1	8.00			
S-21	WALKUP RD	127+80	29.0			SCHOOL	TELESCOPING	3.00	3.00	9.00	REMOVE	1	9.00			
S-21A	WALKUP RD	127+80	29.0			LEFT DOWN ARROW	TELESCOPING	1.75	1.25	2.19	REMOVE	1	2.19			
S-22B	WALKUP RD/ DVORAK DR	128+67	44.0			STOP SIGN	TELESCOPING	3.00	3.00	7.45	REMOVE	1	7.45			
S-23	WALKUP RD	130+06	28.0			SPEED LIMIT 40	TELESCOPING	3.00	2.50	7.50	REMOVE	1	7.50			
S-24	WALKUP RD	131+16	24.0			LEFT TURN ONLY/ THRU	TELESCOPING	2.50	2.50	6.25	REMOVE	1	6.25			
S-25	WALKUP RD/ SHENANDOAH CT	141+16	36.0	141+04	52.0	SHENANDOAH CT	TELESCOPING	0.75	3.00	2.25	RELOCATE	1	2.25		2.25	
S-25A	WALKUP RD/ SHENANDOAH CT	141+16	36.0	141+04	52.0	SHENANDOAH CT	TELESCOPING	0.75	3.00	2.25	RELOCATE	1	2.25		2.25	
S-28	SHENANDOAH CT	141+85	46.0			STOP SIGN	TELESCOPING	3.00	3.00	7.45	REMOVE	1	7.45			
S-30	WALKUP RD	143+77	32.0			CROSS RD	TELESCOPING	3.00	3.00	9.00	REMOVE	1	9.00			
S-30A	WALKUP RD	143+77	32.0			DEERWOOD DR (LEFT) PLEASANT HILL RD (RT)	TELESCOPING	1.50	3.00	4.50	REMOVE	1	4.50			
S-31	WALKUP RD/ DEERWOOD DR/	151+33	35.0			DEERWOOD DR	TELESCOPING	0.75	3.50	2.63	REMOVE	1	2.63			
S-31A	/PLEASANT HILL RD	151+33	35.0			WALKUP RD	TELESCOPING	0.75	5.50	4.13	REMOVE	1	4.13			
S-31B	WALKUP RD/ DEERWOOD DR/	151+33	35.0			PLEASANT HILL RD	TELESCOPING	0.75	4.00	3.00	REMOVE	1	3.00			
S-33	PLEASANT HILL RD	151+87	39.0			STOP SIGN	TELESCOPING	3.00	3.00	7.45	REMOVE	1	7.45			
S-34	WALKUP RD	152+56	29.0	153+84	32.0	MCHENRY COUNTY "ADOPT A HIGHWAY"	TELESCOPING	2.50	2.50	6.25	RELOCATE	1	6.25		6.25	
S-34A	WALKUP RD	152+56	29.0	153+84	32.0	MCHENRY COUNTY RETIRED TEACHERS	TELESCOPING	2.50	1.50	3.75	RELOCATE	1	3.75		3.75	
S-35	WALKUP RD	154+59	24.0			SPEED LIMIT 45	WOOD POST	3.00	2.50	7.50	REMOVE	1	7.50			
S-37	HIDDEN OAK DR	168+89	48.0			STOP SIGN	WOOD POST	3.00	3.00	7.45	REMOVE	1	7.45			
S-40	WALKUP RD	174+95	24.0			CROSS RD	TELESCOPING	3.00	3.00	9.00	REMOVE	1	9.00			
S-40A	WALKUP RD	174+95	24.0			EDGEWOOD RD (RIGHT) BERRY CT (LEFT)	TELESCOPING	1.50	3.00	4.50	REMOVE	1	4.50			
S-41	WALKUP RD	178+03	22.0			SCHOOL BUS STOP AHEAD	WOOD POST	3.00	3.00	9.00	REMOVE	1	9.00			
S-42	EDGEWOOD RD	181+89	37.0	153+84	31.0	WEIGHT LIMIT 5 TONS	TELESCOPING	2.50	2.00	5.00	RELOCATE	1	5.00		5.00	
S-42A	EDGEWOOD RD	181+89	37.0	153+84	31.0	EXCEPT FOR LOCAL DELIVERIES	TELESCOPING	2.00	1.50	3.00	RELOCATE	1	3.00		3.00	
S-44	EDGEWOOD RD	182+33	40.0			STOP SIGN	WOOD POST	3.00	3.00	7.45	REMOVE	1	7.45			
S-45	WALKUP RD	184+10	23.0			SPEED LIMIT 45	WOOD POST	3.00	2.50	7.50	REMOVE	1	7.50			
S-47	RUNNING IRON DR	190+60	28.0			STOP SIGN	WOOD POST	3.00	3.00	7.45	REMOVE	1	7.45			
S-48	WALKUP RD/ RUNNING IRON DR	190+67	22.0	190+96	28.0	WALKUP RD	TELESCOPING	0.75	2.50	1.88	RELOCATE	1	1.88		1.88	
S-48A	WALKUP RD/ RUNNING IRON DR	190+67	22.0	190+96	28.0	RUNNING IRON DR	TELESCOPING	0.75	4.00	3.00	RELOCATE	1	3.00		3.00	
S-49	WALKUP RD	195+20	28.0			REVERSE CURVE	WOOD POST	3.00	3.00	9.00	REMOVE	1	9.00			
S-50	WALKUP RD	197+49	22.0			SIDE ROAD	WOOD POST	3.00	3.00	9.00	REMOVE	1	9.00			
S-50A	WALKUP RD	197+49	22.0			CRYSTAL SPRINGS RD	WOOD POST	0.75	4.00	3.00	REMOVE	1	3.00			
S-51	WALKUP RD	198+42	21.0			SPEED LIMIT 45	WOOD POST	3.00	2.50	7.50	REMOVE	1	7.50			
S-52	WALKUP RD	205+18	24.0			LEFT TURN ONLY/ THRU	WOOD POST	3.00	2.50	7.50	REMOVE	1	7.50			
S-53	WALKUP RD	207+95	29.0	207+95	29.0	VILLAGE OF BULL VALLEY	WOOD POST	2.00	4.00	8.00	RELOCATE	1	8.00		8.00	
S-54	WALKUP RD	209+33	28.0	209+87	32.0	MCHENRY COUNTY "ADOPT A HIGHWAY"	TELESCOPING	2.50	2.50	6.25	RELOCATE	1	6.25		6.25	
S-54A	WALKUP RD	209+33	28.0	209+87	32.0	YOUR GROUP NAME HERE	TELESCOPING	2.50	1.50	3.75	RELOCATE	1	3.75		3.75	
S-55	WALKUP RD	211+89	32.0			SPEED LIMIT 45	WOOD POST	3.00	2.50	7.50	REMOVE	1	7.50			
S-58	HAZELWOOD DR	217+46	56.0	217+47	49.0	HAZELWOOD DR	TELESCOPING	0.75	3.50	2.63	RELOCATE	1	2.63		2.63	
S-58A	HAZELWOOD DR	217+46	56.0	217+47	49.0	HAZELWOOD DR	TELESCOPING	0.75	3.50	2.63	RELOCATE	1	2.63		2.63	
S-58B	HAZELWOOD DR	217+46	56.0			STOP SIGN	TELESCOPING	3.00	3.00	7.45	REMOVE	1	7.45			
S-66	WALKUP RD	216+71	-25.0			SIDE ROAD	WOOD POST	3.00	3.00	9.00	REMOVE	1	9.00			
S-66A	WALKUP RD	216+71	-25.0			CRYSTAL SPRINGS RD	WOOD POST	0.75	3.00	2.25	REMOVE	1	2.25			
S-67	WALKUP RD	214+80	-22.0			SPEED LIMIT 45	WOOD POST	3.00	2.50	7.50	REMOVE	1	7.50			
S-68	WALKUP RD	211+97	-26.0			THRU/ RIGHT TURN ONLY	WOOD POST	3.00	2.50	7.50	REMOVE	1	7.50			
S-69	WALKUP RD	211+34	-30.0	210+82	-41.0	VILLAGE OF BULL VALLEY	WOOD POST	2.00	4.00	8.00	RELOCATE	1	8.00		8.00	
S-70	WALKUP RD	208+71	-51.0			WALKUPRD	TELESCOPING	1.00	3.00	3.00	REMOVE	1	3.00			

NOTE:
1) FOR EXISTING ROADWAY SIGN TO "REMAIN" REFER SHEET 3 OF 3 UNDER EXISTING SIGNING SCHEDULE
2) FOR SCHEDULE OF QUANTITIES FOR "RELOCATION" REFER SHEET 2 OF 2 UNDER PROPOSED SIGNING SHEET

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SIGNING SCHEDULE EXISTING SIGNS SHEET 1 OF 3

SCALE: N.T.S. DRAWN BY: MAM
DATE: 08/17/09 CHECKED BY: BRH

TENG
TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000

..\SC009RC.DGN..\TTBOOY_V.DGN..\SC0008-3.DGN
8-14-2009,4:55:33 T:\DOCUMENT\93100\03\CIVIL\DGN\SGN006-1.DGN
1 2 3 4 5 6 7 8 9 0 1 2 3 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63
STANKIRJ