

SIGN ID	ROAD	EXISTING LOCATION		RELOCATED		SIGN DESCRIPTION	GROUND MOUNTING TYPE	HEIGHT FT	WIDTH FT	AREA SQ. FT	PROP. ACTION	PANEL TYPE	REMOVE SIGN	REMOVE SIGN	RELOCATE SIGN	RELOCATE SIGN	
		STATION	OFFSET	STATION	OFFSET								PANEL TY 1	PANEL TY 2	PANEL TY 1	PANEL TY 2	
S-70A	WALKUP RD	208+71	-51.0			CRYSTAL SPRINGS RD	TELESCOPING	1.00	4.00	4.00	REMOVE	1	4.00				
S-71	CRYSTAL SPRING RD	207+86	-42.0			STOP SIGN	WOOD POST	3.00	3.00	7.45	REMOVE	1	7.45				
S-73	WALKUP RD	198+93	-24.0			SPEED LIMIT 45	WOOD POST	3.00	2.50	7.50	REMOVE	1	7.50				
S-74	WALKUP RD	198+20	-24.0			SCHOOL BUS STOP AHEAD	WOOD POST	3.00	3.00	9.00	REMOVE	1	9.00				
S-75	WALKUP RD/ OAKWOOD MANOR DR	190+19	-39.0	190+07	-37.0	STREET SIGN (OAKWOOD MANOR DR)	TELESCOPING	0.75	4.00	3.00	RELOCATE	1	3.00			3.00	
S-75A	WALKUP RD/ OAKWOOD MANOR DR	190+19	-39.0	190+07	-37.0	STREET SIGN (OAKWOOD MANOR DR)	TELESCOPING	0.75	4.00	3.00	RELOCATE	1	3.00			3.00	
S-76	OAKWOOD MANOR DR	190+23	-51.0			STOP SIGN	TELESCOPING	3.00	3.00	7.45	REMOVE	1	7.45				
S-77	WALKUP RD	189+35	-26.0			CROSS ROAD	TELESCOPING	3.00	3.00	9.00	REMOVE	1	9.00				
S-77A	WALKUP RD	189+35	-26.0			EDGEWOOD RD (LEFT) BERRY CT (RIGHT)	TELESCOPING	1.50	3.00	4.50	REMOVE	1	4.50				
S-78	WALKUP RD	182+40	-40.0			STREET SIGN (WALKUP RD)	TELESCOPING	0.75	3.00	2.25	REMOVE	1	2.25				
S-78A	WALKUP RD	182+40	-40.0			STREET SIGN (EDGEWATER RD)/ (BERRY CT)	TELESCOPING	1.50	3.00	4.50	REMOVE	1	4.50				
S-79	BERRY CT	182+24	-61.0	182+32	-94.0	RED SQUARE	TELESCOPING	1.50	1.50	2.25	RELOCATE	1	2.25			2.25	
S-79A	BERRY CT	182+24	-61.0	182+32	-94.0	WEIGHT LIMIT 5 TONS	TELESCOPING	2.50	2.00	5.00	RELOCATE	1	5.00			5.00	
S-79B	BERRY CT	182+24	-61.0	182+32	-94.0	NO THRU TRUCK TRAFFIC	TELESCOPING	2.00	1.50	3.00	RELOCATE	1	3.00			3.00	
S-80	BERRY CT	181+77	-37.0			STOP SIGN	WOOD POST	3.00	3.00	7.45	REMOVE	1	7.45				
S-81	WALKUP RD	179+87	-22.0			SPEED LIMIT 45	TELESCOPING	3.00	2.50	7.50	REMOVE	1	7.50				
S-82	WALKUP RD	164+86	-23.0			NO PASSING ZONE	TELESCOPING	4.00	5.00	10.00	REMOVE	2		10			
S-84	WALKUP RD	158+87	-22.0			CROSS ROAD	WOOD POST	3.00	3.00	9.00	REMOVE	1	9.00				
S-84A	WALKUP RD	158+87	-22.0			PLEASANT HILL RD (LEFT) DEERWOOD DR (RIGHT)	WOOD POST	1.50	3.00	4.50	REMOVE	1	4.50				
S-85	WALKUP RD	152+66	-42.0			RIGHT TURN ONLY	TELESCOPING	2.50	2.00	5.00	REMOVE	1	5.00				
S-86	DEERWOOD DR	151+87	-77.0	151+91	-79.0	WEIGHT LIMIT 8 TONS	TELESCOPING	2.50	2.00	5.00	RELOCATE	1	5.00			5.00	
S-87	DEERWOOD DR	151+46	-51.0			STOP SIGN	TELESCOPING	3.00	3.00	7.45	REMOVE	1	7.45				
S-88	DEERWOOD DR	151+37	-48.0			DEERWOOD DRIVE	WOOD POST	3.50	5.00	7.45	RELOCATE	1	7.45			7.45	
S-89	WALKUP RD	149+65	-23.0			SPEED LIMIT 40	WOOD POST	3.00	2.50	7.50	REMOVE	1	7.50				
S-90	WALKUP RD	142+88	-22.0	143+11	-32.0	MCHENRY COUNTY "ADOPT A HIGHWAY"	TELESCOPING	2.50	2.50	6.25	RELOCATE	1	6.25			6.25	
S-90A	WALKUP RD	142+88	-22.0	143+11	-32.0	YOUR GROUP NAME HERE	TELESCOPING	2.50	1.50	3.75	RELOCATE	1	3.75			3.75	
S-91	WALKUP RD	137+22	-30.0	138+22	-36.0	PRAIRIE RIDGE HIGH SCHOOL 2008 IHSA CHAMPION	TELESCOPING	2.50	4.00	10.00	RELOCATE	2		10			10
S-92	WALKUP RD	135+75	-28.0			SCHOOL ZONE SPEED LIMIT AHEAD	TELESCOPING	3.00	3.00	9.00	REMOVE	1	9.00				
S-95	LIVE OAK RD	134+21	-39.0			STOP SIGN	WOOD POST	3.00	3.00	7.45	REMOVE	1	7.45				
S-96	WALKUP RD	132+16	-29.0			SCHOOL	TELESCOPING	3.00	3.00	9.00	REMOVE	1	9.00				
S-96A	WALKUP RD	132+16	-29.0			AHEAD	TELESCOPING	1.00	2.00	2.00	REMOVE	1	2.00				
S-97	WALKUP RD	131+99	-28.0			LEFT TURN ONLY/ THRU	TELESCOPING	2.50	2.50	6.25	REMOVE	1	6.25				
S-98	WALKUP RD	130+22	-32.0			SCHOOL SPEED LIMIT 20 WHEN CHILDREN PRESENT	METAL POST	4.00	2.00	8.00	REMOVE	1	8.00				
S-99	WALKUP RD	128+28	-32.0			SCHOOL	TELESCOPING	3.00	3.00	9.00	REMOVE	1	9.00				
S-99A	WALKUP RD	128+28	-32.0			LEFT DOWN ARROW	TELESCOPING	1.75	1.25	2.19	REMOVE	1	2.19				
S-100	WALKUP RD	125+98	-43.0			SPEED LIMIT 40	TELESCOPING	3.00	2.50	7.50	REMOVE	1	7.50				
S-105	VERMONT TR	112+80	-52.0			STOP SIGN	WOOD POST	3.00	3.00	7.45	REMOVE	1	7.45				
S-106	WALKUP RD	110+40	-24.0			STOP LIGHT HILLSIDE RD	TELESCOPING	1.50	5.00	7.50	REMOVE	1	7.50				
S-107	WALKUP RD	107+85	-18.0			LEFT TURN ONLY/ THRU/ RIGHT TURN ONLY	TELESCOPING	2.50	3.00	7.50	REMOVE	1	7.50				
S-108	WALKUP RD	106+42	-19.0			SPEED LIMIT 40	TELESCOPING	3.00	2.50	7.50	REMOVE	1	7.50				
S-112	WALKUP RD	95+60	-23.0			LEFT TURN ONLY/ THRU/ RIGHT TURN ONLY	WOOD POST	2.50	3.00	7.50	REMOVE	1	7.50				
S-113	WALKUP RD	93+15	-30.0			SPEED LIMIT 40	TELESCOPING	3.00	2.50	7.50	REMOVE	1	7.50				
S-115B	WALKUP RD/ WALKUP LN	90+24	-28.0			STOP SIGN	TELESCOPING	3.00	3.00	7.45	REMOVE	1	7.45				
S-116	WALKUP RD	87+19	-23.0			THRU/ RIGHT TURN ONLY	TELESCOPING	2.50	2.50	7.45	REMOVE	1	7.45				
S-119B	WALKUP RD/ REDBIRD LN	82+87	-37.0			STOP SIGN	TELESCOPING	3.00	3.00	7.45	REMOVE	1	7.45				
S-120	WALKUP RD	79+07	-25.0			SPEED LIMIT 40	TELESCOPING	3.00	2.50	7.50	REMOVE	1	7.50				
										TOTAL			659.1	30	107.63	20	

NOTE:

- 1) FOR EXISTING ROADWAY SIGNS TO "REMAIN" REFER SHEET 3 OF 3 UNDER EXISTING SIGNING SCHEDULE
- 2) FOR SCHEDULE OF QUANTITIES FOR "RELOCATION" REFER SHEET 2 OF 2 UNDER PROPOSED SIGNING SCHEDULE

REVISIONS	
NAME	DATE

MCHENRY COUNTY DIVISION OF TRANSPORTATION
WALKUP ROAD F.A.U. 0085

SIGNING SCHEDULE
EXISTING SIGNS
SHEET 2 OF 3

SCALE: N.T.S. DRAWN BY: MAM
DATE: 08/17/09 CHECKED BY: BRH



TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
255 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0000

\SC0008\41C.DGN...ATTBODY...V.DGN...S.C0008-3.DGN...S.C0008-3.DGN
 8-4-2009 14:55:35 T:\DOCUMENT\9300003\CVI.DGN\SIGN008-4.DGN
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63