ORIGINAL SURVEY		BY	DATE
	SURVEYED		
	PLOTTED		
NOTE BOOK	TEMPLATE		
	AREAS		
NO.	AREAS CHECKED		

FINAL SURVEY		BY	DATE
	SURVEYED		
	PLOTTED		
NOTE BOOK	TEMPLATE		
	AREAS		
NO.	AREAS CHECKED		

..\ALT00@QA.DGN, ..\TP000@R.DGN, ..\RDW00@RS.DGN, ..\ROW00@RA.DGN, ..\DRA00@K.DGN, ..\SCR00@X9.DGN, ..\RDW00@XA.DGN, ..\ROW00@RB.DGN, ..\UTL00@R\.DGN, ..\UTL00@RN.DGN, ..\UTL00@RNORIGINAL.DGN, ..\XSC00@X8 WETLANDS.DGN
8-14-2009, 15:05:36 T:\DOCUMENT\93000\CIVIL\DGN\XSC00@X1.DGN S.ANKIRJ

NOTE: THE EXCACT LOCATION AND ELEVATION OF EXISTING STRUCTURES, UTILITIES, AND PIPING SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR.

℄ WALKUP RD

STAGE I

EX ROW

927.45 927.83 927.68 927.48

1:29 2% 1:3

EX ROW PR ROW

ALL UNITS IN SQ FT STAGE I
EARTH EXCAVATION= 0.00
EMBANKMENT= 29.60
UNS MTL (TOPSOIL EXC)= 9.57

84+00.00

℄ WALKUP RD

STAGE I

927.78 928.16 928.01 927.81

1:32 2% 1:3

EX ROW PR ROW

ALL UNITS IN SQ FT STAGE I
EARTH EXCAVATION= 0.00
EMBANKMENT= 28.44
UNS MTL (TOPSOIL EXC)= 10.06

83+00.00

℄ WALKUP RD

STAGE I

EX ROW

928.06 928.44 928.24 928.04

1:18 2% 1:3

EX ROW PR ROW

ALL UNITS IN SQ FT STAGE I
EARTH EXCAVATION= 0.00
EMBANKMENT= 21.98
UNS MTL (TOPSOIL EXC)= 9.68

82+00.00

℄ WALKUP RD

STAGE I

BURNING BUSH TRAIL

EX ROW

ALL UNITS IN SQ FT STAGE I
EARTH EXCAVATION= 0.00
EMBANKMENT= 0.00
UNS MTL (TOPSOIL EXC)= 0.00

81+00.00

℄ WALKUP RD

STAGE I

EX ROW

927.92 928.30 928.08 927.88

1:24.6 2% 1:3

EX ROW PR ROW

ALL UNITS IN SQ FT STAGE I
EARTH EXCAVATION= 0.03
EMBANKMENT= 12.61
UNS MTL (TOPSOIL EXC)= 13.00

80+00.00

PROPOSED CROSS-SECTIONS: WALKUP ROAD

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6085	00-00246-01-FP	MCHENRY	236	193
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
STA.	TO STA.	CONTRACT NO: 62266		