

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2967	09-00018-00-RS	WILL.	10	3
STA.		TO STA.		
ARA-9003 (431)		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 63328				

SUMMARY OF QUANTITIES

SPECIAL PROVISION	ITEM NO.	DESCRIPTION	UNIT	CONSTRUCTION CODE
				1000 TOTAL QUANTITY
	21101615	TOPSOIL FURNISH AND PLACE - 4"	SY YD	4400
	25000210	SEEDING CLASS 2A	ACRE	0.9
	25100105	MULCH METHOD 1	ACRE	0.9
	28000400	PERIMETER EROSION BARRIER	FOOT	400
	28000500	INLET AND PIPE PROTECTION	EACH	5
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	4200
	40600300	AGGREGATE PRIME COAT	TON	24
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2500
	40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	720
	40600982	HOT-MIX SURFACE REMOVAL, BUTT JOINT	SY YD	1200
	44201705	CLASS D PATCH, TYPE II - 5"	SQ YD	300
	44201709	CLASS D PATCH, TYPE III - 5"	SQ YD	300
	44201711	CLASS D PATCH, TYPE IV - 5"	SQ YD	300
	44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	15600
	48101200	AGGREGATE SHOULDERS TYPE B	TON	1100
	67100100	MOBILIZATION	L SUM	1
	70102620	TRAFFIC CONTROL AND PROTECTION STD. 701501	L SUM	1
	70102635	TRAFFIC CONTROL AND PROTECTION STD. 701701	L SUM	1
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6
	70300210	TEMPORARY PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	10
	70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	4000
	70300240	TEMPORARY PAVEMENT MARKING-LINE 6"	FOOT	300
	70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	10
	70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	400
Δ	78000100	THERMOPLASTIC PVMT. MKG. - LETTERS & SYMBOLS	SQ FT	150
Δ	78000200	THERMOPLASTIC PVMT. MKG. - LINE 4"	FOOT	14800
Δ	78000400	THERMOPLASTIC PVMT. MKG. - LINE 6"	FOOT	500
Δ	78000600	THERMOPLASTIC PVMT. MKG. - LINE 12"	FOOT	100
Δ	78000650	THERMOPLASTIC PVMT. MKG. - LINE 24"	FOOT	130
Δ	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	70

Δ = SPECIALTY ITEM

INDEX OF STANDARDS

606001-04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
701006-03	OFF-RD OPERATIONS, 2L, 2W, 15' (4.5 M) TO 24' (600 MM) FROM PAVEMENT EDGE
701301-03	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701501-05	URBAN LANE CLOSURE, 2L, 2W UNDIVIDED
701701-06	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701901-01	TRAFFIC CONTROL DEVICES
780001-02	TYPICAL PAVEMENT MARKINGS
280001-05	TEMPORARY EROSION CONTROL SYSTEMS
442201-03	CLASS C AND D PATCHES
635001-01	DELINEATORS
720001-01	SIGN PANEL MOUNT DETAILS
720006-02	SIGN PANEL ERECT DETAILS
720011-01	METAL POSTS FOR SIGNS, MARKERS, AND DELINEATORS

REVISIONS	
NAME	DATE

VILLAGE OF UNIVERSITY PARK
UNIVERSITY PARK, IL
UNIVERSITY PARKWAY RESURFACING
CRAWFORD AVENUE TO STEGER-MONEE ROAD

SUMMARY OF QUANTITIES

SCALE: VERT. NA
HORIZ. NA
DATE: OCTOBER, 2009

DRAWN BY: CMH
CHECKED BY: JSK

