

	PAY CODE	DESCRIPTION	UNIT	QUANTITY	Y047	Y003	X932-2A
+	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	50	---	50	---
+	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	50	---	50	---
	20100500	TREE REMOVAL, ACRES	ACRE	1.00	---	1.00	---
	20101000	TEMPORARY FENCE	FOOT	1000	---	1000	---
	20101200	TREE ROOT PRUNING	EACH	13	---	13	---
	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	7	---	7	---
	20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	6	---	6	---
	20200100	EARTH EXCAVATION	CU YD	460	460	---	---
+	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	40	40	---	---
	20800250	TRENCH BACKFILL, SPECIAL	CU YD	15	---	---	15
+	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	120	120	---	---
	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	2014	---	2014	---
+	21301084	EXPLORATION TRENCH 84" DEPTH	FOOT	100	100	---	---
	25000110	SEEDING, CLASS 1A	ACRE	0.09	---	0.09	---
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	10	---	10	---
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	10	---	10	---
	25100630	EROSION CONTROL BLANKET	SQ YD	2824	---	2824	---
	25100800	EROSION CONTROL MAT	SQ YD	150	---	150	---
+	25200200	SUPPLEMENTAL WATERING	UNIT	85	---	85	---
+	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	59	---	59	---
	28000400	PERIMETER EROSION BARRIER	FOOT	1053	---	1053	---
+	28000510	INLET FILTERS	EACH	2	---	2	---
	28100105	STONE RIPRAP, CLASS A3	SQ YD	15	---	---	15
	28200200	FILTER FABRIC	SQ YD	15	---	---	15
	35100120	AGGREGATE BASE COURSE, TYPE A 2"	SQ YD	46	46	---	---
	35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	528	528	---	---
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	257	257	---	---
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	80	80	---	---
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	129	129	---	---
	42001300	PROTECTIVE COAT	SQ YD	144	144	---	---
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	413	413	---	---
	42400800	DETECTABLE WARNINGS	SQ FT	35	35	---	---
	48101800	AGGREGATE SHOULDERS (SPECIAL)	SQ YD	4	4	---	---
	50200510	COFFERDAMS (SPECIAL)	EACH	2	2	---	---
	50300225	CONCRETE STRUCTURES	CU YD	47.6	---	---	47.6
	50300300	PROTECTIVE COAT	SQ YD	200	---	---	200
	50800105	REINFORCEMENT BARS	POUND	12950	---	---	12950
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7300	---	---	7300
	51603000	DRILLED SHAFT IN SOIL	CU YD	109	---	---	109
	54213870	STEEL END SECTIONS 15"	EACH	4	---	---	4

	PAY CODE	DESCRIPTION	UNIT	QUANTITY	Y047	Y003	X932-2A
	550B0070	STORM SEWERS, CLASS B, TYPE 1 15"	FOOT	54	---	---	54
+	* 56106600	ADJUSTING WATER MAIN 12"	FOOT	40	---	---	40
+	* 56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	150	---	---	150
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	425	425	---	---
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	---	---
	67100100	MOBILIZATION	L SUM	1	1	---	---
	70101900	TRAFFIC CONTROL AND PROTECTION (DETOUR 1)	L SUM	1	1	---	---
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	---	---
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	---	---
	* 70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	---	---
	70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	1510	1510	---	---
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	630	630	---	---
	70400100	TEMPORARY CONCRETE BARRIER	FOOT	325	325	---	---
	72000100	SIGN PANEL - TYPE 1	SQ FT	12	12	---	---
	72900200	METAL POST - TYPE B	FOOT	24	24	---	---
	* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	491	491	---	---
	* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	1170	1170	---	---
	* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	48	48	---	---
	* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	12	12	---	---
	78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	28	28	---	---
	X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	1	---	---	1
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	42	42	---	---
	* X0322508	PEDESTRIAN TRUSS SUPERSTRUCTURE	SQ FT	4084	---	---	4084
	X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	259	259	---	---
	X0426200	DEWATERING	L SUM	1	---	---	1
+	XX008290	TEMPORARY DITCH CHECKS, SPECIAL	EACH	9	9	---	---
	XX005913	TEMPORARY ACCESS CAUSEWAY	L SUM	1	1	---	---
+	XX006522	FURNISH WITNESS POST	EACH	2	2	---	---
+	XX006658	FLOCCULATION LOGS	EACH	5	---	5	---
+	XX006659	FLOCCULATION POWDER	POUND	50	---	50	---
	XX006701	SEEDING, CLASS 4 (MODIFIED) MESIC PRAIRIE	ACRE	0.20	---	0.20	---
	XX006702	SEEDING, CLASS 4 (MODIFIED) WET TO MESIC PRAIRIE	ACRE	0.29	---	0.29	---
	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	480	480	---	---
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	---	---
+	Z0019600	DUST CONTROL WATERING	UNIT	5	5	---	---
	Z0030250	IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	3	3	---	---
	Δ Z0076600	TRAINEES	HOURL	500	500	---	---
	Z0077700	WOOD FENCE TO BE REMOVED AND RE-ERECTED	FOOT	35	35	---	---
	* XX008287	BOARDWALK STRUCTURE	SQ FT	7271	---	---	7271
	XX008288	SEDIMENT COLLECTION CHAMBER SYSTEM, TEMPORARY	EACH	2	2	---	---