

SUMMARY OF QUANTITIES CONT.

| CODE NUMBER | PAY ITEM | UNIT | TOTAL QUANTITY | ROADWAY 1000 | NON-PARTICIPATING |
|-------------|--|-------|----------------|--------------|-------------------|
| 40600990 | TEMPORARY RAMP | SQ YD | 357 | 357 | - |
| 40603080 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 | TON | 48 | 48 | - |
| 40603085 | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 | TON | 4,794 | 4,794 | - |
| 40603310 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON | 119 | 119 | - |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 3,944 | 3,944 | - |
| 42001300 | PROTECTIVE COAT | SQ YD | 2,955 | 2,955 | - |
| 42300200 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH | SQ YD | 178 | 178 | - |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SQ YD | 471 | 471 | - |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SQ FT | 13,000 | 13,000 | - |
| 42400800 | DETECTABLE WARNINGS | SQ FT | 866 | 866 | - |
| 44000157 | HOT-MIX ASPHALT SURFACE REMOVAL, 2" | SQ YD | 3,135 | 3,135 | - |
| 44000167 | HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/2" | SQ YD | 30,305 | 30,305 | - |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 2,100 | 2,100 | - |
| 44000300 | CURB REMOVAL | FOOT | 120 | 120 | - |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 12,395 | 12,395 | - |
| 44001700 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 10,000 | 10,000 | - |
| 44003100 | MEDIAN REMOVAL | SQ FT | 1,900 | 1,900 | - |
| 44201737 | CLASS D PATCHES, TYPE I, 8 INCH | SQ YD | 190 | 190 | - |
| 44201741 | CLASS D PATCHES, TYPE II, 8 INCH | SQ YD | 439 | 439 | - |
| 44201745 | CLASS D PATCHES, TYPE III, 8 INCH | SQ YD | 1,353 | 1,353 | - |
| 44201747 | CLASS D PATCHES, TYPE IV, 8 INCH | SQ YD | 5,800 | 5,800 | - |
| 44201785 | CLASS D PATCHES, TYPE I, 12 INCH | SQ YD | 10 | 10 | - |
| 44201789 | CLASS D PATCHES, TYPE II, 12 INCH | SQ YD | 20 | 20 | - |
| 44201794 | CLASS D PATCHES, TYPE III, 12 INCH | SQ YD | 40 | 40 | - |
| 44201796 | CLASS D PATCHES, TYPE IV, 12 INCH | SQ YD | 100 | 100 | - |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 2 | 2 | - |
| 550A0030 | STORM SEWERS, CLASS A, TYPE 1 8" | FOOT | 111 | 111 | - |
| 550A0040 | STORM SEWERS, CLASS A, TYPE 1 10" | FOOT | 65 | 65 | - |
| 550A0050 | STORM SEWERS, CLASS A, TYPE 1 12" | FOOT | 90 | 90 | - |
| 550A0340 | STORM SEWERS, CLASS A, TYPE 2 12" | FOOT | 416 | 416 | - |

* INDICATES SPECIALTY ITEM

I:\ADDINA\070142-ARMY TRAIL-MILL LAPP & WATER MAIN\CADD-SURVEY\DRAWINGS\DWGS\070142-SMK-QTY.DWG 06
 Plotted: 12/10/2009 6:12 AM by: 23106B
 Copyright © 2009, by Baxter Woodman, Inc.
 State of Illinois Professional Engineer License No. 184-001121 - Expires 4-30-11



| | |
|----------------|-----------------------------------|
| DESIGNED - MWP | REVISED - VILLAGE REVIEW 9-08-09 |
| DRAWN - UKB | REVISED - VILLAGE REVIEW 11-05-09 |
| CHECKED - RWL | REVISED - IDOT REVIEW 11-17-09 |
| DATE - 8-19-09 | REVISED - VILLAGE REVIEW 12-07-09 |

**VILLAGE OF ADDISON, ILLINOIS
MILL ROAD AND ARMY TRAIL BOULEVARD
STP IMPROVEMENTS**

SUMMARY OF QUANTITIES

SCALE: PROJECT NO: 070142 STA. TO STA.

*3884 ARMY TRAIL BLVD.
*2625 MILL ROAD

| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|-----------------------|----------------|--|--------------|-----------|
| * | 09-00098-00-RS | DuPage | 69 | 6 |
| C-91-056-10 | | CONTRACT NO. 63427 | | |
| FED. ROAD DIST. NO. 1 | | ILLINOIS FED. AID PROJECT M-9003 (474) | | |