

**SUMMARY OF QUANTITIES CONT.**

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000	NON-PARTICIPATING
* XX003542	DUCTILE IRON WATER MAIN FITTINGS 6" 45 DEGREE BEND	EACH	7	-	7
* XX003543	DUCTILE IRON WATER MAIN FITTINGS 8" 45 DEGREE BEND	EACH	25	-	25
* XX003673	SANITARY SERVICE REPLACEMENT	EACH	8	-	8
* XX003778	FLUOROCARBON RUBBER (VITON) GASKET	EACH	10	-	10
* XX004997	WATER SERVICE CONNECTION 2"	EACH	3	-	3
* XX005003	DUCTILE IRON WATER MAIN FITTING 10" X 6" TEE	EACH	6	-	6
* XX005004	DUCTILE IRON WATER MAIN FITTING 10" X 6" HYDRANT TEE	EACH	3	-	3
* XX005005	DUCTILE IRON WATER MAIN FITTING 10" X 8" TEE	EACH	5	-	5
* XX005010	DUCTILE IRON WATER MAIN FITTING - 4" X 6" REDUCER	EACH	1	-	1
XX005221	TOPSOIL FURNISH AND PLACE (PULVERIZED) VARIABLE DEPTH	SQ YD	3,700	3,700	-
* XX005477	DUCTILE IRON WATER MAIN 4" RESTRAINED JOINT TYPE	FOOT	30	-	30
* XX005478	DUCTILE IRON WATER MAIN 6" RESTRAINED JOINT TYPE	FOOT	300	-	300
* 60249125	VALVE VAULTS, 6' DIAMETER	EACH	1	-	1
* XX006878	DUCTILE IRON SOLID SLEEVE 4"	EACH	3	-	3
* XX006879	DUCTILE IRON SOLID SLEEVE 6"	EACH	7	-	7
* XX007220	PVC CASING PIPE 20"	FOOT	110	-	110
X0320591	SANITARY MANHOLES TO BE REMOVED	EACH	1	1	-
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	8	8	-
X0322032	STORM SEWER (WATER MAIN REQUIREMENTS) 10 INCH	FOOT	376	376	-
X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	461	461	-
X0322124	STORM SEWER (WATER MAIN REQUIREMENTS) 8 INCH	FOOT	17	17	-
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	364	364	-
* X0323820	DUCTILE IRON WATER MAIN TEE, 8" X 8"	EACH	10	-	10
* X0323821	DUCTILE IRON WATER MAIN REDUCER, 10" X 8"	EACH	1	-	1
* X0324445	DUCTILE IRON WATER MAIN FITTINGS 8" 22.5 DEGREE BEND	EACH	2	-	2

\* INDICATES SPECIALTY ITEM

I:\ADDON\070142-ARMY TRAIL-MILL LAPP & WATER MAIN\CADD-SURVEY\DRAWINGS\DWGS\070142-SMK-0TY.DWG 10  
 Plotter: 12/10/2009 8:19 AM By: Z3TURK  
 Copyright © 2009 by Baxter & Woodman, Inc.  
 State of Illinois 184-001121 - Expires 4-30-11  
 License No.



DESIGNED - MWP	REVISED - VILLAGE REVIEW 9-08-09
DRAWN - UKB	REVISED - VILLAGE REVIEW 11-05-09
CHECKED - RWL	REVISED - IDOT REVIEW 11-17-09
DATE - 8-19-09	REVISED - VILLAGE REVIEW 12-07-09

**VILLAGE OF ADDISON, ILLINOIS  
MILL ROAD AND ARMY TRAIL BOULEVARD  
STP IMPROVEMENTS**

<b>SUMMARY OF QUANTITIES</b>	
SCALE:	PROJECT NO: 070142 STA. TO STA.

\*3884 ARMY TRAIL BLVD.  
\*2825 MILL ROAD

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	09-00098-00-RS	DuPage	69	10
C-91-056-10		CONTRACT NO. 63427		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT M-9003 (474)	