



WHITEHALL AVENUE

WOLF ROAD

ADDISON CREEK

LEGEND:

- PAVEMENT REMOVAL
- EXISTING PAVEMENT SURFACE OVER BRIDGE DECK AND SIDEWALK TO BE REMOVED
- HOT-MIX ASPHALT SURFACE REMOVAL, 2"
- SIDEWALK REMOVAL
- CONCRETE CURB AND GUTTER REMOVAL
- FENCE REMOVAL (PAID FOR AS CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED)

NOTES:

1. CONTRACTOR SHALL DISCONNECT AND CUT EXISTING TRAFFIC SIGNAL CABLES AND CONDUIT TO A MINIMUM OF 1' BELOW GRADE AND ABANDON. CONTRACTOR MAY ELECT TO REMOVE CABLES AND SALVAGE AT NO ADDITIONAL COST TO THE OWNER. WORK INCLUDED IN COST FOR REMOVING HANDHOLE.
2. EXISTING CONCRETE HANDHOLE SHALL BE REMOVED AND DISPOSED OF ACCORDING TO SECTION 895 IN THE STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION, LATEST EDITION. THE HANDHOLE SHALL BE COMPLETELY REMOVED, BACKFILLED WITH IDOT APPROVED MATERIAL AND THE SURFACE RESTORED TO SURROUNDING CONDITIONS.

FILE NAME =
N:\NDRTHLAKE\940032HR204\Civil\From_940032hr204.sht

USER NAME = PRAZALAN
DRAWN - EDT
CHECKED - MEW
PLOT SCALE = 10'
PLOT DATE = 11/30/2009

DESIGNED - AMP
DRAWN - EDT
CHECKED - MEW
DATE - 09/30/09

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**EXISTING CONDITIONS AND REMOVAL PLAN
WHITEHALL AVENUE**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
---	09-00071-00-BR	COOK	31	7
CONTRACT NO. 63437				

ILLINOIS FED. AID PROJECT