

SUMMARY OF QUANTITIES			TOTAL QUANTITY	ROADWAY QUANTITY	BRIDGE QUANTITY
			URBAN	1000	X271-2A
CODE	ITEM	UNIT	80% FED.	20% STATE	80% FED.
20200100	EARTH EXCAVATION	CU YD	145	145	
20400800	FURNISHED EXCAVATION	CU YD	1,030	1,030	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	130		130
25000210	SEEDING, CLASS 2A	ACRE	0.9	0.9	
25000750	MOWING	ACRE	1	1	
25100850	EROSION CONTROL BLANKET	SQ YD	3,961	3,961	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	327	327	
28000400	PERIMETER EROSION BARRIER	FOOT	1,288	1,288	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	177	177	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	160	160	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	14	14	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	61	61	
40603940	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	90	90	
42701165	BRIDGE APPROACH PAVEMENT	SQ YD	214	214	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	43	43	
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	99	99	
44000700	APPROACH SLAB REMOVAL	SQ YD	213	213	
44201403	CLASS C PATCHES, TYPE II, 14 INCH	SQ YD	16	16	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	640	640	
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SQ YD	660	660	
50101800	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1
50102400	CONCRETE REMOVAL	CU YD	31.2		31.2
50104650	SLOPE WALL REMOVAL	SQ YD	365		365
50157300	PROTECTIVE SHIELD	SQ YD	458		458
50200100	STRUCTURE EXCAVATION	CU YD	157		157
50300225	CONCRETE STRUCTURES	CU YD	64.6		64.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	246.0		246.0
50300250	BRIDGE DECK GROOVING	SQ YD	690		690
50300300	PROTECTIVE COAT	SQ YD	926		926

SUMMARY OF QUANTITIES			TOTAL QUANTITY	ROADWAY QUANTITY	BRIDGE QUANTITY
			URBAN	1000	X271-2A
CODE	ITEM	UNIT	80% FED.	20% STATE	80% FED.
50500305	ERECTIN'S STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	4,860		4,860
50800515	BAR SPLICERS	EACH	68		68
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	71,980		71,980
51100100	SLOPE WALL, 4 INCH	SQ YD	421		421
51500100	NAME PLATES	EACH	2		2
52000110	PREFORMED JOINT STRIP SEAL	FOOT	71		71
52100210	ERECTIN'S ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12		12
52100220	ERECTIN'S ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12		12
52100520	ANCHOR BOLTS, 1"	EACH	36		36
52100540	ANCHOR BOLTS, 1 1/2"	EACH	24		24
58700300	CONCRETE SEALER	SQ FT	507		507
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	59		59
60109560	PIPE UNDERDRAINS FOR STRUCTURES, 4"	FOOT	156		156
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	387.5	387.5	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	918	918	
63500105	DELINEATORS	EACH	4	4	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	3	3	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	4	4
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	4	4	
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2	2	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	466		466
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7,748		7,748

SUMMARY OF QUANTITIES			TOTAL QUANTITY	ROADWAY QUANTITY	BRIDGE QUANTITY
			URBAN	1000	X271-2A
CODE	ITEM	UNIT	80% FED.	20% STATE	80% FED.
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,916		2,916
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	5,280		3,600
70400100	TEMPORARY CONCRETE BARRIER	FOOT	412.5		412.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	412.5		412.5
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6		6
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4		4
78200410	GUARDRAIL MARKERS, TYPE A	EACH	15		15
78200520	BARRIER WALL MARKERS, TYPE B	EACH	8		8
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4		4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,901		2,901
81603035	UNIT DUCT, 600V, 2-1C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	261		261
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	154		154
83800355	LIGHT POLE FOUNDATION (METAL), 15" BOLT CIRCLE, 8" x 6"	EACH	2		2
84200807	REMOVAL OF POLE FOUNDATION, METAL	EACH	2		2
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2		2
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5
X0323830	DRAINAGE SCUFFERS, DS-11	EACH	2		2
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1		1
84200500	REMOVAL OF LIGHTING UNIT, SAVAGE	EACH	2		2
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2

NON-PARTICIPATING  
100% STATE

DESIGNED AAF  
DRAWN AAF  
CHECKED AAF  
DATE 2/02/09

DESIGNED AAF  
DRAWN AAF  
CHECKED AAF  
DATE 2/02/09

REVISED  
REVISED  
REVISED  
REVISED

\* SPECIALTY ITEMS

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

MIAMI JIAN ROAD  
SUMMARY OF QUANTITIES

NONE SHEETS 11 SHEETS 1 STA

HOH		2945	
F.A.P. R.T.E.	SECTION	COUNTY	TOTAL SHEETS
301	1-HOR-2	WINNEBAGO	57
CONTRACT NO		G4D50	
FED. ROAD DIST. NO.		ILLINOIS FED. PROJECT	