SUMMARY OF QUANTITES

CODE NUMBER	ITEM	UNITS	TOTAL QUANTITY	90% FED 10% STATE J000
	EXISTING			
20200600	EXCAVATING AND GRADING SHOULDER	UNIT	3940	3940
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	540	540
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	152	152
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	8253	8253
44213000	PATCHING REINFORCEMENT	SQ YD	8945	8945
44213200	SAW CUTS	FOOT	29680	29680
48100100	AGGREGATE SHOULDERS, TYPE A	TON	60,015	60,015
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SQ YD	336,126	336,126
63500205	REMOVING AND REPLACING DELINEATORS	EACH	650	650
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10
67100100	MOBILIZATION	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	16	16
70103815	TRAFFIC CONTROL AND PROTECTION SURVEILLANCE	CAL DA	85	85
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	105600	105600
* 78001140	PAINT PAVEMENT MARKING LINE - 8"	FOOT	11500	11500
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	250	250
⚠ Z0005400	BREAKER-RUN CRUSHED STONE	TON	1784	1784
X0326764	COLD MILLING (SPECIAL)	SQ YD	336,126	336,126
⚠ 31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	1364	1364
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
⚠ X0325519	DRAIN FOR AGGREGATE BASE COURSE	SQ YD	385	385
Z0075300	TIE BARS	EACH	5892	5892

* SPECIALTY ITEM

⚠ Rev. 2-16-10

FILE NAME =	USER NAME = dossdd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-39 SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw_work\PWIDOT\DOSSDD\d0162099\D202210-sht-cover.dgn		DRAWN -	REVISED -			39	(103-1, 103-2)SHLD	LEE	60	4
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -					CONTRACT NO. 64F82		
	PLOT DATE = Wed Oct 21 13:11:42 2009	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT		