

PATCHING SCHEDULE

LOCATION	REMARKS	44200553		44200557		44200559		44213000		44213200		Z0075300		Z0005400		31100300		X0325519				
		LENGTH	WIDTH		CLASS A PATCHES		CLASS A PATCHES		CLASS A PATCHES		PATCHING REINFORCEMENT		SAW CUTS		TIE BARS		12" BREAKER-RUN CRUSHED STONE		SUB-BASE GRAN MATERIAL TY A 4"		DRAIN FOR AGG BSE COURSE	
			FT	FT	FT	TYPE II, 10 INCH	SQ YD	TYPE III, 10 INCH	SQ YD	TYPE IV, 10 INCH	SQ YD	SQ YD	FOOT	FOOT	EACH	EACH	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD
STA TO STA			INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE
South Bound																						
820 + 0 - 820 + 30	Patch 1/2 Lane Long. Crack	30	6	6			20				20		84		16		7.1		5.8		2.3	
820 + 50 - 820 + 80	Patch 1/2 Lane Long. Crack	30	6	6			20	20			20	20	84	84	16	16	7.1	8.1	5.8	5.8	2.3	2.3
821 + 50 - 824 + 0	Patch 1/2 Lane Long. Crack	250	6	6						167		167		524		126		68.3		54.7		14.0
825 + 60 - 827 + 0	Patch 1/2 Lane Long. Crack	140	6	6					93		93		304		71		35.7		30.2		9.3	
826 + 90 - 828 + 50	Patch 1/2 Lane Long. Crack	160	6	6						107		107		344		81		43.8		34.7		9.3
828 + 50 - 830 + 0	Patch 1/2 Lane Long. Crack	150	6	6						100		100		324		76		41.6		32.4		9.3
934 + 90 - 934 + 96		6	12	12		8						8		60								
951 + 60 - 951 + 66		6	12	12		8						8		60								
960 + 70 - 960 + 76		6	12	12		8						8		60								
969 + 0 - 969 + 20		20	12	12					27		27		88		11							
979 + 0 - 979 + 6		6	12	12		8						8		60								
985 + 70 - 985 + 76		6	12	12	8					8		8		60								
987 + 90 - 987 + 96		6	12	12		8						8		60								
993 + 80 - 993 + 86		6	12	12		8						8		60								
994 + 80 - 994 + 86		6	12	12		8						8		60								
1000 + 10 - 1000 + 16		6	12	12		8						8		60								
1009 + 0 - 1009 + 10		10	12	12		13						13		68								
1040 + 30 - 1040 + 50		20	12	12					27		27		88		11							
1040 + 90 - 1040 + 96		6	12	12		8						8		60								
1050 + 40 - 1050 + 60		20	12	12					27		27		88		11							
1052 + 10 - 1052 + 16		6	12	12		8						8		60								
1071 + 60 - 1071 + 66		6	12	12	8						8		60									
1071 + 80 - 1071 + 86		6	12	12		8						8		60								
1072 + 50 - 1072 + 56		6	12	12		8						8		60								

NOTE: STATIONS ARE APPROXIMATE AND ARE SUBJECT TO CHANGE BY THE RE/TE

FILE NAME =	USER NAME = stringerjm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-39 PATCHING SCHEDULE	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pwork\PIWIDOT\STRINGERJM\0162099\202110-shr-schedule.dgn	202110-shr-schedule.dgn	DRAWN -	REVISED -			39	*	LEE	60	16	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	REVISED -			CONTRACT NO. 64F82					
PLOT DATE = Tue Feb 16 11:21:49 2010	DATE -	REVISED -	REVISED -			ILLINOIS FED. AID PROJECT					