

SHOULDER SCHEDULE

LOCATION	REMARKS	SHOULDERS			Z0010800		20200600		48100100		48300300		63500205
		LENGTH	WIDTH		COLD MILLING (SPECIAL)	EXCAVATING AND GRADING EXISTING SHOULDER	AGGREGATE SHOULDERS, TYPE A		PCC SHOULDERS 8"		REMAND REPLACING DELINEATORS		
			FT	FT			FT	SQ YD	UNIT	TON		SQ YD	EACH
STA TO STA			INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	OUTSIDE
North Bound													
320 + 50 - 338 + 84	LaSalle County	1833.9	6	10	1223	2038	18	18	326	234	1223	2038	6
338 + 84 - 496 + 11		15727.1	6	10	10485	17475	157	157	2794	2006	10485	17475	40
496 + 11 - 499 + 21	Shoulder omission	310	6	10									
499 + 21 - 605 + 68		10647	6	10	7098	11830	106	106	1892	1358	7098	11830	28
605 + 68 - 608 + 68	Chicago Rd - Ramp	300.3	6	6 & Var	200	232	3	3	53	38	200	232	4
608 + 68 - 612 + 36	Chicago Rd - Ramp	367.65	6	6	245	248	4	4	65	47	245	248	5
612 + 36 - 638 + 66		2629.65	6	10	1753	2922	26	26	467	335	1753	2922	8
638 + 66 - 642 + 83	Chicago Rd - Ramp & Gore	417.7	6	6	278	479	4	4	74	53	278	479	5
642 + 83 - 650 + 0	Chicago Rd - Ramp	716.7	6	6 & Var	478	512	7	7	127	91	478	512	8
650 + 0 - 713 + 16		6316	6	10	4211	7018	63	63	1122	806	4211	7018	17
713 + 16 - 720 + 72	Shoulder omission	756.4	6	10									3
720 + 72 - 732 + 96	Omit outside Conc Shldr	1223.3	6	10	816		12		217		816		4
732 + 96 - 752 + 24		1927.85	6	10	1285	2142	19	19	343	246	1285	2142	6
752 + 24 - 769 + 35	Omit outside Conc Shldr	1711.45	6	10									5
769 + 35 - 856 + 22		8686.7	6	10	5791	9652	87	87	1543	1108	5791	9652	23
856 + 22 - 862 + 81	US 30 - Ramp	659.3	6	6 & Var	440	475	7	7	117	84	440	475	8
862 + 81 - 862 + 97	US 30 - Ramp	15.9	6	6	11	11	0	0	3	2	11	11	1
862 + 97 - 876 + 9		1311.9	6	10	875	1458	13	13	233	167	875	1458	4
876 + 9 - 876 + 21	Approach Shldr Omission	12	6	10									
876 + 21 - 877 + 96	US 30 Bridge Omission	174.9	6	10									

FILE NAME =	USER NAME = dowsdd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				I-39 SHOULDER SCHEDULE				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct\pwr_work\PWIDOT\DOSSDD\0162099\020210-ah-t-schedule.dgn		DRAWN -	REVISED -					39	*	LEE	60	6				
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -					SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 64F82				
PLOT DATE = Wed Dec 30 15:20:42 2009		DATE -	REVISED -					ILLINOIS FED. AID PROJECT • (103-1, 103-2)SHLD								