

PATCHING SCHEDULE

LOCATION	REMARKS	44200553			44200557		44200559		44213000		44213200		Z0075300	
		CLASS A PATCHES			CLASS A PATCHES		CLASS A PATCHES		PATCHING REINFORCEMENT		SAW CUTS		TIE BARS	
		TYPE II, 10 INCH			TYPE III, 10 INCH		TYPE IV, 10 INCH							
		STA TO STA	LENGTH	WIDTH		SQ YD		SQ YD		SQ YD		SQ YD		FOOT
North Bound	FT	FT	FT	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	
665 + 50 - 665 + 56		6	12	12		8				8		60		
691 + 50 - 691 + 58	Patch 1/2 Lane Long. Crack	8	6	6		5				5		40		
693 + 0 - 694 + 0	Patch 1/2 Lane Long. Crack	100	6	6					67	67		224		51
700 + 50 - 703 + 30	Patch 1/2 Lane Long. Crack	280	6	6					187	187		584		141
705 + 50 - 706 + 50	Patch 1/2 Lane Long. Crack	100	6	6					67	67		224		51
707 + 50 - 709 + 50	Patch 1/2 Lane Long. Crack	200	6	6					133	133		424		101
710 + 0 - 713 + 0	Patch 1/2 Lane Long. Crack	300	6	6					200	200		624		151
723 + 50 - 727 + 50	Patch 1/2 Lane Long. Crack	400	6	6					267	267		824		201
727 + 80 - 728 + 80	Patch 1/2 Lane Long. Crack	100	6	6					67	67		224		51
729 + 0 - 733 + 0	Patch 1/2 Lane Long. Crack	400	6	6					267	267		824		201
751 + 75 - 757 + 0	Patch 1/2 Lane Long. Crack	525	6	6					350	350		1074		264
751 + 75 - 757 + 0	REST AREA - RAMP	525	6	6					350	350		1074		264
757 + 60 - 758 + 0		40	12	12					53	53		128		21
759 + 0 - 759 + 80		80	12	12					107	107		208		41
762 0 - 762 + 80		80	12	12					107	107		208		41
774 60 - 775 + 0		40	12	12					53	53		128		21
777 90 - 778 + 0		10	12	12		13				13		68		
788 50 - 788 + 56		6	12	12		8				8		60		
788 75 - 789 + 15		40	12	12					53	53		128		21
800 20 - 800 + 26		6	12	12		8				8		60		
839 20 - 839 + 26		6	12	12		8				8		60		
845 80 - 846 + 20		40	12	12					53	53		128		21
846 80 - 847 + 20		40	12	12					53	53		128		21
848 0 - 848 + 50		50	12	12					67	67		148		26

NOTE: STATIONS ARE APPROXIMATE AND ARE SUBJECT TO CHANGE BY THE RE/TE

FILE NAME =	USER NAME = dosadd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-39 PATCHING SCHEDULE	F.A.I. RTE. 39	SECTION *	COUNTY LEE	TOTAL SHEETS 60	SHEET NO. 12
cr\pw_work\PWIDOT\DOSSDD\0162099\02022\0-sh-t-schedule.dgn		DRAWN -	REVISED -							
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -							
	PLOT DATE = Mon Oct 19 11:49:00 2009	DATE -	REVISED -							
						SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 64F82	