

# PATCHING SCHEDULE

		44200553			44200557		44200559		44213000		44213200		Z0075300			
LOCATION	REMARKS				CLASS A PATCHES		CLASS A PATCHES		CLASS A PATCHES		PATCHING REINFORCEMENT		SAW CUTS		TIE BARS	
		STA TO STA	LENGTH	WIDTH		TYPE II, 10 INCH		TYPE III, 10 INCH		TYPE IV, 10 INCH						
FT				FT	FT	SQ YD		SQ YD		SQ YD		SQ YD		FOOT		EACH
North Bound			INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE
862 + 80 - 863 + 30		50	12	12						67		67		148		26
865 + 0 - 865 + 30		30	12	12						40		40		108		16
866 + 25 - 866 + 75		50	12	12						67		67		148		26
892 + 0 - 893 + 50	Patch 1/2 Lane Long. Crack	150	6	6						100		100		324		76
901 + 60 - 901 + 80		20	12	12						27		27		88		11
906 + 80 - 907 + 20		40	12	12						53		53		128		21
922 + 0 - 923 + 0	Patch 1/2 Lane Long. Crack	100	6	6						67		67		224		51
945 + 60 - 946 + 40	Patch 1/2 Lane Long. Crack	80	6	6						53		53		184		41
950 + 60 - 950 + 80		20	12	12						27		27		88		11
959 + 20 - 960 + 0	Patch 1/2 Lane Long. Crack	80	6	6						53		53		184		41
965 + 50 - 967 + 0	Patch 1/2 Lane Long. Crack	150	6	6						100		100		324		76
968 + 40 - 969 + 0	Patch 1/2 Lane Long. Crack	60	6	6						40		40		144		31
970 + 50 - 973 + 50	Patch 1/2 Lane Long. Crack	300	6	6						200		200		624		151
979 + 0 - 979 + 50		50	12	12						67		67		148		26
980 + 80 - 981 + 0		20	12	12						27		27		88		11
981 + 50 - 983 + 20	Patch 1/2 Lane Long. Crack	170	6	6						113		113		364		86
1197 + 30 - 1199 + 30	Perry Rd - Ramp Long Crack	200		6						133		133		424		101
1341 + 50 - 1341 + 56		6	12	12			8					8		60		
South Bound																
321 + 75 - 323 + 25	Patch 1/2 Lane Long. Crack	150	6	6						100		100		324		76
349 + 50 - 351 + 0	Patch 1/2 Lane Long. Crack	150	6	6						100		100		324		76
351 + 70 - 354 + 0	Patch 1/2 Lane Long. Crack	230	6	6						153		153		484		116
356 + 0 - 357 + 30	Patch 1/2 Lane Long. Crack	130	6	6						87		87		284		66

NOTE: STATIONS ARE APPROXIMATE AND ARE SUBJECT TO CHANGE BY THE RE/TE

FILE NAME =	USER NAME = d0ssdd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>I-39 PATCHING SCHEDULE</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca\p\work\FWIDOT\DOSSDD\d0162099\020210-shr-schedule.dgn		DRAWN -	REVISED -			39	*	LEE	60	13	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64F82					
PLOT DATE = Mon Oct 19 11:49:01 2009		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
						SCALE: SHEET NO. OF SHEETS STA. TO STA.					