

PATCHING SCHEDULE

		44200553			44200557		44200559		44213000		44213200		Z0075300			
LOCATION	REMARKS				CLASS A PATCHES		CLASS A PATCHES		CLASS A PATCHES		PATCHING REINFORCEMENT		SAW CUTS		TIE BARS	
		STA TO STA	LENGTH	WIDTH		TYPE II, 10 INCH		TYPE III, 10 INCH		TYPE IV, 10 INCH						
FT			FT	FT	SQ YD		SQ YD		SQ YD		SQ YD		FOOT		EACH	
South Bound			INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE
628 + 0 - 628 + 20	Patch 1/2 Lane Long. Crack	20	6	6		13						13		64		11
628 + 70 - 629 + 0	Patch 1/2 Lane Long. Crack	30	6	6				20				20		84		16
630 + 0 - 630 + 40	Patch 1/2 Lane Long. Crack	40	6	6						27		27		104		21
632 + 80 - 632 + 86		6	12	12		8						8		60		
639 + 60 - 640 + 40	Patch 1/2 Lane Long. Crack	80	6	6						53		53		184		41
647 + 0 - 647 + 50	Patch 1/2 Lane Long. Crack	50	6	6						33		33		124		26
653 + 50 - 653 + 70	Patch 1/2 Lane Long. Crack	20	6	6		13						13		64		11
654 + 0 - 655 + 0	Patch 1/2 Lane Long. Crack	100	6	6						67		67		224		51
655 + 50 - 658 + 0	Patch 1/2 Lane Long. Crack	250	6	6						167		167		524		126
665 + 90 - 665 + 96		6	12	12		8						8		60		
692 + 0 - 692 + 6		6	12	12		8						8		60		
712 + 0 - 714 + 0	Patch 1/2 Lane Long. Crack	200	6	6					133	133	133	133	424	424	101	101
727 + 0 - 727 + 80	Patch 1/2 Lane Long. Crack	80	6	6						53		53		184		41
730 + 30 - 730 + 40	Patch 1/2 Lane Long. Crack	10	6	6		7						7		44		
734 + 60 - 734 + 68		8	12	12		11						11		64		
736 + 30 - 736 + 40	Patch 1/2 Lane Long. Crack	10	6	6		7						7		44		
739 + 70 - 739 + 80	Patch 1/2 Lane Long. Crack	10	6	6		7						7		44		
742 + 0 - 744 + 0	Rest Area - Ramp	200	6	6						133		133		424		101
745 + 0 - 745 + 40		40	12	12						53		53		128		21
746 + 50 - 746 + 75		25	12	12						33		33		98		14
786 + 0 - 786 + 6		6	12	12		8						8		60		
815 + 0 - 817 + 0	Patch 1/2 Lane Long. Crack	200	6	6						133		133		424		101
817 + 50 - 818 + 50	Patch 1/2 Lane Long. Crack	100	6	6						67		67		224		51
819 + 0 - 819 + 60	Patch 1/2 Lane Long. Crack	60	6	6						40		40		144		31

NOTE: STATIONS ARE APPROXIMATE AND ARE SUBJECT TO CHANGE BY THE RE/TE

FILE NAME =	USER NAME = dosddd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-39 PATCHING SCHEDULE				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci\pwork\PWIDOT\DOSSDD\0162099\020210-shr-schedule.dgn		DRAWN -	REVISED -		39	*	LEE	60	15				
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 64F82				
PLOT DATE = Mon Oct 19 11:49:03 2009		DATE -	REVISED -		ILLINOIS FED. AID PROJECT								