

PATCHING SCHEDULE

LOCATION	REMARKS	44200553		44200557		44200559		44213000		44213200		Z0075300				
		CLASS A PATCHES		CLASS A PATCHES		CLASS A PATCHES		PATCHING REINFORCEMENT		SAW CUTS		TIE BARS				
		TYPE II, 10 INCH		TYPE III, 10 INCH		TYPE IV, 10 INCH		SQ YD		SQ YD		SQ YD		EACH		
		STA TO STA	LENGTH	WIDTH		SQ YD		SQ YD		SQ YD		FOOT		EACH		
South Bound		FT	FT	FT	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE		
820 + 0 - 820 + 30	Patch 1/2 Lane Long. Crack	30	6	6			20				20		84		16	
820 + 50 - 820 + 80	Patch 1/2 Lane Long. Crack	30	6	6			20	20			20	20	84	84	16	16
821 + 50 - 824 + 0	Patch 1/2 Lane Long. Crack	250	6	6						167		167		524		126
825 + 60 - 827 + 0	Patch 1/2 Lane Long. Crack	140	6	6					93		93		304		71	
826 + 90 - 828 + 50	Patch 1/2 Lane Long. Crack	160	6	6						107		107		344		81
828 + 50 - 830 + 0	Patch 1/2 Lane Long. Crack	150	6	6						100		100		324		76
934 + 90 - 934 + 96		6	12	12		8					8		60			
951 + 60 - 951 + 66		6	12	12		8					8		60			
960 + 70 - 960 + 76		6	12	12		8					8		60			
969 + 0 - 969 + 20		20	12	12						27		27		88	11	
979 + 0 - 979 + 6		6	12	12		8					8		60			
985 + 70 - 985 + 76		6	12	12	8						8		60			
987 + 90 - 987 + 96		6	12	12		8					8		60			
993 + 80 - 993 + 86		6	12	12		8					8		60			
994 + 80 - 994 + 86		6	12	12		8					8		60			
1000 + 10 - 1000 + 16		6	12	12		8					8		60			
1009 + 0 - 1009 + 10		10	12	12		13					13		68			
1040 + 30 - 1040 + 50		20	12	12						27		27		88		11
1040 + 90 - 1040 + 96		6	12	12		8					8		60			
1050 + 40 - 1050 + 60		20	12	12						27		27		88		11
1052 + 10 - 1052 + 16		6	12	12		8					8		60			
1071 + 60 - 1071 + 66		6	12	12	8						8		60			
1071 + 80 - 1071 + 86		6	12	12		8					8		60			
1072 + 50 - 1072 + 56		6	12	12		8					8		60			

NOTE: STATIONS ARE APPROXIMATE AND ARE SUBJECT TO CHANGE BY THE RE/TE

FILE NAME =	USER NAME = dosadd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-39 PATCHING SCHEDULE	SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	F.A.I. RTE. 39	SECTION *	COUNTY LEE	TOTAL SHEETS 60	SHEET NO. 16	
cr\pwork\PWIDOT\DOSSDD\0162099\02022\@-shtr-schedule.dgn		DRAWN -	REVISED -			CONTRACT NO. 64F82								
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			ILLINOIS FED. AID PROJECT								
PLOT DATE = Mon Oct 19 11:49:04 2009		DATE -	REVISED -			* (103-1, 103-2)SHLD								