

SUMMARY OF QUANTITIES				90% FED. 10% STATE		
CODE NO.	ITEM	CONSTRUCTION CODE TYPE:		1000-2A ROADWAY	SFTY-2A SN 050-2559	Y030-1E
		UNIT	TOTAL QUANTITY			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	12	12		
20200100	EARTH EXCAVATION	CU YD	1531	1531		
20400800	FURNISHED EXCAVATION	CU YD	659	659		
* 25000200	SEEDING, CLASS 2	ACRE	1.18	1.18		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	107	107		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	107	107		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	107	107		
* 25100115	MULCH, METHOD 2	ACRE	1.12	1.12		
* 25100630	EROSION CONTROL BLANKET	SQ YD	309	309		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	118	118		
28000305	TEMPORARY DITCH CHECKS	FOOT	184	184		
28000400	PERIMETER EROSION BARRIER	FOOT	111	111		
28100107	STONE RIPRAP, CLASS A4	SQ YD	219	219		
28200200	FILTER FABRIC	SQ YD	219	219		
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2086	2086		
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	1596	1596		
35400200	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 7"	SQ YD	247	247		
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	43	43		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	798	798		
40600300	AGGREGATE (PRIME COAT)	TON	12	12		
40600400	MIXTURE FOR JOINTS, CRACKS, AND FLANGEWAYS	TON	1	1		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	244	244		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	289	289		
40600990	TEMPORARY RAMP	SQ YD	114	114		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N70	TON	336	336		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX *D*, N70	TON	504	504		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	18	18		
42001200	PAVEMENT FABRIC	SQ YD	100	100		
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY, PAVEMENT 8 INCH	SQ YD	111	111		
44000100	PAVEMENT REMOVAL	SQ YD	26	26		
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	3116	3116		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	344	344		
44002805	ISLAND REMOVAL	SQ FT	146	146		
44200924	CLASS B PATCHES, TYPE III, 7 INCH	SQ YD	17	17		
44213200	SAW CUTS	FOOT	554	554		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	352	352		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2212	2212		

* SPECIALTY ITEMS

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
cs:\pw_work\PW\DOT\UNCANBD\dms31838\epd	2508-sht-details.DGN	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	311	(5)N	LASALLE	39	3
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -		CONTRACT NO. 66857										
	PLOT DATE = Dec 16, 2009 - 10:33:19 AM	DATE -	REVISED -		ILLINOIS FED. AID PROJECT										