

SUMMARY OF QUANTITIES				← 90% FED. 10% STATE →		
CODE NO.	ITEM	CONSTRUCTION CODE TYPE:		1000-2A ROADWAY	SFTY-2A SN 050-2559	Y030-1E
		UNIT	TOTAL QUANTITY			
48300410	PORTLAND CEMENT CONCRETE SHOULDERS 9 1/2"	SQ YD	14	14		
50102400	CONCRETE REMOVAL	CU YD	15.8		15.8	
50105220	PIPE CULVERT REMOVAL	FOOT	50	50		
50800105	REINFORCEMENT BARS	POUND	1210		1210	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	280		280	
54003000	CONCRETE BOX CULVERTS	CU YD	16.7		16.7	
54010606	PRECAST CONCRETE BOX CULVERT 6' X 6'	FOOT	16		16	
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	50	50		
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	2.5	2.5		
54213453	END SECTIONS 18"	EACH	2	2		
54213459	END SECTIONS 24"	EACH	1	1		
54248510	CONCRETE COLLAR	CU YD	3.2		3.2	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	1		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	92	92		
60625600	ISLAND PAVEMENT (6")	SQ YD	12	12		
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6' ^{FOOT} POSTS	FOOT	425	425		
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	12.5	12.5		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3		
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1	1		
63200310	GUARDRAIL REMOVAL	FOOT	557	557		
64200105	SHOULDER RUMBLE STRIP	FOOT	2212	2212		
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	69	69		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	4	4		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	25	25		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1022	1022		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2686	2686		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	537.5	537.5		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	337.5	337.5		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	78	78		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	193	193		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	168	168		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	30	30		

* SPECIALTY ITEMS

FILE NAME =	USER NAME = duncanbd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
ct:\pw_work\PWIDOT\DUNCANBD\dms31838\epd2508-shd-details.DGN		DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	311	(5)N	LASALLE	39	4
		CHECKED -	REVISED -		CONTRACT NO. 66857										
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT										