

FOR INFORMATION ONLY

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	1000 TAZEWELL CO URBAN 80/20	1000 TAZEWELL CO RURAL 80/20	1000 WOODFORD CO. RURAL 80/20	1000 DIEBLE RD. TAZEWELL CO. 100%-COUNTY	1000 TAZEWELL CO. RURAL 100%-STATE	1000 WOODFORD CO. RURAL 100%-STATE	Y031-1F TAZEWELL CO. URBAN 80/20
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	16			16				
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	145	75	43	26	1			
40600300	AGGREGATE (PRIME COAT)	TON	520	276	144	93	7			
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	7,253	3,850	2,012	1,301	90			
40600895	CONSTRUCTING TEST STRIP	EACH	2	0.5	0.5	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	583	315	108	107	53			
40600990	TEMPORARY RAMP	SQ YD	242	108	54	54	27			
40603535	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	14,544	7,718	4,033	2,609	184			
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	278,526	143,026	82,874	50,021	2,605			
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	66		49	17				
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	35		35					
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	156			156				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,147	1,113	605	417	12			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	13,376	6,482	4,422	2,404	68			
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	113			112.5				
63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4			4				
63200310	GUARDRAIL REMOVAL	FT	113			112.5				
63304385	TRAFFIC BARRIER TERMINAL REMOVAL, TYPE 1	EACH	4			4				
64200105	SHOULDER RUMBLE STRIP	FOOT	93,627	49,586	29,967	14,074				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	1	1					
67100100	MOBILIZATION	L SUM	0.7	0.3	0.4	0.3				
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	0.5		0.5				

FILE NAME = 68467 - Phase II.dgn

USER NAME = johnsantv

DESIGNED -

REVISED -

DRAWN -

REVISED -

PLOT SCALE = 1/8" = 1' / IN.

CHECKED -

REVISED -

PLOT DATE = 12/18/2009

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SHEET NO. 1 OF 3 SHEETS

F.A.P. RTE.

317

SECTION

17RS-6; 18RS-1; 35RS-8

COUNTY

TAZEWELL WOODFORD

TOTAL SHEETS

60

SHEET NO.

9

CONTRACT NO. 68467

ILLINOIS FED. AID PROJECT