

LOCATION OF WORK:

FAP 808 (US 150)  
 CHAMPAIGN COUNTY  
 STATION 92+58.00  
 TO  
 STATION 152+50.42  
 URBAN 5-LANE  
 100% STATE  
 I000

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,662.0
40600300	AGGREGATE (PRIME COAT)	TON	37.0
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	1,693.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600990	TEMPORARY RAMP	SQ YD	1,428.0
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	3,076.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	572.0
40800030	AGGREGATE (PRIME COAT)	TON	6.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	477.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	16,359.0
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	20,260.0
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	5,725.0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	630.0
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	32.0
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	174.0
56109210	WATER VALVES TO BE ADJUSTED	EACH	32.0
60255500	MANHOLES TO BE ADJUSTED	EACH	37.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4.0
67100100	MOBILIZATION	L SUM	1.0
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19,209.0
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,556.0

FILE NAME =	USER NAME = buckles_jj	DESIGNED -	REVISED -
c:\pw_work\PWIDOT\BUCKLESJJ\d0141682\0570121-sht-500.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/11/2009	DATE -	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES				
SCALE:	SHEET NO.	OF	SHEETS	STA. TO STA.

F.A.P. RTE. 808	SECTION (282)RS-5	COUNTY Champaign	TOTAL SHEETS 59	SHEET NO. 4
CONTRACT NO. 70121			ILLINOIS FED. AID PROJECT	