

PAVEMENT MARKING SCHEDULE

LOCATION	(78000200)					(78000400)	(78000600)		(78000650)	(78000100)			(70300100)	(70301000)
	THERMOPLASTIC PAVEMENT MARKING LINE, 4"					THERMOPLASTIC PVMT MARKING LINE, 6"	THERMOPLASTIC PAVEMENT MARKING LINE, 12"		THERMOPLASTIC PVMT MARKING LINE, 24"	THERMOPLASTIC PAVEMENT MARKING LETTERS & SYMBOLS			SHORT-TERM PAVEMENT MARKING	WORK ZONE PVMT MARKING REMOVAL
	LANE LINE SKIP DASH (WHITE)	TURN LANE SOLID (YELLOW)	TURN LANE SKIP DASH (YELLOW)	TURN LANE SOLID (WHITE)	CONC MEDIAN SOLID (YELLOW)	CROSSWALK / RADIUS SOLID (WHITE)	DIAGONAL SOLID (YELLOW)	DIAGONAL SOLID (WHITE)	STOP BAR SOLID (WHITE)	TURN ARROW (WHITE)	RR "X" (WHITE)	RR "R" (WHITE)	FT	SQ FT
FT	FT	FT	FT	FT	FT	FT	FT	FT	SQ FT	SQ FT	SQ FT	FT	SQ FT	
STA. 92+58.00 TO STA. 94+50.00	86.0	562.0		70.0		120.0	24.0		35.0	31.2		614.8	102.4	
S. WRIGHT STREET		93.0		47.0		149.0			38.0	15.6		484.2	80.6	
STA. 95+40.00 TO STA. 99+65.00	205.0	808.0	104.0	114.0		117.0			35.0	109.2		851.6	141.8	
STA. 99+65.00 TO STA. 103+66.00	200.5	1,084.0		215.0			90.0			46.8		420.2	70.0	
S. MATHEWS AVENUE		8.0		4.0		80.0			22.0			266.4	44.4	
STA. 103+66.00 TO STA. 108+20.00	220.5	740.0	117.0	237.0		158.0			51.0	140.4		1,077.4	179.4	
N. GOODWIN AVENUE		74.0		37.0		118.0			29.0	15.6		370.2	61.6	
S. GOODWIN AVENUE		60.0		60.0		259.0	48.0		39.0	31.2		492.0	81.9	
STA. 108+90.00 TO STA. 113+00.00	195.0	752.0	112.0	95.0		159.0			36.0	93.6		847.0	141.0	
STA. 113+00.00 TO STA. 117+52.00	226.0	776.0	194.0							93.6		491.2	81.8	
STA. 117+52.00 TO STA. 121+30.00	177.5	566.0	76.5	72.0		177.0			90.0	93.6	108.0	1,317.0	465.0	
N. LINCOLN AVENUE	51.7	102.0		48.0	169.0	145.0			49.0	31.2		634.0	105.6	
S. LINCOLN AVENUE	50.7	94.0		47.0	52.0	160.0			36.0	15.6		491.0	81.8	
STA. 121+90.00 TO STA. 126+85.00	240.5	874.0	149.5	75.0		160.0			84.0	93.6	108.0	1,400.7	155.5	
STA. 126+85.00 TO STA. 131+60.00	228.5	772.0	131.0	82.0		123.0			34.0	93.6		1,299.6	144.3	
N. COLER AVENUE		62.0		31.0		102.0			21.0	15.6		270.6	45.1	
S. COLER AVENUE		62.0		29.0		91.0			24.0	15.6		306.2	51.0	
STA. 132+05.00 TO STA. 135+35.00	143.5	576.0		165.0		261.0			69.0	78.0		1,636.5	181.7	
ORCHARD STREET						123.0			35.0			420.0	69.9	
STA. 135+85.00 TO STA. 139+75.00	177.5	934.0	55.5	95.0		234.0	78.0		56.0	62.4		1,596.3	177.2	
STA. 140+45.00 TO STA. 145+15.00	228.0	865.0	166.3	100.0		118.0			34.0	93.6		1,374.6	152.6	
STA. 145+15.00 TO STA. 147+95.00	133.5	422.0	105.5							62.4		397.8	44.2	
STA. 147+95.00 TO STA. 150+35.00	111.0	448.0		105.0		114.0	11.0		33.0	46.8		693.1	99.1	
N. RACE STREET						78.0			14.0			168.0	28.0	
S. RACE STREET		52.0				77.0			16.0			202.4	33.7	
STA. 150+85.00 TO STA. 152+50.42	83.5	482.0		93.0		123.0	9.0		34.0	31.2		885.3	98.3	
GRAND TOTALS	2,759.0	11,268.0	1,212.0	1,821.0	221.0	3,246.0	212.0	48.0	914.0	1,311.0	216.0	29.0	19,209.0	2,918.0

SURVEY MONUMENT COVER ASSEMBLY (Z0070100)

STATION	LOCATION	EACH
5+26.94 (P.C.)	N. WRIGHT ST.	1.0
100+54.90 (P.I.)	US 150	1.0
111+58.44 (P.I.)	US 150	1.0
127+83.89 (P.I.)	US 150	1.0
146+51.37 (P.I.)	US 150	1.0
150+00.36 (P.C.)	US 150	1.0
TOTAL =		6.0

PAVEMENT MARKING GROOVING (X0325605)

LOCATION	MOVEMENT	SQ FT
N. LINCOLN AVE.	SB TO EB	10.9
S. LINCOLN AVE.	NB TO WB	10.1
TOTAL =		21.0