

PAVEMENT MARKINGS SCHEDULE

TEMPORARY RAMP SCHEDULE*

(40600990)

STATION	OFFSET	TYPE	LENGTH	WIDTH	SQYD
76+02	CL	START (US 136)	8.0	26.0	23.11
42+81	LT	TROTTER DR.	33.0	8.0	29.33
57+15	RT	1600 E (TR 256)	50.0	8.0	44.44
113+37	LT	1700 E (TR 278)	30.0	8.0	26.67
153+18	LT	1775 E (TR 292)	30.0	8.0	26.67
166+60	RT	1800 E (TR 300)	30.0	8.0	26.67
221+53	RT	1900 E (GILLUM RD)	22.0	8.0	19.56
223+74	LT	1900 E (GILLUM RD)	40.0	8.0	35.56
274+65	RT	2000 E	30.0	8.0	26.67
276+69	LT	2000 E	30.0	8.0	26.67
328+40	RT	2100 E (CH 27)	30.0	8.0	26.67
329+70	LT	2100 E (DOWNS RD)	27.0	8.0	24.00
382+32	RT	2200 E	27.0	8.0	24.00
383+02	LT	2200 E	30.0	8.0	26.67
462+67	RT	2350 E	30.0	8.0	26.67
462+67	LT	2350 E	27.0	8.0	24.00
520+38	RT	2450 E	22.0	8.0	19.56
521+65	LT	2450 E (LEROY RD)	90.0	8.0	80.00
540+29.41	CL	SN 057-0151 (W)	8.0	26.0	23.11
540+29.41	CL	SN 057-0151 (E)	8.0	26.0	23.11
547+39	RT	2500 E	30.0	8.0	26.67
547+90	LT	2500 E	27.0	8.0	24.00
616+98	CL	SN 057-0185 (W)	15.0	26.0	43.33
616+98	CL	SN 057-0185 (E)	15.0	26.0	43.33
652+79	CL	SN 057-0096 (E)	8.0	26.0	23.11
652+79	CL	SN 057-0096 (W)	8.0	26.0	23.11
653+60	RT	2700 E (CH 21)	28.0	8.0	24.89
653+60	LT	2700 E (CH 21)	40.0	8.0	35.56
698+50	LT	WB I-74 EXIT RAMP	18.0	8.0	16.00
698+80	RT	EB I-74 ENTRANCE	18.0	8.0	16.00
706+20	CL	SN 057-0135 (E)	20.0	26.0	57.78
706+20	CL	SN 057-0135 (W)	20.0	26.0	57.78
713+85	LT	WB I-74 ENTRANCE	18.0	8.0	16.00
713+85	RT	EB I-74 EXIT RAMP	18.0	8.0	16.00
739+04	CL	CRC RR X-ING (W)	20.0	26.0	57.78
739+04	CL	CRC RR X-ING (E)	20.0	26.0	57.78
774+30	CL	END (US 136)	8.0	26.0	23.11
TOTAL					1,145.3

* No Temporary Ramps within City Limits or at P.E./C.E. between Heyworth and US 150

** Temporary Ramps at Sideroads may be omitted at the Resident Engineers discretion

STATION	TO	STATION	LENGTH	SHORT TERM PVT MKS (FOOT) (70300100)	SKIP DASH YELLOW, 4" FOOT (78001110)	SOLID YELLOW, 4" FOOT	SOLID WHITE, 4" FOOT	STOP BAR WHITE, 24" FOOT (78001180)	CROSSWALK WHITE, 6" FOOT (78001130)	CROSSWALK WHITE, 12" FOOT	ISLAND STRIPING WHITE, 12" FOOT (78001150)	ISLAND STRIPING YELLOW, 12" FOOT
0+50.00		1+65.00	115.0	23.0 (2)		230.0		74				
1+65.00		20+20.00	1,855.0	371.0 (2)	463.8				52	84		
CURB AND GUTTER ENDS												
20+20.00		24+60.00	440.0	237.6 (3)	110.0	440.0	880.0					
24+60.00		26+00.00	140.0	75.6 (3)	35.0		280.0					
26+00.00		31+18.60	518.6	280.0 (3)	129.7	518.6	1,037.2					
EQ. Sta. 31+18.60 BK = 31+28.68 AH												
31+28.68		34+90.00	361.3	195.1 (3)	90.3	361.3	722.6					
34+90.00		38+00.00	310.0	167.4 (3)	77.5		620.0					
38+00.00		46+50.00	850.0	459.0 (3)	212.5	850.0	1,700.0					
46+50.00		48+30.00	180.0	97.2 (3)	45.0		360.0					
48+30.00		55+60.00	730.0	394.2 (3)	182.5	730.0	1,460.0					
55+60.00		99+70.00	4,410.0	2,381.4 (3)	1,102.5		8,820.0	17	163		87	
99+70.00		110+00.00	1,030.0	556.2 (3)	257.5	1,030.0	2,060.0					
110+00.00		119+50.00	950.0	513.0 (3)	0.0	1,900.0	1,900.0					
119+50.00		129+50.00	1,000.0	540.0 (3)	250.0	1,000.0	2,000.0					
129+50.00		142+80.00	1,330.0	718.2 (3)	332.5		2,660.0					
142+80.00		151+00.00	820.0	442.8 (3)	205.0	820.0	1,640.0					
151+00.00		152+00.00	100.0	54.0 (3)	0.0	200.0	200.0					
152+00.00		159+00.00	700.0	378.0 (3)	175.0	700.0	1,400.0					
159+00.00		186+90.00	2,790.0	1,506.6 (3)	697.5		5,580.0					
186+90.00		194+55.00	765.0	413.1 (3)	191.3	765.0	1,530.0					
194+55.00		197+85.00	330.0	178.2 (3)	82.5		660.0					
197+85.00		201+20.00	335.0	180.9 (3)	83.8	335.0	670.0					
201+20.00		237+60.00	3,640.0	1,965.6 (3)	910.0		7,280.0					
237+60.00		242+05.00	445.0	240.3 (3)	111.3	445.0	890.0					
242+05.00		250+40.00	835.0	450.9 (3)	208.8		1,670.0					
250+40.00		256+70.00	630.0	340.2 (3)	157.5	630.0	1,260.0					
256+70.00		492+30.00	23,560.0	12,722.4 (3)	5,890.0		47,120.0					
492+30.00		500+80.00	850.0	459.0 (3)	212.5	850.0	1,700.0					
500+80.00		502+70.00	190.0	102.6 (3)	47.5		380.0					
502+70.00		520+00.00	1,730.0	934.2 (3)	432.5	1,730.0	3,460.0					

Rev. Sheet 2-11-10

FILE NAME =	USER NAME = lerrygms	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\DOT\LEROYMA\0170848\057507.sht-schedules.dgn		DRAWN -	REVISED -			315		McLean	115	16	
PLOT SCALE = 40.0000" / IN.		CHECKED -	REVISED -			*101.102XR,RS-2 & 55RS-PRK LN CONTRACT NO. 70507					
PLOT DATE = 2/5/2010		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					

SCALE: SHEET NO. OF SHEETS STA. TO STA.