F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-15, 60-15B	MADISON	474	27
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CONTRACT NO. 76323

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

PAVEMENT MARKING SCHEDULE CONTINUED

STATION TO STATION		SIDE	DESCRIPTION	THERMOPLASTIC PAVEMENT MARKING						PREFORMED PLASTIC PAVEMENT MARKING	EPOXY PAVEMENT MARKING					
				LETTERS AND SYMBOLS	YELLOW	WHITE	WHITE	WHITE	WHITE	TYPE B - LINE 100MM	LETTERS AND SYMBOLS	YELLOW	WHITE	WHITE	WHITE	WHITE
					LINE 100MM		LINE 200MM	LINE 300MM	LINE 600MM			LINE 100MM		LINE 200MM	LINE 300MM	LINE 600MM
				SQ M	METER					METER	SQ M	METER				
RAMP 3																
1+615.8	1+710.6	RT	EDGE LINE			94.8										
RAMP A																
0+015.4	0+019.7	LT	CROSSWALK												13.4	
0+016.6	0+022.8	RT	CROSSWALK												13.4	
0+018.4		LT	STOP BAR													4.9
0+048.9	0+703.1	RT	EDGE LINE			654.2										
0+048.9	0+322.4	LT	EDGE LINE		273.5											
0+322.4	0+472.5	LT	CHANNELIZATION				150.2									
RAMP B																
0+000.0	0+546.2	RT	EDGE LINE			546.2										
0+084.4	0+200.1	LT	CHANNELIZATION				115.7									
0+200.1	0+546.2	LT	EDGE LINE		346.1											
0+446.2	0+546.2	LT	LANE LINE			100.0										
0+546.2	0+575.0	LT	TURN LANE										28.9			
0+568.7		RT	RIGHT TURN ARROW								1.47					
0+570.0		LT	LEFT TURN ARROW								1.47					
0+570.0		LT & RT	LEFT TURN ARROW								1.47					
0+573.0	0+579.0	RT	CROSSWALK												13.4	
0+573.4		RT	STOP BAR													4.9
0+575.3		LT & RT	STOP BAR													7.2
0+578.3	0+580.1	LT & RT	CROSSWALK												19.8	
HUMBERT RAMP C																
0+043.1	0+275.7	RT	EDGE LINE			232.6										
0+043.1	0+274.4	LT	EDGE LINE		231.3											
0+274.4	0+348.2	LT	CHANNELIZATION											73.7		
0+275.7	0+350.2	RT	EDGE LINE										74.5			
0+348.2	0+443.8	LT	CHANNELIZATION				95.7									
0+350.2	0+508.7	RT	EDGE LINE			158.5										
HUMBERT RAMP D																
0+000.0	0+003.1	RT	EDGE LINE			3.1										
0+003.1	0+087.4	RT	EDGE LINE										84.2			
0+016.1	0+084.9	LT	CHANNELIZATION											68.8		
0+084.9	0+087.4	LT	CHANNELIZATION				2.5									
0+087.4	0+378.9	RT	EDGE LINE			291.5										
0+089.2	0+378.9	LT	EDGE LINE		289.7											
0+400.7		LT	STOP BAR													4.9
0+401.2		LT & RT	STOP BAR													4.9
0+401.3	0+406.3	LT & RT	CROSSWALK												13.4	
0+401.9	0+405.4	LT	CROSSWALK												14.6	
RAMP F																
0+040.5	0+533.9	RT	EDGE LINE			493.4										
0+040.5	0+318.8	LT	EDGE LINE		278.3											
0+318.8	0+469.0	LT	CHANNELIZATION				150.2									
RAMP E																
0+000.0	0+376.9	RT	EDGE LINE			376.9										
0+130.2	0+376.9	LT	EDGE LINE		246.7											
0+400.2		LT	STOP BAR						5.5							
0+401.3		RT	STOP BAR						5.5							
IL 111 RAMP D																
0+040.8	0+762.5	RT	EDGE LINE			721.7										
0+040.8	0+360.1	LT	EDGE LINE		319.4											
0+360.1	0+532.7	LT	CHANNELIZATION				172.6									
IL 111 RAMP C																
0+000.0	0+579.5	RT	EDGE LINE			579.5										
0+083.2	0+196.2	LT	CHANNELIZATION				113.1									
0+196.2	0+579.5	LT	EDGE LINE		383.3											
SUBTOTALS				0.00	2368.3	4252.4	800.0	0.0	11.0	0.0	4.41	0.0	187.6	142.5	88.0	26.8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULES OF QUANTITIES
FAP 310 (IL 255)
SECTION 60-15
MADISON COUNTY

DRAWN BY EBB
DATE CHECKED BY

6/28/2007
p:\00files\00024\dmainline\schedules\schedquant015a.dgn