

SUMMARY OF QUANTITIES			LIABAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE										BOX CULVERT X028-2A 80% FED 20% STATE	RETAINING WALLS Y007 80% FED 20% STATE	
				ROADWAY I000-2A				TRAFFIC SIGNALS Y031-IF			UTILITIES Y060					
				ST. CLAIR COUNTY		MADISON COUNTY		MADISON COUNTY	MADISON COUNTY	ST. CLAIR COUNTY	ST. CLAIR COUNTY	MADISON COUNTY	ST. CLAIR COUNTY			MADISON COUNTY
				80% FED 20% STATE	80% FED 10% STATE 10% CITY	80% FED 20% STATE	80% FED 10% STATE 10% CITY	E. CHURCH ST. 80% FED 10% STATE 10% CITY	MID BLOCK CROSSING 80% FED 20% CITY	MORRISON AVE. 80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE			80% FED 20% STATE
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4					4								
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	4					4								
88102820	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 2-SECTION BRACKET MOUNTED	EACH	4					2	2							
88200300	TRAFFIC SIGNAL BACKPLATE, PLASTIC	EACH	14					10	4							
88500100	INDUCTIVE LOOP DETECTOR	EACH	10					10								
88600100	DETECTOR LOOP, TYPE I	FOOT	1800					1800								
88600600	DETECTOR LOOP REPLACEMENT	FOOT	475							475						
88800100	PEDESTRIAN PUSH-BUTTON	EACH	10					8	2							
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1					1								
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	100					100								
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1					1								
89502380	REMOVE EXISTING HANDHOLE	EACH	3					3								
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9					9								
A2001720	TREE, ACER SACCHARUM (SUGAR MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	13			13										
A2006920	TREE, QUERCUS PALUSTRIS (PIN OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6			6										
A2007120	TREE, QUERCUS RUBRA (RED OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3			3										
B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	33	9		24										
B2005016	TREE, MALUS SNOWDRIFT (SNOWDRIFT CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	21			21										
X0320591	SANITARY MANHOLES TO BE REMOVED	EACH	2								2					
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	11								11					
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	163			163										
X0326859	PAVEMENT IMPRINTING	SQ YD	656			656										
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	262										262			
X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	18746										3950	14796		
X0324896	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 2-SECTION, BRACKET MOUNTED	EACH	3					3								

*Specialty Items

Rev.

FILE NAME =	USER NAME = keplarc1	DESIGNED -	REVISED -
ct:\pwork\PW100T\KEPLARCL\dms79807\08	8838-shr-plan.dgn	DRAWN -	REVISED -
	PLOT SCALE = 50.3041' / IN.	CHECKED -	REVISED -
	PLOT DATE = 11/19/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
600	60-(30,31,128)-1	MADISON/ST. CLAIR	399	13
CONTRACT NO. 76830				
FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT				

SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____