



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 17, 2010

SUBJECT: FAP Route 809 (IL 158)
Project ACF-0809 (005)
Section 67-1HBR
Monroe County
Contract No. 76977
Item No. 131, March 5, 2010 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised sheets 2-10, 12-14, 17, 36, 43-45, 48-51 and 66 of the Plans.
3. Added sheet 14A to the Plans.
4. Revised page iii of the Table of Contents to the Special Provisions.
5. Added page 114 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Mary C. Lamie, Region 5, District 8; Mike Renner; R. E. Anderson;
Estimates

TBW:DB:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76977

State Job # - C-98-003-06
 PPS NBR - 8-89344-0000
 County Name - MONROE- -
 Code - 133 - -
 District - 8 - -
 Section Number - 67-1HBR

Project Number
 ACF-0809/005/

Route
 FAP 809

* REVISED : FEBRUARY 11, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0322400	PILE EXTRACTION	EACH	8.000				
X0323988	TEMP SOIL RETEN SYSTM	SQ FT	207.000				
X0502600	TEMP LIGHTING	L SUM	1.000				
X4421000	PARTIAL DEPTH PATCH	TON	100.000				
X4422030	PARTIAL DEPTH REM 3	SQ YD	570.000				
X5080600	MECHANICAL SPLICERS	EACH	120.000				
X6060500	CORRUGATED MED REM	SQ FT	535.000				
X7200200	WIDE LOAD SIGNING	L SUM	1.000				
X7800100	PT PVT MK- RAISED MED	SQ FT	47.000				
X7800200	PAINT PVT MARK CURB	FOOT	1,280.000				
X8161000	EXP & REL EX UNIT DCT	FOOT	100.000				
* Z0017202	DOWEL BARS 1 1/2	EACH	529.000				
Z0030250	IMP ATTN TEMP NRD TL3	EACH	4.000				
Z0030350	IMP ATTN REL NRD TL3	EACH	2.000				
Z0073500	TEMP SUPPORT SYSTEM	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76977

State Job # - C-98-003-06
 PPS NBR - 8-89344-0000
 County Name - MONROE- -
 Code - 133 - -
 District - 8 - -
 Section Number - 67-1HBR

Project Number
 ACF-0809/005/

Route
 FAP 809

* REVISED : FEBRUARY 11, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0076600	TRAINEES	HOUR	1,000.000		0.800		800.000
20200100	EARTH EXCAVATION	CU YD	325.000				
20400800	FURNISHED EXCAVATION	CU YD	1,315.000				
20700400	POROUS GRAN EMB SPEC	CU YD	139.000				
25000200	SEEDING CL 2	ACRE	1.250				
25000400	NITROGEN FERT NUTR	POUND	112.000				
25000500	PHOSPHORUS FERT NUTR	POUND	112.000				
25000600	POTASSIUM FERT NUTR	POUND	112.000				
25100115	MULCH METHOD 2	ACRE	1.250				
28000250	TEMP EROS CONTR SEED	POUND	125.000				
28000305	TEMP DITCH CHECKS	FOOT	100.000				
28000400	PERIMETER EROS BAR	FOOT	1,990.000				
28100105	STONE RIPRAP CL A3	SQ YD	62.000				
35501324	HMA BASE CSE 10	SQ YD	880.000				
35501328	HMA BASE CSE 11	SQ YD	5,770.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76977

State Job # - C-98-003-06
 PPS NBR - 8-89344-0000
 County Name - MONROE- -
 Code - 133 - -
 District - 8 - -
 Section Number - 67-1HBR

Project Number
 ACF-0809/005/

Route
 FAP 809

* REVISED : FEBRUARY 11, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40600200	BIT MATLS PR CT	TON	4.000				
40600300	AGG PR CT	TON	20.000				
40600635	LEV BIND MM N70	TON	600.000				
40600982	HMA SURF REM BUTT JT	SQ YD	156.000				
40600985	PCC SURF REM BUTT JT	SQ YD	490.000				
40600990	TEMPORARY RAMP	SQ YD	72.000				
40603085	HMA BC IL-19.0 N70	TON	1,820.000				
40603340	HMA SC "D" N70	TON	1,100.000				
40800020	BIT MATLS PR CT	TON	0.200				
40800030	AGG PR CT	TON	1.000				
40800050	INCIDENTAL HMA SURF	TON	80.000				
42001430	BR APPR PVT CON (FLX)	SQ YD	74.000				
44000100	PAVEMENT REM	SQ YD	840.000				
44000500	COMB CURB GUTTER REM	FOOT	4,360.000				
44003100	MEDIAN REMOVAL	SQ FT	10,900.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76977

State Job # - C-98-003-06
 PPS NBR - 8-89344-0000
 County Name - MONROE- -
 Code - 133 - -
 District - 8 - -
 Section Number - 67-1HBR

Project Number
 ACF-0809/005/

Route
 FAP 809

* REVISED : FEBRUARY 11, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
44004000	PAVED DITCH REMOVAL	FOOT	35.000				
44004250	PAVED SHLD REMOVAL	SQ YD	1,770.000				
* 44200970	CL B PATCH T2 10	SQ YD	213.000				
44200974	CL B PATCH T3 10	SQ YD	37.000				
44200976	CL B PATCH T4 10	SQ YD	45.000				
44213100	PAVEMENT FABRIC	SQ YD	60.000				
* 44213200	SAW CUTS	FOOT	1,261.000				
48102100	AGG WEDGE SHLD TYPE B	TON	30.000				
48203100	HMA SHOULDERS	TON	1,725.000				
50100100	REM EXIST STRUCT	EACH	1.000				
50105220	PIPE CULVERT REMOV	FOOT	32.000				
50157300	PROTECTIVE SHIELD	SQ YD	1,018.000				
50200100	STRUCTURE EXCAVATION	CU YD	157.000				
50200400	ROCK EXC STRUCT	CU YD	349.000				
50300225	CONC STRUCT	CU YD	543.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76977

State Job # - C-98-003-06
 PPS NBR - 8-89344-0000
 County Name - MONROE- -
 Code - 133 - -
 District - 8 - -
 Section Number - 67-1HBR

Project Number
 ACF-0809/005/

Route
 FAP 809

* REVISED : FEBRUARY 11, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50300255	CONC SUP-STR	CU YD	539.000				
50300260	BR DECK GROOVING	SQ YD	1,022.000				
50300280	CONCRETE ENCASEMENT	CU YD	7.000				
50300300	PROTECTIVE COAT	SQ YD	1,377.000				
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	6,960.000				
50800205	REINF BARS, EPOXY CTD	POUND	202,020.000				
50800515	BAR SPLICERS	EACH	303.000				
51100100	SLOPE WALL 4	SQ YD	494.000				
51201600	FUR STL PILE HP12X53	FOOT	513.000				
51202305	DRIVING PILES	FOOT	513.000				
51203600	TEST PILE ST HP12X53	EACH	1.000				
51204650	PILE SHOES	EACH	20.000				
51205200	TEMP SHT PILING	SQ FT	163.000				
51500100	NAME PLATES	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76977

State Job # - C-98-003-06
 PPS NBR - 8-89344-0000
 County Name - MONROE- -
 Code - 133 - -
 District - 8 - -
 Section Number - 67-1HBR

Project Number
 ACF-0809/005/

Route
 FAP 809

* REVISED : FEBRUARY 11, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
52000110	PREF JT STRIP SEAL	FOOT	115.000				
52100010	ELAST BEARING ASSY T1	EACH	16.000				
52100540	ANCHOR BOLTS 1 1/2	EACH	32.000				
52100560	ANCHOR BOLTS 2	EACH	16.000				
54213657	PRC FLAR END SEC 12	EACH	1.000				
* 550A0050	STORM SEW CL A 1 12	FOOT	34.000				
58700300	CONCRETE SEALER	SQ FT	1,531.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	274.000				
60109580	P UNDR FOR STRUCT 4	FOOT	247.000				
60236800	INLETS TA T11F&G	EACH	1.000				
60260100	INLETS ADJUST	EACH	8.000				
60404800	FR & GRATES T11	EACH	8.000				
60500060	REMOV INLETS	EACH	1.000				
60605600	COMB CC&G TB9.06	FOOT	4,300.000				
* 60618300	CONC MEDIAN SURF 4	SQ FT	10,745.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76977

State Job # - C-98-003-06
 PPS NBR - 8-89344-0000
 County Name - MONROE- -
 Code - 133 - -
 District - 8 - -
 Section Number - 67-1HBR

Project Number
 ACF-0809/005/

Route
 FAP 809

* REVISED : FEBRUARY 11, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
63000001	SPBGR TY A 6FT POSTS	FOOT	525.000				
63000003	SPBGR TY A 9FT POSTS	FOOT	3,850.000				
63100045	TRAF BAR TERM T2	EACH	3.000				
63100085	TRAF BAR TERM T6	EACH	4.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	8.000				
63200310	GUARDRAIL REMOV	FOOT	5,109.000				
67000400	ENGR FIELD OFFICE A	CAL MO	20.000				
67100100	MOBILIZATION	L SUM	1.000				
70100420	TRAF CONT-PROT 701411	EACH	1.000				
70100450	TRAF CONT-PROT 701201	L SUM	1.000				
70100455	TRAF CONT-PROT 701206	L SUM	1.000				
70100460	TRAF CONT-PROT 701306	L SUM	1.000				
70100500	TRAF CONT-PROT 701326	L SUM	1.000				
70100600	TRAF CONT-PROT 701336	L SUM	1.000				
70100825	TRAF CONT-PROT 701456	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76977

State Job # - C-98-003-06
 PPS NBR - 8-89344-0000
 County Name - MONROE- -
 Code - 133 - -
 District - 8 - -
 Section Number - 67-1HBR

Project Number
 ACF-0809/005/

Route
 FAP 809

* REVISED : FEBRUARY 11, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70101200	TC-PROT 701431 SPL	EACH	1.000				
70101205	TC-PROT 701321 SPL	EACH	1.000				
70101800	TRAF CONT & PROT SPL	L SUM	1.000				
* 70103815	TR CONT SURVEILLANCE	CAL DA	30.000				
70106600	TEMP BR TRAF SIG SFC	EACH	1.000				
70106700	TEMP RUMBLE STRIP	EACH	6.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	30.000				
70300100	SHORT-TERM PAVT MKING	FOOT	950.000				
70300220	TEMP PVT MK LINE 4	FOOT	14,846.000				
70300240	TEMP PVT MK LINE 6	FOOT	2,325.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	5,265.000				
70400100	TEMP CONC BARRIER	FOOT	1,325.000				
70400200	REL TEMP CONC BARRIER	FOOT	1,000.000				
78000200	THPL PVT MK LINE 4	FOOT	13,840.000				
78000500	THPL PVT MK LINE 8	FOOT	1,805.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

76977

State Job # - C-98-003-06
 PPS NBR - 8-89344-0000
 County Name - MONROE- -
 Code - 133 - -
 District - 8 - -
 Section Number - 67-1HBR

Project Number
 ACF-0809/005/

Route
 FAP 809

* REVISED : FEBRUARY 11, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78008210	POLYUREA PM T1 LN 4	FOOT	1,006.000				
78100100	RAISED REFL PAVT MKR	EACH	61.000				
78200300	PRISMATIC CURB REFL	EACH	120.000				
78200410	GUARDRAIL MKR TYPE A	EACH	49.000				
78200520	BAR WALL MKR TYPE B	EACH	6.000				
78200530	BAR WALL MKR TYPE C	EACH	6.000				
78201000	TERMINAL MARKER - DA	EACH	8.000				
78300100	PAVT MARKING REMOVAL	SQ FT	6,152.000				
78300200	RAISED REF PVT MK REM	EACH	61.000				
80300100	LOCATE UNDERGR CABLE	FOOT	2,760.000				
* 81603035	UD 2#6 #6G XLPUSE 1	FOOT	2,960.000				
81900200	TR & BKFIL F ELECT WK	FOOT	2,760.000				
* DELETED							
* 83600300	LIGHT POLE FDN 30D	FOOT	16.000				
84200806	REM POLE FDN CONCRETE	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 76977

State Job # - C-98-003-06
 PPS NBR - 8-89344-0000
 County Name - MONROE--
 Code - 133 - -
 District - 8 - -
 Section Number - 67-1HBR

Project Number
 ACF-0809/005/

Route
 FAP 809

* REVISED : FEBRUARY 11, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
84400105	RELOC EX LT UNIT	EACH	2.000				

REINFORCEMENT BARS - STORAGE AND PROTECTION (BDE)..... 96
SELF-CONSOLIDATING CONCRETE FOR PRECAST PRODUCTS (BDE)..... 96
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 97
TEMPORARY EROSION CONTROL (BDE) 98
THERMOPLASTIC PAVEMENT MARKINGS (BDE) 99
TRAFFIC BARRIER TERMINAL, TYPE 6 (BDE) 101
TRAINING SPECIAL PROVISIONS 101
WORKING DAYS (BDE) 103
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) 103
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 106
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) 110
FILTER FABRIC (BDE)..... 114

Revised 02/17/2010

FILTER FABRIC (BDE)

Effective: November 1, 2009

Revised: January 1, 2010

Revise the physical property tables in Article 1080.03 of the Standard Specifications to read:

"Physical Properties	Gradation 4 & 5	Gradation 6 & 7
Weight of Fabric (oz/sq yd), ASTM D 3776 (Mod.)	6.0 min.	8.0 min.
Burst Strength (psi), ASTM D 3786 ^{1/}	250 min.	300 min.
Trapezoidal Tear Strength (lb), ASTM D 5733 ^{2/}	60 min.	75 min.
Grab Tensile Strength (lb), ASTM D 4632 ^{2/}	160 min.	200 min.
Grab Tensile Elongation (%), ASTM D 4632 ^{2/}	50 max.	50 max.

Physical Properties (Metric)	Gradation 4 & 5	Gradation 6 & 7
Weight of Fabric (g/sq m), ASTM D 3776 (Mod.)	200 min.	270 min.
Burst Strength (kPa), ASTM D 3786 ^{1/}	1720 min.	2070 min.
Trapezoidal Tear Strength (N), ASTM D 5733 ^{2/}	265 min.	335 min.
Grab Tensile Strength (N), ASTM D 4632 ^{2/}	700 min.	900 min.
Grab Tensile Elongation (%), ASTM D 4632 ^{2/}	50 max.	50 max.

1/ Manufacturer's certification of fabric to meet requirements.

2/ Test sample shall be tested wet."

Added 02/17/2010