

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 80% FEDERAL 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		SUMMARY OF QUANTITIES			80% FEDERAL 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		X271-2A	I000-2A	CODE NO	ITEM	UNIT		X271-2A	I000-2A
X7200200	WIDE LOAD SIGNING	L SUM	1	1							
* X7800100	PAINT PAVEMENT MARKING - RAISED MEDIAN	SQ FT	47		47						
* X7800200	PAINT PAVEMENT MARKING CURB	FOOT	1280	720	560						
X8161000	EXPOSE AND RELOCATE EXISTING UNIT DUCT	FOOT	100	100							
Z0017202	DOWEL BARS 1 1/2"	EACH	502	502							
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4							
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2							
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1	1							
⓪ 20076600	TRAINEES	HOUR	1,000	1,000							

01080

\*Specialty Items

FILE NAME =	USER NAME = okenbj	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 809	SECTION 67-1HBR	COUNTY MONROE	TOTAL SHEETS 144	SHEET NO. 5
cr:\pwork\pwork\okenbj\dms52558\p1n00826a.dgn	PLOT SCALE = 50.0000' / IN.	DRAWN -	REVISED -							
	PLOT DATE = 12/10/2009	CHECKED -	REVISED -							
		DATE -	REVISED -							
						SCALE:	SHEET NO. 3 OF 3 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

Rev.

CONTRACT NO. 76977