PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKING					POLYUREA PAVEMENT MARKING			PAINT	PAINT		PAVEMENT	RAISED REFLECTIVE	RAISED REFLECTIVE		PRISMATIC	SHORT	TEMPORARY PAVEMENT MARKING				WORK ZONE
	SKIP-DASH CENTERLINE	SOLID CENTERLINE	EDGE LINE 4" WHITE		SOLID CHANNELIZING	SOLID CENTERLINE	EDGE LINE 4" WHITE		PAVEMENT MARKING -	PAVEMENT MARKING - CURB		MARKING REMOVAL	PAVEMENT MARKER REMOVAL	PAVEMENT MARKER		CURB REFLECTOR	TERM PAVEMENT	SKIP-DASH CENTERLINE	SOLID CENTERLINE	EDGE LINE 4" WHITE		PAVEMENT MARKING
	4" YELLOW	4" YELLOW	LT	RT	8" WHITE	4" YELLOW	LT	RT	RAISED MEDIAN	LT	RT			1-WAY CRYSTAL	2-WAY AMBER		MARKING	4" YELLOW	4" YELLOW	LT	RT	REMOVAL
STATION TO STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	SQ FT	EACH	EACH	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT
STA 103+20.00 TO STA 108+00.00		960	480	480						320		640				12	105		960	480	480	675
STA 108+00.00 TO STA 109+73.00		347	173	173						128		231				4	38		347	173	173	244
STA 109+73.00 TO STA 112+24.50						503	251.5	251.5		160		335				6	56		503	251.5	251.5	354
STA 112+24.50 TO STA 114+00.00		351	175	175						112		234				4	39		351	175	175	247
STA 114+00.00 TO STA 115+00.00		200	100	100								133				3	22		200	100	100	141
STA 115+00.00 TO STA 119+00.00		800	400	20	380						32	660				10	89		800	400	20	436
STA 119+00.00 TO STA 120+00.00		200	45		142						64	176	5	5		3	22		200	45		89
STA 120+00.00 TO STA 126+00.00		1200		6	381						400	656	41	41		15	132		1200		6	446
STA 126+00.00 TO STA 132+00.00		1200	575	600					47		64	792	3		3	3	89		1200	575	600	821
STA 132+00.00 TO STA 138+00.00	130	700	600	600								677	7		7		79	130	700	600	600	703
STA 138+00.00 TO STA 142+00.00	100	400	400	400								433	5		5		52	100	400	400	400	451
STA 63+25.00 TO STA 73+85.00				1061	460							660					138				1061	399
STA 19+74.00 TO STA 26+62.00			689		442							524					89			689		259
SUB-TOTAL	230	6358	3637	3615		503	251.5	252		720	560			46	15			230	6861	3889	3867	
TOTAL	13840				1805	1006			47	1280		6152	61	61		60	950	14846				5265

PAVEMENT PATCHING SCHEDULE - CLASS B

LOCATION	SIZE		CLASS B PATCHING 10" TYPE II	CLASS B PATCHING 10" TYPE III	CLASS B PATCHING 10" TYPE IV	SAW CUT	DOWEL BARS 1-1/2"	PVMT FABRIC
	LENGTH	WIDTH						
STATION	FOOT	FOOT	SQ YD	SQ YD	SQ YD	FT	EACH	SQ YD
IL 158 EASTBOUND								
115+25	8	16	14.2			64	28	
116+30	8	16	14.2			64	28	
117+10	8	16	14.2			64	28	
119+00	8	12	10.7			52	20	
120+40	6	12	8.0			48	20	
120+50	6	16	10.7			60	28	
122+00	8	16	14.2			64	28	
123+75	25	16			45	98	28	44
125+25	8	18		16		70	32	16
127+30	8	15	13.2			61	26	
128+10	8	14	12.4			58	24	
130+20	8	13	11.6			55	22	
IL 158 WESTBOUND								
115+25	8	16	14.2			64	28	
116+30	8	16	14.2			64	28	
117+10	8	16	14.2			64	28	
123+85	8	16	14.2			64	28	
123+85	8	16	14.2			64	28	
126+15	12	16		21		72	28	
130+20	8	13	11.6			55	22	
TOTAL			206	37	45	1205	502	60

PARTIAL DEPTH PATCHING SCHEDULE

LOCATION	SIDE	SIZE		PARTIAL DEPTH REMOVAL 3"	PARTIAL DEPTH PATCHING
	RT / LT	LENGTH	WIDTH		
STATION	OR CNTR	FOOT	FOOT	SQ YD	TON
IL 158 EASTBOUND					
117+50	RT	475	2	105.6	17.7
117+95	CNTR	6	6	4.0	0.7
118+05	CNTR	6	6	4.0	0.7
119+40	RT	20	6	13.3	2.2
120+60	RT	1075	2	238.9	40.1
121+00	CNTR	110	4	48.9	8.2
122+30	CNTR	4	4	1.8	0.3
122+50	RT	120	2	26.7	4.5
123+40	RT	2	10	2.2	0.4
125+00	CNTR	4	4	1.8	0.3
127+10	CNTR	4	4	1.8	0.3
127+60	LT	16	8	14.2	2.4
128+60	CNTR	20	2	4.4	0.7
128+70	LT	4	4	1.8	0.3
129+60	CNTR	4	4	1.8	0.3
129+80	CNTR	4	4	1.8	0.3
131+95	CNTR	2	12	2.7	0.4
135+00	CNTR	2	12	2.7	0.4
136+50	CNTR	2	12	2.7	0.4
IL 15 WESTBOUND					
114+75	CNTR	4	4	1.8	0.3
115+45	CNTR	4	4	1.8	0.3
124+50	RT	300	2	66.7	11.2
125+00	CNTR	2	16	3.6	0.6
125+10	CNTR	2	16	3.6	0.6
127+90	LT	2	8	1.8	0.3
129+00	CNTR	2	14	3.1	0.5
135+00	CNTR	2	12	2.7	0.4
135+65	CNTR	2	12	2.7	0.4
TOTAL				568	96
ROUNDING				570	100

REMOVAL SCHEDULE

LOCATION	PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	MEDIAN REMOVAL	PAVED SHOULDER REMOVAL	
				LEFT	RIGHT
STATION TO STATION	SQ YD	FOOT	SQ FT	SQ YD	SQ YD
IL 158					
STA 103+20 TO STA 104+00	53.2	160	400	71	71
STA 104+00 TO STA 105+00	66.6	200	500	89	89
STA 105+00 TO STA 106+00	66.6	200	500	89	89
STA 106+00 TO STA 107+00	66.6	200	500	89	89
STA 107+00 TO STA 108+00		200	500		89
STA 108+00 TO STA 109+00		200	500		89
STA 109+00 TO STA 109+67		160	400		71
STRUCTURE					
STA 112+30 TO STA 113+00		200	500		89
STA 113+00 TO STA 114+00		200	500		89
STA 114+00 TO STA 115+00	66.6	200	500	89	89
STA 115+00 TO STA 116+00	66.6	200	500	89	89
STA 116+00 TO STA 117+00	66.6	200	500	89	44
STA 117+00 TO STA 118+00	66.6	200	500	89	
STA 118+00 TO STA 119+00	66.6	200	500	89	
STA 119+00 TO STA 120+00		200	500		
STA 120+00 TO STA 121+00		200	500		
STA 121+00 TO STA 122+00		200	500		
STA 122+00 TO STA 123+00		200	500		
STA 123+00 TO STA 124+00		200	500		
STA 124+00 TO STA 125+00		200	500		
STA 125+00 TO STA 126+00		200	500		
STA 126+00 TO STA 127+00		200	500		
STA 127+00 TO STA 128+00		40	100		
SUB-TOTAL				783	987
TOTAL	586 *	4200	10900	1770	

* NOT A TOTAL QUANTITY. SEE STAGING SCHEDULE.