

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE - 100% STATE FUNDING						
CODE NO	ITEM	UNIT		ROADWAY	EXCHANGE AVE. BRIDGE S.N. 082-0378	RETAINING WALL S.N. 082-W301	LIGHTING	SIGNING	STRUCTURE DEMOLITION	ITS
44003100	MEDIAN REMOVAL	SO FT	1,217	1,217	X271 - 2A	Y007	Y030 - 1E	Y002 - 1C	Y007	Y032 - 1F
44004250	PAVED SHOULDER REMOVAL	SO YD	2,440	2,440						
44200680	CLASS A PATCHES, TYPE IV	SO YD	182	182						
44213200	SAW CUTS	FOOT	208	208						
48100100	AGGREGATE SHOULDERS, TYPE A	TON	566	566						
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	600	600						
48203037	HOT-MIX ASPHALT SHOULDERS, 10"	SO YD	5,236	5,236						
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SO YD	1,286	1,286						
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1						1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1						1	
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1						1	
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1						1	
50101700	REMOVAL OF EXISTING SUPERSTRUCTURES NO. 1	EACH	1						1	
50157300	PROTECTIVE SHIELD	SO YD	1,243		1,243					
50200100	STRUCTURE EXCAVATION	CU YD	3,379		3,013	366				
50300225	CONCRETE STRUCTURES	CU YD	1,101.1		1,027.8	73.3				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	695.7		695.7					
50300260	BRIDGE DECK GROOVING	SO YD	927		927					
50300285	FORM LINER TEXTURED SURFACE	SO FT	4,678		3,660	1,018				