

LANDSCAPE ITEMS						
	SEEDING CL 2A	NITROGEN FERT NUTR	PHOSPHORUS FERT NUTR	POTASSIUM FERT NUTR	AGR GROUND LIMESTONE	MULCH METHOD 2
STATION TO STATION	ACRE	POUND	POUND	POUND	TON	TON
EXCHANGE AVE	1.46	131	131	131	2.92	2.92
RAMP P REMOVAL	0.68	61	61	61	1.36	1.36
BOWMAN YARD ACCESS RD	1.24	112	112	112	2.48	2.48
CSX ACCESS ROAD AND SPUR	0.42 0.25	38 23	38 23	38 23	0.84 0.50	0.84 0.50
RAMP O, INCLUDING INFIELD	4.45	401	401	401	8.90	8.90
TOTALS	8.25 8.08	743 728	743 728	743 728	16.50 16.16	16.50 16.16

EARTHWORK SCHEDULE				
LOCATION	EARTH EXCAVATION (CY)	EXCAVATION ADJUSTED FOR SHRINKAGE (CY)	EMBANKMENT (CY)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CY)
EXCHANGE AVE	1123	842	3825	-2983
7TH ST	808	606	1	605
BOWMAN	2896	2172	419	1753
RAMP "O"	10044	7533	1586	5947
RAMP "O" INFIELD	28387 24611	22048 18458	220 215	21828 18243
CSX ACCESS RD	0 53	0 40	891 713	891 -673
CSX SPUR	104	78	0	78
BOWMAN YARD	4591	3443	0	3443
RAMP "P"/I-55	9756	7317	0	7317
WALL E	1285	964	0	964
TOTAL	60004 55271	45003 41453	6942 6759	36660 34694