

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000	-----	-----	CODE NO	ITEM	UNIT		-----	-----	-----
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	31	31									
40600300	AGGREGATE (PRIME COAT)	TON	145	145									
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8119	8119									
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	96652	96652									
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	265	265									
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	69	69									
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SQ YD	93	93									
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	73231	73231									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4									
67100100	MOBILIZATION	L SUM	1	1									
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1									
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1									
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7081	7081									
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	260	260									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	95366	95366									
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	470	470									
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	693	693									
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	144	144									
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1180	1180									
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	229	229									
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	95366	95366									
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	470	470									
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	693	693									
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	144	144									
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	541	541									
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	541	541									
* 80300100	LOCATING UNDERGROUND CABLE	FOOT	100	100									
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1635	1635									
32007600	TRAINNEES	HOUR	500	500									

04080

* Specialty Items

Rev.

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN - ---	REVISED - ---			604	(101,102,JRS-3)	MADISON	13	3	
	PLOT SCALE = #SCALE#	CHECKED - ---	REVISED - ---			CONTRACT NO. 76D27					
	PLOT DATE = #DATE#	DATE - ---	REVISED - ---			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					

SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____