

### RESURFACING SCHEDULE

LOCATION			BIT. MAT'L PRIME COAT	AGGREGATE PRIME COAT	SURFACE COURSE	HMA SURFACE REMOVAL 1.5"	STRIP REFLECTIVE CRACK CONTROL	REMARKS
Sta.	To	Sta.	(TON)	(TON)	(TON)	(SQ YD)	(FOOT)	
IL 159								
400+00	to	422+18	1.85	8.87	496.83	5914.67	4436	
422+18	to	440+45	1.52	7.31	409.25	4872.00	3654	M.M. 19
440+45	to	457+90	1.46	6.98	390.88	4653.33	3490	BEG. 3' SHLDRS
457+90	to	460+92	0.31	1.51	84.56	1006.67	1208	MORO RD. INT.
460+92	to	467+70	0.85	4.07	227.81	2712.00	2712	MORO RD. INT.
467+70	to	470+70	0.31	1.50	84.00	1000.00	1200	MORO RD. INT.
470+70	to	473+92	0.27	1.29	72.13	858.67	644	MORO RD. INT.
473+92	to	526+72	4.41	21.12	1182.72	14080.00	10560	M.M. 20
526+72	to	579+52	4.41	21.12	1182.72	14080.00	10560	M.M. 21
579+52	to	632+32	4.41	21.12	1182.72	14080.00	10560	M.M. 22
632+32	to	685+12	4.41	21.12	1182.72	14080.00	10560	M.M. 23
685+12	to	737+92	4.41	21.12	1182.72	14080.00	10560	M.M. 24
737+92	to	751+58	1.14	5.46	305.98	3642.67	2732	M.M. 25
MORO RD								
239+89	to	241+20	0.26	1.25	70.22	836.00	131	
238+38	to	239+50	0.24	1.13	63.5	756.00	224	
TOTAL			31	145	819	96652	73231	

### PATCHING SCHEDULE

LOCATION	SB/NB	LENGTH (FEET)	WIDTH (FEET)	PAVEMENT PATCHING 14"		
				TYPE 2	TYPE 3	TYPE 4
				(SQ YDS)	(SQ YDS)	(SQ YDS)
400+53	SB	8	12	11		
426+40	SB	20	12			27
426+40	NB	20	12			27
442+24	NB	6	12	8		
484+48	NB	6	12	8		
502+96	SB	15	12		20	
502+96	NB	15	12		20	
505+60	SB	8	12	11		
505+60	NB	8	12	11		
526+72	SB	6	12	8		
547+84	SB	6	12	8		
547+84	NB	6	12	8		
548+90	SB	6	12	8		
548+90	NB	10	12	13		
558+40	SB	10	12	13		
563+68	SB	10	12	13		
563+68	NB	8	12	11		
627+04	SB	20	12			27
627+04	NB	8	12	11		
648+16	SB	6	12	8		
648+16	NB	6	12	8		
669+28	SB	6	12	8		
674+56	SB	6	12	8		
695+68	SB	15	12		20	
698+32	SB	6	12	8		
698+32	NB	6	12	8		
719+44	SB	6	12	8		
727+36	SB	6	12	8		
727+36	NB	6	12	8		
732+64	SB	6	12	8		
743+20	SB	6	12	8		
SUB-TOTALS				230	60	81
15% FOR ANTICIPATED FAILURES				35	9	12
TOTALS				265	69	93

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - ---	REVISED - ---			604	(101,102)RS-3	MADISON	13	8
	PLOT SCALE = #SCALE#	CHECKED - ---	REVISED - ---			SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT CONTRACT NO. 76D27		
	PLOT DATE = #DATE#	DATE - -----	REVISED - ---							