

GENERAL NOTES

1. THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.
2. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AMEREN CIPS (GAS & ELECTRIC)
 - AT&T ILLINOIS (COMMUNICATIONS)
 - CHARTER COMMUNICATIONS, INC. (CABLE TV)
 - VILLAGE OF GODFREY (SANITARY SEWER)
 - ILLINOIS AMERICAN WATER CO. (WATER)
 (MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY *. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.)
3. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
4. NO SURVEY WAS PERFORMED FOR THIS PROJECT. THE STATIONING, PAVEMENT MARKING, TOPOGRAPHY, ETC. SHOWN IS APPROXIMATE AND WAS CREATED USING MICROFILM.
5. NO OVERNIGHT LANE CLOSURES SHALL BE ALLOWED ON THE PROJECT.
6. FLAGGERS SHALL BE PRESENT DURING ALL CLOSURE HOURS, INCLUDING LUNCH HOUR, AND NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.
7. THE RESIDENT ENGINEER SHALL VERIFY THE EXISTENCE OF HIGHWAY LIGHTING AND/OR ITS UTILITIES WITHIN THE PROJECT LIMITS. IF HIGHWAY LIGHTING AND/OR ITS EXISTS WITHIN THE PROJECT LIMITS, AND IF THESE ITEMS REQUIRE LOCATING, THE CONTRACTOR SHALL BE DIRECTED TO DO SO ACCORDING TO SECTION 803 OF THE STANDARD SPECIFICATIONS. IF LOCATING UNDERGROUND CABLE IS NOT INCLUDED AS PART OF THE PLANS, THIS WORK SHALL BE PAID FOR ACCORDING TO ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.
8. SHORT TERM PAVEMENT MARKING SHALL BE APPLIED TO EACH PASS. ONLY THE REMOVAL OF THE FINAL SURFACE APPLICATION WILL BE PAID FOR (WORK ZONE PAVEMENT MARKING REMOVAL - SQ FT). AN AMOUNT OF TEMPORARY PAVEMENT MARKING WHICH EQUALS THE AMOUNT OF PERMANENT PAVEMENT MARKING HAS ALSO BEEN ADDED TO THE PLANS.
9. THE APPLICATION RATE FOR MICRO-SURFACING, TYPE II AND MICRO-SURFACING RUT FILLING, TYPE III SHALL BE 20 LB/SQ YD PER PASS.
10. THE CONTRACTOR SHALL DEVISE AND SUBMIT A JOINT PLAN THAT MEETS THE APPROVAL OF THE RESIDENT ENGINEER AS REQUIRED BY THE SPECIAL PROVISION "MICRO-SURFACING".
11. THE PROPOSED PAVEMENT MARKINGS SHALL BE PLACED IN THE SAME LOCATION AS EXISTING AS DIRECTED BY THE RESIDENT ENGINEER. CARE SHALL BE TAKEN TO ENSURE PAVEMENT MARKING CAN BE REPLICATED BEFORE PAVEMENT MARKING REMOVAL IS COMMENCED.
12. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT THE BEGINNING OF THE PROJECT PLUS THE INTERSECTING SIDEROADS, AND WILL BE CONSIDERED INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE 48" X 48" FLUORESCENT ORANGE.
13. THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

MIXTURE USE	BIT MIX MICRO-SURF.
AC/PG	
RAP % (MAX)	
DESIGN AIR VOIDS	
MIX COMPOSITION	
(GRADATION MIXTURE)	
FRICITION AGG	MIXTURE "D"

INDEX OF SHEETS

- | | |
|------|---|
| 1 | COVER SHEET |
| 2 | INDEX OF SHEETS, GENERAL NOTES
COMMITMENTS & HIGHWAY STANDARDS |
| 3 | SUMMARY OF QUANTITIES |
| 4 | TYPICAL SECTION |
| 5-6 | SCHEDULES OF QUANTITIES |
| 7-17 | PAVEMENT MARKING SHEETS |
| 18 | DETAILS |

HIGHWAY STANDARDS

000001-05	701606-06
001006	701701-06
701001-02	701901-01
701006-03	780001-02
701602-04	781001-03

COMMITMENTS

NONE

FILE NAME =	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES, STANDARDS AND COMMITMENTS	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - ---	REVISED - ---			9122	3Q-ZBS-1	MADISON	18	2
		CHECKED - ---	REVISED - ---			SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____		CONTRACT NO. 76034		
		DATE - -----	REVISED - ---	FED. ROAD DIST. NO. _ [ILLINOIS] FED. AID PROJECT						

Rev.