

PAVEMENT SCHEDULE

LOCATION: STATION TO STATION	PAVEMENT REMOVAL	PCC PAVEMENT 10" (JOINTED)	STABILIZED SUB-BASE 4"	GUTTER REMOVAL	CONCRETE GUTTER, TYPE B	PROTECTIVE COAT	AGGREGATE SHOULDERS, TYPE B 8"
	SQ YD	SQ YD	SQ YD	FOOT	FOOT	SQ YD	SQ YD
IL 37 FAP 726 PULASKI COUNTY							
STA 702+00 TO STA 702+64	171.0	171.0	192.0	64.0	64.0	183.0	28.0
IMPROVEMENT TOTAL:	171.0	171.0	192.0	64.0	64.0	183.0	28.0

CULVERT SCHEDULE

LOCATION: STATION TO STATION	PIPE CULVERT REMOVAL 2-30" RCCP	CONCRETE HEADWALL REMOVAL	PRECAST CONCRETE BOX CULVERT 4' X3'	PRECAST CONCRETE BOX CULVERT END SECTION 4' X3'
	FOOT	EACH	FOOT	EACH
IL 37 FAP 726 PULASKI COUNTY				
STA 702+32		198.0	2.0	123.0
IMPROVEMENT TOTAL:		198.0	2.0	123.0