SCHEDULE OF QUANTITIES

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
206	06-00094-05-DR	MERCER	36	3
STA. 257+10.06		TO STA. 428+35.00		
FED. ROAD DIST. NO. 7		ILLINOIS		

20800150 TRENCH BACKFILL — C.Y.

STA. 283+61 CULVERT REPLACEMENT LOCATION	32
STA. 298+70 CULVERT REPLACEMENT LOCATION	55
STA. 318+16 CULVERT REPLACEMENT LOCATION	90
STA. 345+27 CULVERT REPLACEMENT LOCATION	143
STA. 381+06 CULVERT REPLACEMENT LOCATION	59
STA. 391+83 CULVERT REPLACEMENT LOCATION	50
STA. 403+72 CULVERT REPLACEMENT LOCATION	69
RT. STA. 399+91 ENTRANCE PIPE	2
TOTAL	500

21400100 GRADING AND SHAPING DITCHES — FOOT

RT. STA. 265+54 - 265+89	35
RT. STA. 266+37 - 266+52	15
LT. STA. 270+03 - 270+18	15
LT. STA. 276+59 - 276-89	30
RT. STA. 277+15 - 277+30	15
LT. STA. 277+27 - 278+06	79
LT. STA. 278+64 - 279+25	61
LT. STA. 279+63 - 279+98	35
RT. STA. 280+71 - 281+76	105
LT. STA. 283+61 - 284+31	70
LT. STA. 284+71 - 284+91	20
LT. STA. 290+97 - 291+22	25
LT. STA. 291+60 - 292+00	40
LT. STA. 293+61 - 294+01	40
LT. STA. 294+39 - 294+64	25
RT. STA. 310+40 - 310+65	25
LT. STA. 310+64 - 310+94	30
RT. STA. 311+05 - 311+25	20
RT. STA. 313+55 - 313+75	20
RT. STA. 314+15 - 314+40	25
LT. STA. 315+44 - 315+69	25
RT. STA. 315+41 - 315+66	25
RT. STA. 316+01 - 326+21	20
LT. STA. 316+07 - 316+32	25
RT. STA. 319+22 - 319+32	10
RT. STA. 325+96 - 326+11	15
RT. STA. 328+34 - 328+54	20
RT. STA. 328+90 - 329+20	30
LT. STA. 331+34 - 331+49	15
LT. STA. 331+88 - 332+08	20
RT. STA. 335+74 - 336+34	60
RT. STA. 336+72 - 336+87	15
LT. STA. 336+79 - 336+89	10
LT. STA. 337+31 - 337+41	10
LT. STA. 352+09 - 352+29	20
RT. STA. 352+49 - 352+64	15
LT. STA. 355+10 - 355+20	10
LT. STA. 355+35 - 355+55	20
LT. STA. 355+99 - 356+14	15
RT. STA. 355+98 - 356+23	25
RT. STA. 361+86 - 362+13	35
LT. STA. 374+39 - 374+64	25
LT. STA. 375+06 - 375+26	20
LT. STA. 384+98 - 385+23	35
LT. STA. 385+61 - 385+71	10
LT. STA. 387+92 - 388+27	35
RT. STA. 388+24 - 388+89	65
LT. STA. 388+61 - 389+67	106
RT. STA. 389+27 - 389+77	50
LT. STA. 390+07 - 390+32	25
RT. STA. 400+15 - 400+35	20
LT. STA. 401+30 - 402+00	70
LT. STA. 402+38 - 402+63	25
RT. STA. 414+23 - 415+41	130
RT. STA. 415+94 - 416+61	67
LT. STA. 416+31 - 416+56	25
RT. STA. 416+97 - 417+37	40
LT. STA. 416+94 - 417+09	15
LT. STA. 418+96 - 419+51	55
LT. STA. 419+83 - 420+08	25
LT. STA. 426+69 - 427+49	80
LT. STA. 427+81 - 427+91	10
TOTAL	2,103

25100630 EROSION CONTROL BLANKET — S.Y.

LT. STA. 283+61	8
RT. STA. 283+61	17
LT. STA. 298+70	13
RT. STA. 298+70	17
LT. STA. 318+16	15
RT. STA. 318+16	19
LT. STA. 345+27	27
RT. STA. 345+27	26
LT. STA. 381+01	16
RT. STA. 381+01	8
LT. STA. 391+83	14
RT. STA. 391+83	15
LT. STA. 403+72	12
RT. STA. 403+72	16
TOTAL	223.0

28000250 TEMPORARY EROSION CONTROL SEEDING — POUND

AREAS TO BE CLASS 1 OR 2 SEEDED (2 APPLICATIONS ASSUMED)	150
TOTAL	150

28000305 TEMPORARY DITCH CHECKS — FOOT

LT. STA. 276+60 - 279+98	75
RT. STA. 281+86	25
LT. STA. 291+00	25
RT. STA. 298+48	25
RT. STA. 310+40	25
LT. STA. 310+50	25
RT. STA. 314+40	25
RT. STA. 316+20	25
LT. STA. 316+25	25
RT. STA. 329+20	25
RT. STA. 335+70	25
LT. STA. 344+80	25
RT. STA. 356+20	25
RT. STA. 361+85	25
RT. STA. 374+40	25
LT. STA. 380+91	25
LT. STA. 384+85	25
LT. STA. 388+60 - 390+40	50
RT. STA. 389+80	25
RT. STA. 400+35	25
LT. STA. 401+31	25
RT. STA. 403+43	25
RT. STA. 414+25	25
LT. STA. 418+95	25
LT. STA. 426+70	25
TOTAL	700

28000400 PERIMETER EROSION BARRIER — FOOT

RT. STA. 282+80 - 283+80	100
RT. STA. 318+05 - 318+75	70
LT. STA. 391+65 - 392+00	35
TOTAL	205

28000500 INLET AND PIPE PROTECTION — EACH

RT. STA. 266+38	1
LT. STA. 270+05	1
RT. STA. 277+16	1
LT. STA. 277+28	1
LT. STA. 278+63	1
LT. STA. 279+64	1
LT. STA. 283+60	1
LT. STA. 284+71	1
LT. STA. 291+57	1
LT. STA. 294+40	1
LT. STA. 298+77	1
RT. STA. 311+05	1
LT. STA. 311+34	1
RT. STA. 313+75	1
LT. STA. 315+67	1
RT. STA. 315+71	1
LT. STA. 318+17	1
RT. STA. 319+24	1
RT. STA. 324+59	1
RT. STA. 326+06	1
RT. STA. 328+50	1
LT. STA. 331+47	1
RT. STA. 336+74	1
LT. STA. 337+31	1
RT. STA. 345+56	1
LT. STA. 352+26	1
RT. STA. 352+63	1
RT. STA. 355+19	1
LT. STA. 355+54	1
LT. STA. 375+00	1
RT. STA. 381+06	1
LT. STA. 385+62	1
LT. STA. 388+27	1
RT. STA. 388+87	1
LT. STA. 389+68	1
RT. STA. 391+84	1
RT. STA. 399+75	1
LT. STA. 402+38	1
LT. STA. 403+97	1
RT. STA. 415+91	1
LT. STA. 416+94	1
RT. STA. 416+97	1
LT. STA. 419+83	1
LT. STA. 427+81	1
TOTAL	44

28100105 STONE RIPRAP, CLASS A3 — S.Y.

RT. STA. 283+62	1.7
RT. STA. 298+70	1.7
RT. STA. 318+16	1.7
RT. STA. 345+27	1.7
LT. STA. 381+06	1.7
LT. STA. 391+83	1.7
TOTAL	10.2

35800200 AGGREGATE BASE REPAIR — TON

RT. STA. 427+30-428+05	20
TOTAL	20

SCHEDULE OF QUANTITIES
SECTION 06-00094-05-DR
F.A.S. RTE. 206, STA. 257+10.06 TO 428+35.00
RICHLAND GROVE TOWNSHIP
MERCER COUNTY