

# SUMMARY OF QUANTITIES

FAU RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982	*	SANGAMON	68	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 09-00447-03-PV		CITY OF SPRINGFIELD		

CODE NO.	ITEM DESCRIPTION	UNIT	URBAN	ROADWAY		LANDSCAPING	TRAFFIC SIGNALS
				TOTAL QUANTITY	CAPITOL AVENUE 09-00447-03-PV STA. 42+11.00 TO STA. 49+62.70	CAPITOL AVENUE 09-00447-03-PV	CAPITOL AVENUE 09-00447-03-PV
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	24.3	24.3			
(S) 78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	53	53			
(S) 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	110	110			
(S) 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	36	36			
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	105				105
* 81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	251				251
* 81021520	CONDUIT AUGERED 1" DIA., PVC	FOOT	64			64	
81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	4				4
81603010	UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA, POLYETHYLENE	FOOT	500				500
* 81900205	TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)	FOOT	356				356
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	514				514
* 87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 9C	FOOT	269				269
* 87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 12C	FOOT	270				270
* 87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3 C	FOOT	28				28
* 87501100	TRAFFIC SIGNAL POST, 15 FT.	EACH	4				4
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	28				28
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3.5				3.5
88040070	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	6				6
88040230	SIGNAL HEAD ,POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2				2
88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8				8
* 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	10				10
* 89000105	TEMPORARY TRAFFIC SIGNAL INSTALLATION (SPECIAL)	EACH	1				1
* 89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1				1
* 89502380	REMOVE EXISTING HANDHOLE	EACH	3				3
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	8				8
* A2004824	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 3" CALIPER, BALLED AND BURLAPPED	EACH	4			4	

\* PAY ITEM REQUIRES A SPECIAL PROVISION

(S) DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

FAU RTE 7982 CAPITOL AVE  
SEC NO. 09-00447-03-PV  
SANGAMON COUNTY, ILLINOIS

SCALE: VERT.  
HORIZ.  
DATE 10/9/09

DRAWN BY TCJ  
CHECKED BY MH



LAYOUT TCJ 02/27/01  
 DRAWN TCJ 02/27/01  
 REVIEWED MH / /  
 PLOT DATE = 11/24/2009  
 FILE NAME = I:\02\job\02262941\A\000\Road\Microstation\Sheet\Section\_2\_5\h\7h\c-004\_500.dgn  
 PLOT SCALE = 50.000 / 1"  
 USER NAME = Hagan0901