

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982		SANGAMON	68	12
STA.	TO STA.			
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
09-00447-03-PV		CITY OF SPRINGFIELD		

UTILITY ADJUSTMENT SCHEDULE

LOCATION	EXISTING ELEVATION	PROPOSED ELEVATION	ELEVATION DIFFERENCE	MANHOLES TO BE ADJUSTED EACH	FRAMES AND LIDS TO BE ADJUSTED EACH	NOTES		
MIDBLOCK OF 5TH ST. AND 6TH ST.								
42+13.18	16.54'	RT	590.07	590.04	-0.03	1	SEWER	
42+17.90	22.42'	RT	589.89	589.80	-0.09	1	ELECTRIC	
42+20.83	3.19'	RT	590.49	590.39	-0.10	1	TELEPHONE	
42+40.57	9.86'	RT	590.29	590.10	-0.19		1	WATER VALVE
42+46.76	6.00'	LT	590.56	590.32	-0.24	1	SEWER	
43+19.34	28.32'	RT	590.86	591.12	0.26		1	GAS VALVE
43+25.05	7.18'	RT	591.30	591.21	-0.09		1	WATER VALVE
44+32.82	5.86'	LT	592.38	592.09	-0.29	1	SEWER	
44+35.37	29.28'	RT	592.17	592.20	0.03		1	GAS VALVE
44+36.52	25.73'	RT	592.09	592.17	0.08		1	WATER VALVE
44+37.55	27.68'	RT	592.14	592.18	0.04		1	WATER VALVE
44+37.76	20.27'	LT	592.12	592.18	0.06	1	ELECTRIC	
44+40.62	27.33'	RT	592.16	592.17	0.01		1	GAS VALVE
44+42.00	25.93'	RT	592.13	592.16	0.03		1	WATER VALVE
44+43.77	26.90'	RT	592.16	592.16			1	WATER VALVE
44+47.21	21.09'	RT	591.96	592.03	0.07	1	ELECTRIC	
44+50.27	28.36'	LT	592.34	592.35	0.01		1	GAS VALVE
44+60.88	11.83'	LT	592.18	591.86	-0.32		1	WATER VALVE
45+18.69	26.49'	RT	591.53	591.86	0.33		1	GAS VALVE
SUBTOTAL						7	12	
6TH ST. INTERSECTION								
45+70.53	40.10'	RT	591.41	591.40	-0.01		1	GAS VALVE
45+76.94	18.09'	RT	591.22	591.04	-0.18	1	ELECTRIC	
45+82.23	7.61'	RT	591.54	591.28	-0.26	1	TELEPHONE	
45+86.42	31.06'	LT	591.67	591.46	-0.21	1	CMS	
45+89.46	20.47'	RT	591.41	591.25	-0.16	1	N/A	
45+91.85	6.79'	LT	591.67	591.45	-0.22	1	FIBER OPTIC	
45+97.55	22.74'	RT	591.46	591.24	-0.22		1	WATER VALVE
46+07.19	25.51'	RT	591.28	591.10	-0.18	1	SEWER	
46+07.55	9.24'	LT	591.81	591.45	-0.36	1	SEWER	
46+08.22	48.25'	LT	591.97	591.89	-0.08	1	SEWER	
46+11.83	30.57'	RT	591.08	590.96	-0.12		1	WATER VALVE
46+13.12	2.06'	LT	591.78	591.39	-0.39		1	WATER VALVE
46+25.13	19.49'	RT	591.06	590.91	-0.15	1	ELECTRIC	
46+26.07	14.63'	LT	591.62	591.24	-0.38	1	ELECTRIC	
46+46.22	7.46'	LT	591.71	591.03	-0.68		1	GAS VALVE
SUBTOTAL						10	5	
MIDBLOCK OF 6TH ST. AND 7TH ST.								
47+89.21	15.91'	RT	591.57	591.23	-0.34		1	WATER VALVE
47+95.65	30.73'	RT	591.33	591.44	0.11		1	GAS VALVE
48+03.46	0.28'	LT	592.32	591.90	-0.42	1	SEWER	
48+07.45	9.13'	RT	592.04	591.68	-0.36	1	N/A	
48+10.19	20.02'	LT	592.11	592.07	-0.04	1	ELECTRIC	
48+11.58	21.99'	RT	591.64	591.57	-0.07	1	ELECTRIC	
48+12.26	35.32'	RT	591.55	591.58	0.03		1	GAS VALVE
48+44.64	30.14'	LT	592.89	592.79	-0.10		1	WATER VALVE
48+55.91	30.25'	RT	592.75	592.64	-0.11		1	GAS VALVE
48+93.81	7.36'	RT	593.61	593.28	-0.33		1	WATER VALVE
49+36.77	29.97'	LT	594.71	594.96	0.25		1	GAS VALVE
SUBTOTAL						4	7	
TOTAL						21	24	

**FIRE HYDRANT SCHEDULE
LOCATION INFORMATION FOR CONTRACTOR
WORK TO BE COMPLETED BY CWLP**

LOCATION	FIRE HYDRANTS TO BE REMOVED	FIRE HYDRANTS
CAPITOL AVENUE 5TH STREET - 6TH STREET		
43+34.56	26.00' LT	
43+34.56	26.00' RT	
44+65.22	26.00' RT	
44+65.00	22.00' LT	1
45+20.00	22.00' RT	1
SUBTOTAL		
CAPITOL AVENUE/6TH STREET INTERSECTION		
46+28.57	48.08' RT	1
46+28.57	48.08' RT	1
SUBTOTAL		
CAPITOL AVENUE 6TH STREET - 7TH STREET		
47+37.25	26.00' LT	
47+37.25	26.00' RT	
47+74.25	26.00' RT	
47+83.80	30.09' RT	1
48+25.00	22.00' LT	1
48+67.70	26.00' LT	
48+67.70	26.00' RT	
SUBTOTAL		
TOTAL		

**WATER HYDRANT SCHEDULE
WORK BY CONTRACTOR**

LOCATION	WATER HYDRANT EACH	COPPER SERVICE TYPE K 3/4" FOOT	4" PVC CASING PIPE FOOT	TRENCH BACKFILL CU YD
CAPITOL AVENUE 5TH STREET - 6TH STREET				
43+34.56	1	55	52	9.2
43+34.56	1			
44+65.22	1			
44+65.00				
45+20.00				
SUBTOTAL				
CAPITOL AVENUE/6TH STREET INTERSECTION				
46+28.57				
46+28.57				
SUBTOTAL				
CAPITOL AVENUE 6TH STREET - 7TH STREET				
47+37.25	1	55	52	9.2
47+37.25	1			
47+74.25				
47+83.80				
48+25.00				
48+67.70	1	55	52	9.2
48+67.70	1			
SUBTOTAL				
TOTAL				

**LIGHTING SCHEDULE
LOCATION INFORMATION FOR CONTRACTOR
WORK TO BE COMPLETED BY CWLP**

LOCATION	REMOVE EXISTING LIGHT POLE	VENDOR ACCESS HANDHOLE	ORNAMENTAL PEDESTRIAN LIGHT	ORNAMENTAL STREET LIGHT	NOTES
CAPITOL AVENUE 5TH STREET - 6TH STREET					
42+56.76	24.63' LT				
42+58.84	25.04' RT				
43+27.55	26.00' RT			1	
43+27.55	26.00' LT			1	
44+00.79	25.53' RT				
44+01.04	24.29' LT			1	
44+72.22	26.00' RT				
45+37.58	24.71' LT			1	
45+42.12	25.35' RT			1	
SUBTOTAL		6		3	
CAPITOL AVENUE/6TH STREET INTERSECTION					
45+75.63	46.60' RT			1	
SUBTOTAL				1	
CAPITOL AVENUE 6TH STREET - 7TH STREET					
46+56.00	28.53' RT			1	
46+69.78	29.26' LT			1	
46+92.06	30.35' RT			1	
46+99.54	30.43' LT			1	
47+29.73	30.42' LT			1	
47+30.25	26.00' RT				1
47+30.25	26.00' LT				1
47+41.28	30.42' RT			1	
47+77.98	30.27' RT			1	
48+06.00	29.91' LT			1	
48+22.09	28.01' RT			1	
48+35.26	30.13' RT			1	
48+74.70	26.00' RT				1
48+74.70	26.00' LT				1
48+77.90	30.30' RT			1	
49+07.98	30.11' RT			1	
49+38.27	30.22' RT			1	
49+47.55	31.07' RT			1	
49+92.83	28.97' LT			1	
SUBTOTAL		15		4	
TOTAL		22		7	

SEE STREETScape PLANS



LAYOUT: TCJ 03/21/04
 DRAWN: TCJ 03/27/07
 REVIEWED: MH / /
 PLOT DATE: 11/29/2009
 FILE NAME: I:\2009\2252\04\1\CA001\Road\Microstation\Sheet\Section_2_5th-7th\VC-005_SCH.DGN
 PLOT SCALE: 1/8"=1'-0"
 USER NAME: Hejmen@951

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAU RTE 7982 CAPITOL AVE
 SEC NO. 09-00447-03-PV
 SANGAMON COUNTY, ILLINOIS
 SCALE: VERT. / HORIZ.
 DATE 10/9/09
 DRAWN BY TCJ
 CHECKED BY MH