

SUMMARY OF QUANTITIES

CITY OF MATTOON
SECTION 09-00182-00-RS
VARIOUS F.A.U. ROUTES
JOB#: C-97-030-10
PROJECT#: ARA-M-5042(018)
CONTRACT #: 95610
COLES COUNTY
SHEET 3 OF 54

<i>ITEM #</i>	<i>PAY ITEM</i>	<i>UNIT</i>	<i>QUANTITY</i>
XX003140	SHORT - TERM PAVEMENT MARKING REMOVAL	FOOT	2,000.00
XX004847	STONE DRIVEWAY REMOVAL	SQ. YDS.	130.70
XX006935	BRICK SURFACE REMOVAL - BUTT JOINT	SQ. YDS.	86.60
X0325599	PARTIAL DEPTH PATCHING 2"	TON	41.50
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	LUMP SUM	1.00
Z0048665	RAIL ROAD PROTECTIVE LIABILITY INSURANCE	LUMP SUM	1.00
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,929.00
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1,295.00
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ. YDS.	2,243.80
40603310	HOT-MIX ASPHALT SURFACE COURSE MIX "C", N50	TON	3,366.00
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	33.00
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ. FT.	1,268.00
44000157	HOT-MIX ASPHALT SURFACE REMOVAL 2"	SQ. YDS.	4,973.50
44000161	HOT-MIX ASPHALT SURFACE REMOVAL 3"	SQ. YDS.	569.10
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	317.00
44000600	SIDEWALK REMOVAL	SQ. FT.	951.00
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	219.00
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SQ. YDS.	3.10
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ. YDS.	7.80
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ. YDS.	44.40
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ. YDS.	34.10
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ. YDS.	16.50
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1.00
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3.00
60300350	MANHOLE FRAMES TO BE ADJUSTED	EACH	49.00
60609200	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12	FOOT	317.00
67100100	MOBILIZATION	LUMP SUM	1.00
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	LUMP SUM	1.00
70300100	SHORT - TERM PAVEMENT MARKING	FOOT	2,000.00
* 78000100	THERMO PLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ. FT.	328.00
* 78000200	THERMO PLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15,494.00
* 78000400	THERMO PLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,821.00
* 78000650	THERMO PLASTIC PAVEMENT MARKING - LINE 24"	FOOT	643.00

* SPECIALTY ITEMS