

SCHEDULE OF QUANTITIES

F.A.U. 7685 /32ND STREET

CITY OF MATTOON

SECTION 09-00182-00-RS

ROUTE: F.A.U. 7685

32ND STREET

JOB#: C-97-030-10

PROJ#: ARA-M-5042(018)

CONTRACT#: 95610

COLES COUNTY

SHEET 21 OF 54

40600100 BITUMINOUS MATERIALS (PRIME COAT)

Lt.~Rt., 200+00~218+77 = 250 GALLON

TOTAL = 250 GALLON

40600625 LEVELING BINDER (MACHINE METHOD), N50

11.5' Lt. ~ Rt., 200+00 ~ 218+77 = 198 TON

11.5' - 48' Lt., 200+00 ~ 200+40 = 3 TON

11.5' - 46' Rt., 200+00 ~ 200+40 = 3 TON

11.5' - 20' Lt., 218+34 ~ 218+77 = 2 TON

11.5' - 20' Rt., 218+34 ~ 218+77 = 2 TON

TOTAL = 208 TON

40603310 HOT-MIX ASPHALT SURFACE COURSE MIX "C" N50

11.5' Lt. ~ Rt., 200+00 ~ 217+77 = 396 TON

SAG @ 204+12 ~ 204+78 = 22 TON

11.5' - 48' Lt., 200+00 ~ 200+40 = 5 TON

11.5' - 46' Rt., 200+00 ~ 200+40 = 5 TON

11.5' - 20' Lt., 218+34 ~ 218+77 = 4 TON

11.5' - 20' Rt., 218+34 ~ 218+77 = 4 TON

TOTAL = 436 TON

44000157 HOT MIX ASPHALT SURFACE REMOVAL 2"

48' Lt.~46'Rt., 200+00 ~ 20'Lt.~Rt., 200+40 = 220.7 SQ.YDS.

11.5' Lt.~Rt., 200+40 ~ 204+03 = 927.7 SQ.YDS.

11.5' Lt.~Rt., 204+12 ~ 218+34 = 3,634.0 SQ.YDS.

20' Lt.~Rt., 218+34 ~ 218+77 = 191.1 SQ.YDS.

TOTAL = 4,973.5 SQ.YDS.

44201761 CLASS D PATCHES, TYPE 1, 10 INCH

10'~19' Lt., 200+04 ~ 200+09 = 5.0 SQ. YDS.

TOTAL = 5.0 SQ. YDS.

60300350 MANHOLE FRAMES TO BE ADJUSTED

30' Lt., 200+02 = 1.0 EACH

CL, 204+39 = 1.0 EACH

CL, 206+70 = 1.0 EACH

1' Lt., 211+45 = 1.0 EACH

CL, 215+19 = 1.0 EACH

TOTAL = 5.0 EACH

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

RR CROSSING SYMBOLS 11+32.5 = 122.4 SQ. FT.

TOTAL = 122.4 SQ. FT.

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

YELLOW CL. 200+29 ~ 218+36 = 450 FOOT

WHITE 11' Lt. & Rt., 200+29 ~ 218+36 = 3614 FOOT

TOTAL = 4064 FOOT

78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"

25' Lt.~Rt., 200+16 = 50 FOOT

21' Lt.~Rt., 200+22 = 42 FOOT

20' Lt.~Rt., 218+43 = 40 FOOT

20' Lt.~Rt., 218+49 = 40 FOOT

TOTAL = 172 FOOT

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"

CL. ~ 20' Lt., 200+27 = 20.0 FOOT

CL. ~ 11.5' Rt., 203+20 = 11.5 FOOT

CL. ~ 11.5' Rt., 203+70 = 11.5 FOOT

CL. ~ 11.5' Rt., 203+90 = 11.5 FOOT

CL. ~ 11.5' Lt., 204+30 = 11.5 FOOT

CL. ~ 11.5' Lt., 204+50 = 11.5 FOOT

CL. ~ 11.5' Lt., 205+27 = 11.5 FOOT

CL. ~ 20' Rt., 218+38 = 20.0 FOOT

TOTAL = 109.0 FOOT