

SCHEDULE OF QUANTITIES

F.A.U. 7699 / 6TH STREET

CITY OF MATTOON

SECTION 09-00182-00-RS

ROUTE: F.A.U. 7699
6TH STREET

JOB#: C-97-030-10

PROJ#: ARA-M-5042(018)

CONTRACT#: 95610

COLES COUNTY

SHEET 53 OF 54

X0325599 PARTIAL DEPTH PATCHING 2"

9.5'~13.5' Rt., 500+18 ~ 500+52 = 2 TON
TOTAL = 2 TON

40600100 BITUMINOUS MATERIALS (PRIME COAT)

Lt.~Rt., 500+00~506+05.5 = 96 GALLON
TOTAL = 96 GALLON

40600625 LEVELING BINDER (MACHINE METHOD), N50

12.5' Lt. - Rt., 500+25 ~ 502+10 = 22 TON
11.5' Lt. - Rt., 502+74 ~ 505+93 = 34 TON
12.5'~21'Rt., 502+96 ~ 505+90 = 12 TON
TOTAL = 68 TON

40600982 HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT (1-1/4)

13.5'Lt. ~ Rt., 500+00 ~ 500+25 = 75.0 SQ. YDS.
13.5'Lt. ~ Rt., 502+10 ~ 502+22 = 36.0 SQ. YDS.
12.5'Lt. ~ Rt., 502+62 ~ 502+74 = 33.3 SQ. YDS.
12.5'Lt. ~ Rt., 505+93 ~ 506+05.5 = 34.7 SQ. YDS.
TOTAL = 179.0 SQ. YDS.

40603310 HOT-MIX ASPHALT SURFACE COURSE MIX "C" N50

13.5 Lt. - Rt., 500+00 ~ 502+22 = 47 TON
4 RADIUS @ BROADWAY AVE = 2 TON
12.5' Lt. - Rt., 502+62 ~ 506+05.5 = 66 TON
12.5'~21'Rt., 502+96 ~ 505+90 = 20 TON
TOTAL = 135 TON

44001700 COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT

13.5'Rt., 500+22 ~ 500+58 = 36 FOOT
19'Rt., 502+64 ~ 14'Rt., 502+86 = 24 FOOT
TOTAL = 60 FOOT

44201765 CLASS D PATCHES, TYPE 2, 10 INCH

C~L - 13.5'Lt., 500+48 ~ 500+53 = 7.5 SQ. YDS.
C~L - 13.5'Rt., 501+13 ~ 501+17 = 6.0 SQ. YDS.
TOTAL = 13.5 SQ. YDS.

60300350 MANHOLE FRAMES TO BE ADJUSTED

C~L, 502+89 = 1.0 EACH
18' Rt., 503+91 = 1.0 EACH
TOTAL = 2.0 EACH

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

YELLOW CL.500+00~502+22 = 50 FOOT
CL 502+62~506+05.5 = 80 FOOT

WHITE 12.5'Rt., 502+96~505+90 = 294 FOOT
12.5'~21'Rt., 503+03 = 8.5 FOOT
12.5'~21'Rt., 503+23 = 8.5 FOOT
12.5'~21'Rt., 503+43 = 8.5 FOOT
12.5'~21'Rt., 503+63 = 8.5 FOOT
12.5'~21'Rt., 503+83 = 8.5 FOOT
12.5'~21'Rt., 504+03 = 8.5 FOOT
12.5'~21'Rt., 504+23 = 8.5 FOOT
12.5'~21'Rt., 504+43 = 8.5 FOOT
12.5'~21'Rt., 504+63 = 8.5 FOOT
12.5'~21'Rt., 504+83 = 8.5 FOOT
12.5'~21'Rt., 505+03 = 8.5 FOOT
12.5'~21'Rt., 505+23 = 8.5 FOOT
12.5'~21'Rt., 505+43 = 8.5 FOOT
12.5'~21'Rt., 505+63 = 8.5 FOOT
TOTAL = 543 FOOT

78000400 THERMOPLASTIC PAVEMENT MARKING - LINE 6"

13.5'Lt.~Rt., 501+91 = 27 FOOT
13.5'Lt.~Rt., 501+97 = 27 FOOT
12.5'Lt.~Rt., 502+87 = 25 FOOT
12.5'Lt.~Rt., 502+93 = 25 FOOT
TOTAL = 104 FOOT

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"

CL~13.5'Lt., 501+85 = 13.5 FOOT
CL~13.5'Rt., 502+98 = 13.5 FOOT
TOTAL = 27.0 FOOT