

PAVING SCHEDULE

LOCATION	BIT MATL PR CT (GALLON)	AGG. BASE COURSE TYPE A 4 IN (SQ YD)	HOT-MIX ASPHALT BASE COURSE WIDENING, 8" (SQ YD)	HOT-MIX ASPHALT SURF CSE, MIX C, N70, 2" (TON)	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70 (TON)
OHIO AVENUE					
STA. 101+19.57 LT TO STA. 108+59.70 LT	80.9	632.8	509.2	130.0	48.5
STA. 109+18.52 - 4.99' LT TO STA. 109+18.29 - 55.15' LT	2.9	49.8	41.4	4.6	0.0
TOTAL	84	683	551	135	49

STRIP REFLECTIVE CRACK CONTROL SCHEDULE

LOCATION	LENGTH (FOOT)
OHIO AVENUE	
STA. 101+25.87 - 81.51' LT TO STA. 107+88.66 - 31.97' LT	677
TOTAL	677

TEMPORARY CONCRETE BARRIER SCHEDULE

LOCATION	TEMPORARY CONCRETE BARRIER (TO REMAIN PERMANENTLY) (FOOT)	TEMPORARY CONCRETE BARRIER TERMINAL SECTION (SPECIAL) (EACH)	BARRIER WALL MARKERS, TYPE C (EACH)
OHIO AVENUE			
STA. 101+52.51 - 51.92' LT TO STA 102+99.87 - 26.80' LT	150	2	20
STA. 103+88.28 - 26.50' LT TO STA. 104+00.94 - 26.51' LT	12.5	2	8
STA. 104+88.92 - 26.04' LT TO STA. 106+53.58 - 25.50' LT	162.5	2	22
STA. 107+29.84 - 25.60' LT TO STA. 107+80.34 - 28.87' LT	50	2	10
TOTAL	375	8	60

COMBINATION CURB AND GUTTER SCHEDULE

LOCATION	COMBINATION CONCRETE CURB & GUTTER TYPE B-6.24 (FOOT)
OHIO AVENUE	
STA. 107+88.80 - 30.43' LT TO STA 108+00.79 - 31.66' LT	12.0
STA. 108+42.11 - 47.26' LT TO STA. 108+57.62 - 63.01' LT	22.2
TOTAL	34

PATCHING SCHEDULE

LOCATION	SIZE			PAVEMENT PATCHING CLASS D PATCHES
	LENGTH	X	WIDTH	TYPE I 8 IN (SQ YD)
	(FOOT)		(FOOT)	
OHIO AVENUE				
STA. 102+97.90 - 26.01' LT TO STA. 103+03.08 - 26.01' LT	5.2	X	1.8	1.0
TOTAL				1.0

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-) (CU YD)
OHIO AVENUE	203	153	22	(+) 131
TOTAL	203	153	22	131

NOTE: BASED ON 25% SHRINKAGE

ENTRANCE SCHEDULE

LOCATION	"W" WIDTH (FT)	PCC DRIVEWAY PAVEMENT	PROTECTIVE COAT (SQ YD)	AGGREGATE SURFACE COURSE	"Y" DISTANCE (FT)
		8 IN. (SQ YD)		TYPE A 8 IN. (SQ YD)	
OHIO AVENUE					
CE @ 103+46.79 - LT	30.3	64.3	64.3		17.5
CE @ 104+41.97 - LT	30.0	63.7	63.7		17.5
CE @ 106+98.29 - LT	24.0			37.5	13.9
TOTAL		128	128	38	

PAVEMENT MARKING SCHEDULE

LOCATION	TYPE	THERMOPLASTIC PAVEMENT MARKINGS		PREFORMED PLASTIC PAVEMENT MARKINGS
		6" WHITE (FOOT)	6" YELLOW (FOOT)	12" WHITE (FOOT)
OLD MADISON ROAD				
	CROSSWALK	115		
	STOP BARS			24
	BARRIER EDGE		438	
TOTAL		115	438	24

PLAN SURVEYED, PLOTTED, CHECKED, REVISIONS, DATE, BY, NOTE BOOK NO., CADD FILE NAME

PROFILE SURVEYED, PLOTTED, CHECKED, REVISIONS, DATE, BY, NOTE BOOK NO., STRUCTURE NOTATIONS CHECKED