INLET SCHEDULE

STRUCTURE ID	LOCATION	INLETS SPECIAL (EACH)
	OHIO AVENUE	
H-01	STA. 103+04.82 - 43.25' LT	1
	TOTAL	1

PERIMETER EROSION BARRIER SCHEDULE

LOCATION	PERIMETER EROSION BARRIER (FOOT)
OHIO AVENUE	
STA. 109+24.31 - 5.02' LT TO STA. 109+24.09 - 55.18' LT	50.2
TOTAL	50

INLET AND PIPE PROTECTION SCHEDULE

LOCATION	DISTANCE (FOOT)	INLET PIPE PROTECTOR (EACH)
OHIO AVENUE		
STA. 103+04.82 LT	43.25	1
STA. 104+20.60 LT	45.81	1
STA. 104+62.16 LT	44.78	1
STA. 109+31.86 LT	49.28	1
TOTAL		4

PIPE UNDERDRAIN SCHEDULE

LOCATION	PIPE UNDERDRAINS 6" (FOOT)
OHIO AVENUE	
STA. 102+94.61 - 39.32' LT TO STA. 102+94.76 - 41.41' LT	2
TOTAL	2

RELOCATE SIGN PANEL SCHEDULE

EXISTING LOCATION	PROPOSED LOCATION	REMOVE SIGN PANEL TYPE 1 (SQ FT)	RELOCATE SIGN PANEL TYPE 1 (SQ FT)	METAL POST TYPE A (FOOT)	METAL POST TYPE B (FOOT)
OHIO AVENUE					
STA. 102+78.59 - 37.17' LT	STA. 102+78.59 - 40.75' LT	1.5	1.5	12.0	
STA. 108+56.63 - 66.13' LT	STA. 108+57.93 - 70.66' LT	6.25	6.25		13.5
TOTAL		8	8	12	14

SEEDING SCHEDULE

LOCATION	SEEDING CLASS 2A (AC)	TEMPORARY SEEDING (LB)	NITROGEN FERT NUTR (LB)	PHOSPHORUS FERT NUTR (LB)	POTASSIUM FERT NUTR (LB)	MULCH METHOD 2 (AC)
OHIO AVENUE						
STA. 101+12.02 TO STA. 151+94.35	0.1	10.0	9.0	9.0	9.0	0.1
TOTAL	0.1	10	9	9	9	0.1

HEADWALL RELOCATION SCHEDULE

EXISTING LOCATION	PROPOSED LOCATION	REMOVE AND REINSTALL CONCTERE HEADWALL FOR PIPE UNDERDRAINS (EACH)
OHIO AVENUE		
STA. 102+94.81 - 41.93' LT	STA. 102+94.99 - 43.90' LT	1
TOTAL		1

DETECTABLE WARNINGS SCHEDULE

LOCATION	DETECTABLE WARNINGS (SQ FT)
OHIO AVENUE	
STA. 101+28.27 - 67.39' LT TO STA. 101+34.83 - 64.43' LT	13.78
STA. 108+45.05 - 53.57' LT TO STA. 108+52.79 - 58.58' LT	18
STA. 109+08.90 - 36.33' LT TO STA. 109+10.95 - 45.09' LT	18
TOTAL	50

PLAN | SURVEYED | PLOTTED | ALIGNMENT CHECKED | RT. OF WAY CHECKED | PLOD FILE NAME | NOTE BOOK | NO. | BY | DATE

PROFILE | SURVEYED | PLOTTED | GRADES CHECKED | B.M. NOTED | STRUCTURE NOTATIONS CHKD | NOTE BOOK | NO. | BY | DATE

FILE NAME = combschd ohio	USER NAME = jeremy	DESIGNED - BFK	REVISED -	OHIO AVENUE PEDESTRIAN WALKWAY MADISON, ILLINOIS	QUANTITY SCHEDULES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
		DRAWN - JJB	REVISED -				09-00049-01-SW	ST. CLAIR	26 / 9
	PLOT SCALE = $SCALE$	CHECKED - BFK	REVISED -					CONTRACT NO. 97420	
	PLOT DATE = 12/18/2009	DATE - 10/01/09	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT		