


F. A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 9452	08-00059-00-RP	FRANKLIN	39	1
NORTH DUQUOIN STREET			CONTRACT NO. 99396	


SCALE IN FEET



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLANS FOR
PROPOSED NORTH DUQUOIN STREET IMPROVEMENTS
F.A.U. ROUTE 9452
AMERICAN RECOVERY AND REINVESTMENT ACT 2009

CITY OF BENTON
SECTION 08-00059-00-RP
FRANKLIN COUNTY, ILLINOIS
PROJECT: ARA-M-5005(011)
JOB: C-99-509-09



JOINT UTILITY LOCATING INFORMATION
FOR EXCAVATIONS (J.U.L.I.E.)
PHONE 1-800-892-0123

SHEET NO.	TITLE
1.	COVER SHEET
2.	TYPICAL SECTIONS, MISCELLANEOUS DETAILS, LEGEND
3.	SUMMARY OF QUANTITIES, GENERAL NOTES
4.	STORM WATER POLLUTION PREVENTION PLAN
5.-12.	PLAN AND PROFILE
13.-20.	REMOVAL AND REPLACEMENT MISCELLANEOUS SCHEDULES
21.	PAVEMENT MARKING PLAN
22.	TRAFFIC CONTROL AND PROTECTION PLAN
23.-39.	CROSS SECTIONS

FUNCTIONAL CLASSIFICATION: LOCAL STREET
ADT (2010): 1,060
ADT (2030): 1,300
DESIGN SPEED: 30

STANDARDS:

280001-05	TEMPORARY EROSION CONTROL SYSTEMS
420001-07	PAVEMENT JOINTS
424001-05	CURB RAMPS FOR SIDEWALKS
602301-02	INLET, TYPE A
604001-03	FRAME AND LIDS, TYPE 1
602701-02	MANHOLE STEPS
606201-02	TYPE B GUTTER (INLET, OUTLET & ENTRANCE)
606001-04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
604036-02	TYPE 8 GRATE
701501-05	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
720001-01	SIGN PANEL MOUNT DETAILS
720006-02	SIGN PANEL ERECT DETAILS
731001-01	BASE FOR TELESCOPING STEEL SIGN SUPPORT
780001-02	TYPICAL PAVEMENT MARKINGS
B.L.R. 10-6	PCC PAVEMENT SPECIAL
B.L.R. 26-2	STEEL PLATE BEAM GUARDRAIL




CONTRACT NO. 99396

NOTE: THE LOCATIONS AND SIZES OF EXISTING UTILITIES ARE SHOWN WITH THE BEST AVAILABLE INFORMATION. ACTUAL LOCATIONS, SIZES AND DEPTHS MAY VARY. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE LOCATION OF ALL UTILITIES PRIOR TO CONSTRUCTION.

ALL UTILITY POLES WITHIN 2 FT. OF THE FACE OF PROPOSED CURB SHALL BE RELOCATED, BY OTHERS.


CITY OF BENTON	
Approved: 12-11	20 09
<i>Mary Kraft</i> Local Agency, Mayor	
Passed: 12-14	20 09
<i>Richard W. Mellicke</i> District #9 Engineer of Local Roads & Streets	
Releasing for Bid Based on Limited Review: 12-14	20 09
<i>Mary C. Lemie</i> Deputy Director of Highways, Region #5 Engineer	

Trent J. McPeak
Trent J. McPeak
Illinois Licensed Professional
Engineer No. 062-052906
12-11-2009
Date
License Expires 11-30-2011




LOCATION MAP

LENGTH OF IMPROVEMENT = 3,479 FEET (0.659 MILES)



EXISTING TYPICAL SECTION TO BE REMOVED:
Sta. 2+20 to 25+35




PROPOSED TYPICAL SECTION:
Sta. 2+20 to 25+35

STRUCTURAL DESIGN


CLASS IV STREET
DESIGN PERIOD, 20 YEARS
STRUCTURAL DESIGN TRAFFIC (S.D.T.) YEAR 2030 - 1,300
P.V. 1.235 S.U. 50 M.U. 15

SOIL SUPPORT VALUE I.B.R. - 3.1
TRAFFIC FACTOR (T.F.) - 0.5

PAVEMENT STRUCTURE MATERIALS
BLR 10-6, P.C.C. PAVEMENT, SPECIAL 8.00\"/>



EXISTING TYPICAL SECTION TO BE REMOVED:
Sta. 25+35 to 36+99






PROPOSED TYPICAL SECTION:
Sta. 25+35 to 36+99

STRUCTURAL DESIGN

CLASS IV STREET
DESIGN PERIOD, 20 YEARS
STRUCTURAL DESIGN TRAFFIC (S.D.T.) YEAR 2030 - 1,230
P.V. 1.165 S.U. 50 M.U. 15

SOIL SUPPORT VALUE I.B.R. - 3.1
TRAFFIC FACTOR (T.F.) - 0.5

PAVEMENT STRUCTURE MATERIALS
BLR 10-6, P.C.C. PAVEMENT, SPECIAL 8.00\"/>




NOTES:

CLASS S1 CONCRETE SHALL BE USED THROUGHOUT. SET FACE OF INLET 1\"/>

INLETS WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR INLET, SPECIAL, TYPE 3, 5 FEET WHICH PRICE SHALL INCLUDE THE CAST IRON FRAME, SPECIAL, TYPE 1 WITH TYPE 1 CLOSED LID, THE REINFORCEMENT BARS, METAL STEPS AND JOINT FILLER.




WHEN GALV. IRON STEPS AS DETAILED HEREIN ARE TYPICAL STEPS OF OTHER DESIGN AND MATERIAL THAT WILL CONFORM TO THE MINIMUM REQUIREMENTS OF THE STEPS SHOWN, MAY BE USED WHEN APPROVED BY THE ENGINEER.

INLETS MAY BE PRECAST WHEN APPROVED BY THE ENGINEER.



DETAILS OF INLET SPECIAL, TYPE 3, 5 FEET AND 6 FEET

DESIGN	PIPE DIAM.	*D*
A	18\"/>	




NOTES:

CLASS S1 CONCRETE SHALL BE USED THROUGHOUT. SET FACE OF INLET 1\"/>



INLETS WILL BE PAID FOR AT THE CONTRACT UNIT PRICE EACH FOR INLET, SPECIAL, TYPE 1 WITH TYPE 1 CLOSED LID, THE REINFORCEMENT BARS, METAL STEPS AND JOINT FILLER.

WHEN GALV. IRON STEPS AS DETAILED HEREIN ARE TYPICAL STEPS OF OTHER DESIGN AND MATERIAL THAT WILL CONFORM TO THE MINIMUM REQUIREMENTS OF THE STEPS SHOWN, MAY BE USED WHEN APPROVED BY THE ENGINEER.

INLETS MAY BE PRECAST WHEN APPROVED BY THE ENGINEER.



DETAILS OF INLET, SPECIAL



LEGEND FOR PLAN SHEETS

- | | | |
|---------------------------------|-----------------------|-----------------------------|
| PROP. COMBINATION CURB & GUTTER | PROPOSED INLET | MAIL BOX |
| PROP. DEPRESSED CURB | PROPOSED MANHOLE | MANHOLE |
| EXISTING GAS LINE | SIGN | FENCE POST |
| EXISTING WATER LINE | GAS VALVE | POWER POLE |
| EXISTING SANITARY SEWER | TREE | TELEPHONE POLE |
| EXISTING STORM SEWER | TREE TO BE REMOVED | WATER VALVE |
| EXISTING FENCE | GAS METER | FIRE HYDRANT |
| PROPOSED STORM SEWER | VAPOR LIGHT | EXISTING DITCH FLOW LINE |
| EXISTING RIGHT-OF-WAY | WATER METER | PROPOSED DITCH FLOW LINE |
| PROPOSED EASEMENT | PROPERTY CORNER | PROPOSED SWALE |
| PROPOSED R.O.W. LINE | EXISTING SIGNAL LIGHT | STRAW BALE DIKE |
| CONSTRUCTION LIMITS | GLY WIRE | PROPOSED FLARED END SECTION |
| | TEL. PEDESTAL | C.P. COLD PATCH |

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	QUANTITY
20100110	TREE REMOVAL (6" TO 15" DIAMETER)	UNIT	75
20100210	TREE REMOVAL (OVER 15" DIAMETER)	UNIT	450
20200100	EARTH EXCAVATION	CU YD	3,600
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	625
20800150	TRENCH BACKFILL	CU YD	49
25000100	SEEDING, CLASS 1	ACRE	2
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	180
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	180
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	180
25000700	AGRICULTURAL GROUND LIMESTONE	TON	4
25002300	TEMPORARY SEEDING	ACRE	2
25100630	EROSION CONTROL BLANKET	SQ YD	9,680
28000305	TEMPORARY DITCH CHECKS	FOOT	200
28000400	PERIMETER EROSION BARRIER	FOOT	2,398
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A, 4"	SQ YD	11,742
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	595
LR420129	PORTLAND CEMENT CONCRETE PAVEMENT, 8" SPECIAL w/ INTEGRAL CURB	SQ YD	10,621
42001300	PROTECTIVE COAT	SQ YD	12,000
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY, 6"	SQ YD	674
42400800	DETECTABLE WARNINGS	SQ FT	72
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	SQ FT	13,232
44000100	PAVEMENT REMOVAL	SQ YD	8,696
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	654
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	398
44000600	SIDEWALK REMOVAL	SQ FT	1,294
48100100	AGGREGATE SHOULDERS, TYPE A	TON	325
50105220	PIPE CULVERT REMOVAL	FOOT	148
50901760	PIPE HANDRAIL	FOOT	30
54011005	PRECAST CONCRETE BOX CULVERT 10' x 5'	FOOT	8
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	372
60100935	PIPE DRAINS, 10"	FOOT	477
60100945	PIPE DRAINS, 12"	FOOT	45
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	15
60242400	INLETS, SPECIAL	EACH	7
60243300	INLETS, SPECIAL, TYPE 3, 5 FT.	EACH	20
60300350	MANHOLE FRAMES, TO BE ADJUSTED	EACH	6
60500060	REMOVING INLETS	EACH	3
60600095	CLASS SI CONCRETE OUTLET	CU YD	5.4
* 63000002	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6.75 FOOT POSTS	FOOT	1,125.0
63200305	STEEL PLATE BEAM GUARDRAIL REMOVAL	FOOT	1,130
67100100	MOBILIZATION	LSUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	LSUM	1
72000100	SIGN PANEL, TYPE 1	SQ FT	24
72800100	TELES STL SIN SUPPORT	FOOT	90
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3,203

* SPECIALTY ITEMS

GENERAL NOTES

1. PROTECTIVE COAT SHALL BE APPLIED TO ALL P.C.C. PAVEMENT, P.C.C. DRIVEWAYS, GUTTER FLAGS AND FACE OF CURB, CONCRETE SIDEWALKS AND RETAINING WALLS AS NEEDED ACCORDING TO THE SEASONAL REQUIREMENTS OF ARTICLE 420.21.
2. AT ALL LOCATIONS WHERE CONCRETE PAVEMENT JOINS AN EXISTING BITUMINOUS OR CONCRETE PAVEMENT, A SAWED JOINT SHALL BE CONSTRUCTED. THE COST OF THIS JOINT WILL BE INCLUDED IN THE TYPE OF PAVEMENT BEING CONSTRUCTED.
3. THE REQUIREMENTS OF THE IEPA SHALL GOVERN THE HORIZONTAL AND VERTICAL SEPERATION OF THE WATER MAIN FROM THE STORM SEWER. IF REQUIRED THE STORM SEWER SHALL BE CONSTRUCTED USING WATER QUALITY P.V.C. PIPE. THIS WORK SHALL BE PAID FOR AS WATER QUALITY STORM SEWER OF THE SIZE AND TYPE SPECIFIED.
4. NOT ALL OF THE EXISTING WATER, SEWER, GAS, POWER AND/OR TELEPHONE LINES WHETHER ABOVE OR BELOW GROUND SURFACE HAVE BEEN SHOWN ON THE PLANS. THE LOCATION OF EXISTING UNDERGROUND UTILITIES HAVE BEEN DETERMINED FROM THE BEST AVAILABLE INFORMATION AND ARE GIVEN FOR THE CONVENIENCE OF THE CONTRACTOR. THE CONTRACTOR MUST ASSUME ALL RESPONSIBILITY FOR ALL UTILITIES WHETHER SHOWN OR NOT SHOWN, AND MUST REALIZE THAT THE ACTUAL LOCATION OF THE UTILITIES SHOWN ON THE PLANS MAY DIFFER FROM THE LOCATION INDICATED.

GENERAL

This plan has been prepared to comply with the provision of the NPDES Permit Number ILR10-B376 issued by the Illinois Environmental Protection Agency for storm water discharges from construction site activities.

The following plan has been established and included in these plans to direct the Contractor in the placement of temporary erosion control systems and to provide a storm water pollution prevention plan for compliance under NPDES. The contractor shall comply with all requirements within this plan as part of the contract.

The purpose of this plan is to prevent / minimize siltation within the construction zone and to eliminate sediments from entering and leaving the construction zone by utilizing proper temporary erosion control systems and providing ground cover within a reasonable time.

Certain items shall be placed as shown in this plan. Other items shall be placed as directed by the Engineer based on situations resulting from the type of activities, time of year and weather conditions.

The Contractor shall place permanent erosion control and seeding within a reasonable time, thereby reducing areas open to the possibility of erosion. The Engineer will determine if temporary erosion control systems shown in the plans can be deleted, the size of proposed ditch checks, proper methods of installation, and if additional temporary erosion controls shall be added which are not included in this plan. The Contractor shall perform all work as directed by the Engineer.

SITE DESCRIPTION

Description of Construction Activities

1. Reconstruction of North DuQuoin Street from McFall Street to the Interstate 57 Overpass Bridge to include aggregate sub-base, concrete pavement with curb and gutter, driveways and sidewalks. Storm sewers shall be constructed to replace the existing drainage facilities.

Intended Sequence of Major Construction Activities

1. Mobilization and Construction Staking
2. Install Silt Fences and Temporary Erosion Control Measures
3. Relocate Underground Utilities
4. Tree Removal and Ditch Construction
5. Install Pipe Culverts and Storm Sewers
6. Excavation / Embankment to Designed Sub-grade
7. Subgrade Compaction
8. Aggregate Base Course Placement and Compaction
9. P.C.C. Pavement with Curb and Gutter
10. Seed and Mulch within 14 days after Final Grading
11. Remove Temporary Erosion and Sediment Control Items
12. Final Clean-up

Area of Construction Site

1. The total area of the construction site is estimated to be 6.20 acres in which 4.40 acres will be disturbed by excavation, grading or other activities.

Referenced Documents

1. Soil Boring Logs
2. Soil Survey Map of Franklin County
3. U.S.G.S. Maps

Receiving Streams

1. Unnamed Stream; tributary to Fallet Branch; tributary to the Big Muddy River
2. Unnamed Stream; tributary to Sugar Creek; tributary to the Big Muddy River

EROSION CONTROLS AND SEDIMENT CONTROLS

Stabilization Practices

1. Temporary Stabilization
 - (a) Areas of existing vegetation outside the proposed construction slope limits shall be identified for preservation and shall be protected from construction or other activities which would be detrimental to their maintenance and development.
 - (b) Dead, diseased, or unsuitable vegetation within the site shall be removed as directed by the Engineer, along with required tree removal.
 - (c) As soon as reasonable access is available to all locations where water drains away from the project, temporary ditch checks, and/or erosion control fence shall be installed as called out in this plan and as directed by the Engineer.
 - (d) Bare and sparsely vegetated ground in highly erodible areas as determined by the Engineer shall be temporarily seeded where no construction activities are expected within seven days as stated in the special provision "Temporary Seeding".
 - (e) Top soil stockpiles, earth stockpiles and disturbed portions of the site where construction activity temporarily ceases for at least twenty-one days shall be temporarily seeded no later than fourteen days from the last construction activity in that area as stated in the special provision "Temporary Seeding".
 - (f) Temporary erosion control items shall be removed as directed by the Engineer after the item is no longer needed or it is no longer functioning.

2. Permanent Stabilization

- (a) Excavated areas, embankments and all other disturbed portions of the site where construction activity permanently ceases shall be stabilized with permanent seed no later than fourteen days after the last construction activity. This work shall be done in accordance with Section 250 - Seeding, of the Standard Specifications.
- (b) All seeded areas shall be inspected at least one time each seven days and within 24 hours after a rainfall of 0.5" or greater.
- (c) The project shall be inspected by the Engineer on a bi-weekly basis to determine that erosion control efforts are in place and effective and if other control work is necessary.

Structural Practices

1. Perimeter barriers, ditch checks and inlet/pipe protection shall be constructed at all locations as indicated in the plans and at any additional location as directed by the Engineer.
2. Temporary rip-rap ditch checks will be allowed to remain in place where approved by the Engineer.
3. Sediment collected during construction by the various temporary erosion control systems shall be disposed of on a regular basis as directed by the Engineer.

Storm Water Management

1. Storm water management will be provided by drainage ditches, swales, storm sewers, and catch basins for the site. The areas will be graded to drain and have permanent seeding.

OTHER CONTROLS

Waste Disposal

1. Waste Materials - All waste materials will be collected and stored in containers with lids and will be disposed of by a licensed solid waste company. The containers will meet all state and local solid waste management regulations. All trash and construction debris from the site will be deposited in the containers. The containers will be emptied and the trash hauled offsite on an as needed basis or as directed by the Engineer. No construction waste materials will be buried onsite. All personnel will be instructed regarding the correct procedure for waste disposal and a notice stating these practices will be posted in the Contractor's office trailer.
2. Hazardous Materials - All hazardous waste materials shall be disposed of in the manner specified by state or local regulations or by the manufacturer's Material Safety Data Sheet (MSDS). Site personnel will be instructed regarding the correct procedure for hazardous waste disposal.
3. Sanitary Waste - All sanitary waste will be collected from any portable units a minimum of once per week by a licensed sanitary waste management contractor as required by local regulations.

Offsite Vehicle Tracking

1. If deemed necessary, a vehicle wash off area with yard hydrants will be provided by the contractor to help reduce vehicle tracking of sediments. The contractor shall provide all measures as required by IDOT for accessing public roads by construction vehicles.

TIMING OF CONTROLS/MEASURES

As indicated in the sequence of major activities, the silt fencing and other temporary erosion controls will be constructed prior to clearing or grading of any other portions of the site. Areas where construction activity temporarily ceases for more than twenty-one days will be stabilized with a temporary seed and mulch within fourteen days of the last disturbance. Once construction activity ceases permanently in an area, that area will be stabilized with permanent seed and mulch as per the specifications. All accumulated sediment will be removed and the area will be monitored and maintained until stabilized.

MAINTENANCE/INSPECTION PROCEDURES

These are the inspection and maintenance practices that will be used to maintain erosion and sediment controls:

1. All control measures shall be inspected by the Engineer on a bi-weekly basis and following any storm event of 0.5" or greater.
2. All measures will be maintained in good working order. If a repair is necessary, it will be initiated within 24 hours of the report.
3. Built up sediment will be removed from silt fence when it has reached one-quarter the height of the fence.
4. Silt fence will be inspected for depth of sediment, tears, whether fabric is securely attached to posts, and whether posts are firmly embedded in the ground.
5. Sediment traps and ditch checks will be inspected for depth of sediment and secured placement. Accumulated sediment will be removed when it reaches the maximum allowed sediment level or at the direction of the Engineer.
6. All ditches will be inspected and any breaches promptly repaired.
7. Temporary and permanent seeding will be inspected for bare spots, washouts, rills, cuts and healthy growth.
8. The contractor shall have two individuals who will be responsible for inspections, maintenance and repair activities, and filling out the inspection and maintenance report. The Engineer shall verify all inspections, maintenance and repair activities.

F. A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 9452	08-00059-00-RP	FRANKLIN	39	4
NORTH DUQUOIN ST.		CONTRACT NO. 99396		

9. A maintenance inspection report in accordance with Part IV.D.4.b of the general permit shall be made and kept on file by the Contractor as part of the plan for at least three years after the date of inspection. The report shall be signed in accordance with Part VI.G of the General Permit.

10. If any violation of the provisions of this plan is identified during the conduct of the construction work covered by this plan, The Engineer shall complete and file an "Incident of Noncompliance (ION)" report for the identified violation. The Engineer shall use forms provided by the Illinois Environmental Protection Agency and shall include specific information on the noncompliance, actions which were taken to prevent any further causes of noncompliance, and a statement detailing any environmental impact which may have resulted from the noncompliance.

INVENTORY FOR POLLUTION PREVENTION PLAN

The materials or substances listed below are expected to be present onsite during construction:

- | | |
|----------------|-----------------------|
| 1. Concrete | 5. Cleaning Solvents |
| 2. Detergents | 6. Wood |
| 3. Fertilizers | 7. Lime |
| 4. Paints | 8. Petroleum Products |

SPILL PREVENTION

Material Management Practices

1. Good Housekeeping Practices - The following will be used to reduce the risk of spills or other accidental exposure of materials and substances to storm water runoff:
 - (a) Effort to store only enough product to do the job.
 - (b) Materials stored in a neat, orderly manner in their appropriate containers.
 - (c) Products kept in original containers with original manufacturers labels.
 - (d) Materials not mixed with one another unless recommended by the manufacturer.
 - (e) All of a product will be used before disposing of the container.
 - (f) Manufacturer's recommendations for proper use and disposal will be followed.
2. Hazardous Products - These practices are used to reduce the risks associated with hazardous materials:
 - (a) Products will be kept in original containers unless they are not resealable.
 - (b) Original containers and Material Safety Data Sheets (MSDS's) will be retained.
 - (c) If surplus product must be disposed of, manufacturer's or local and state recommended methods for proper disposal will be followed.

Product Specific Practices

The following practices will be followed onsite:


1. Petroleum Products - All onsite vehicles will be monitored for leaks and receive regular preventive maintenance to reduce the chance of leakage. Petroleum products will be stored in tightly sealed containers which are clearly labeled.

Construction equipment shall be stored and fueled only at designated locations. All necessary measures shall be taken to contain any fuel or pollution runoff in compliance with EPA water quality regulations. Leaking equipment or supplies shall be immediately repaired or removed from the site.
2. Fertilizers - All fertilizers used will be applied only in the minimum amounts recommended by the manufacturer. Once applied, fertilizer will be worked into the soil to limit exposure to storm water runoff. Storage will be in a covered area. The contents of any partially used bags of fertilizer will be transferred to a sealable plastic bin to avoid spills.
3. Paints - All containers will be tightly sealed and stored when not required for use. Excess paint will not be dumped on the ground or discharged into the storm sewer system, but will be properly disposed of according to the manufacturer's instructions or applicable state or local regulations.
4. Concrete Trucks - Concrete trucks will not be allowed to wash out or discharge surplus concrete or drum wash water onsite unless in an approved holding basin.



STORM WATER POLLUTION PREVENTION PLAN CERTIFICATION

This Plan has been prepared to comply with the provisions of the NPDES Permit Number ILR10, issued by the Illinois Environmental Protection Agency for storm water discharges from construction site activities.

I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information is, to the best of my knowledge and belief, true, accurate and complete. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations.


Mayor, City of Benton


12-11-09
Date



BENCH MARKS



TBM1 - EL. 456.46
Top Bolt Betw. "E" & "L" in Mueller on F.H. N.E. Cor. McFall & DuQuoin St. See Pg. 20 Bk. 577

TBM2 - EL. 456.14
Top Bolt Betw. "E" & "L" in "Mueller" on F.H. N.E. Cor. Fourth & DuQuoin St. See Pg. 20 Bk. 577



DRAINAGE STRUCTURES				
STRUCTURE	STATION	RIM EL.	FL EL.	INV. EL.
1	2+40.3 RT	454.79	454.08	450.06(E), 449.22
2	2+76.2 LT	454.65	453.94	450.82
3	2+98 RT	454.69	453.85	441.91(E), 450.35(SW), 449.30
4	4+15 LT	454.09	453.38	451.38
5	4+15 RT	454.09	453.38	451.24(W), 448.46(EST)
6	5+47 LT	453.26	452.55	450.55
7	5+47 RT	453.26	452.55	450.41(W), 447.70(EST)


STORM SEWERS				
POINT TO POINT	LENGTH FT	% GRADE	TYPE	TRENCH BACKFILL CY
4 to 5	31	0.45	12"RCP	4.09
6 to 7	31	0.45	12"RCP	4.09





BENCH MARKS

IBM3 - EL. 453.43
Top Bolt Betw. "E" & "L" in "Mueller" on
F.H. @ N.E. Cor. Fifth & DuQuoin St.
See Pg. 20 Bk. 577

IBM4 - EL. 452.50
Top Bolt Betw. "E" & "L" in "Mueller" on
F.H. @ S.W. Cor. Clayton & Division St.
See Pg. 20 Bk. 577




DRAINAGE STRUCTURES					STORM SEWERS				
STRUCTURE	STATION	RIM EL.	FL EL.	INV. EL.	POINT TO POINT	LENGTH FT	% GRADE	TYPE	TRENCH BACKFILL CY
8	7+00 LT	451.95	451.24	449.24	8 to 9	31	0.45	12"RCP	4.09
9	7+00 RT	451.95	451.24	449.10(W)	10 to 11	31	0.45	12"RCP	4.09
10	8+49 LT	451.17	450.46	448.46	12 to 13	57	1.95	10"PVC	-
11	8+49 RT	451.17	450.46	448.32(W), 446.47(EST)	13 to 14	5	0.40	10"PVC	-
12	9+26.7 LT	450.52	-	449.00(EST)	14 to 15	31	0.45	12"RCP	4.09
13	9+85 LT	450.30	-	447.89	16 to 13	69	1.03	10"PVC	-
14	9+85 LT	450.58	449.87	447.87					
15	9+85 RT	450.58	449.87	447.73(W), 446.24(EST)					
16	10+55.8 LT	450.00	-	448.60(EST)					





BENCH MARKS


TRM5 - EL. 450.98
 Spike nail in PP, 3 trans on S. Side
 Division St., 150' W. of C.L. DuQuoin St.
 See Pg. 51 Bk. 581





DRAINAGE STRUCTURES					STORM SEWERS				
STRUCTURE	STATION	RIM EL.	FL EL.	INV. EL.	POINT TO POINT	LENGTH FT	% GRADE	TYPE	TRENCH BACKFILL CY
17	11+45.1 LT	449.40	-	447.71	17 to 18	49	1.04	10" PVC	-
18	11+96 LT	450.08	-	447.24	18 to 19	5	0.40	10" PVC	-
19	11+96 LT	449.93	449.22	447.22	19 to 20	31	0.45	12" RCP	4.09
20	11+96 RT	449.93	449.22	447.08(EST)	20 to 21	68	1.00	10" PVC	-
21	12+66.8 LT	449.27	-	447.64	21 to 22	47	0.60	10" PVC	-
22	13+36.6 LT	448.89	-	447.26(NW), 446.96	22 to 23	33	0.58	10" PVC	-
23	13+85.4 LT	449.10	-	447.70(EST,W), 446.68	23 to 24	5	0.40	10" PVC	-
24	14+20 LT	448.84	-	446.49	24 to 25	31	0.45	12" RCP	4.09
25	14+20 LT	449.18	448.47	446.47	25 to 26	83	2.31	10" PVC	-
26	14+20 RT	449.18	448.47	446.33(W&E)					
27	15+24.5 LT	448.52	-	447.40(EST)					




BENCH MARKS
 TBM6 - EL. 448.09
 Top Bolt Betw. "E" & "L" in "Mueller"
 on F.H. @ S.E. Cor. Reed & DuQuoin St.
 See Pg. 21 Bk. 577





BENCH MARKS



TBM7 EL. 446.64 Spike nail in PP/3Trans on S. Side Division St., 150' + W. of C.L. DuQuoin St. See Pg. 21 Bk. 577	TBM7A - EL. 442.30 Chisled on S. End Conc. Headwall to 42" RCP on W. Side DuQuoin St. @ Sta. 25+70 - 32.7' Lt. B.L. A See Pg. 1 Bk. 249
---	--



DRAINAGE STRUCTURES					STORM SEWERS				
STRUCTURE	STATION	RIM EL.	FL EL.	INV. EL.	POINT TO POINT	LENGTH FT	% GRADE	TYPE	TRENCH BACKFILL CY
41	23+08 LT	444.35	443.64	441.64	41 to 42	31	0.45	12"RCP	4.09
42	23+08 RT	444.35	443.64	441.50(W), 440.26(EST)					

VERTICAL CURVE #5
 L = 100'
 PC STA. 25+30 EL. 442.93
 PVI STA. 25+80 EL. 442.66
 PT STA. 26+30 EL. 442.91
 g5 = -0.55%
 g6 = +0.50%
 SAG STA. 25+80 EL. 442.77

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00059-00-RP	FRANKLIN	39	10
NORTH DuQUOIN ST.			CONTRACT NO. 99396	




HORIZONTAL CURVE DATA

$\Delta = 34^{\circ}34'$	PC STA. = 26+00
$D = 16^{\circ}30'$	PT STA. = 28+09.40
$R = 348.45'$	SE TRANSITION BEGIN STA. = 25+19
$T = 108.04'$	SE REVERSED CROWN STA. = 25+45
$L = 209.49'$	SE FULL 4% STA. = 26+14 TO 27+95.4
	SE REVERSED CROWN STA. = 28+64.4
	SE TRANSITION END STA. = 28+90.4

BENCH MARKS

TBM - EL. 442.65
 Mag Nail in W. Side PP/Trans on E. Side
 DuQuoin St. & 50' N. of Apartments
 See Pg. 21 Bk. 577





BENTON - NORTH DuQUOIN STREET

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00059-00-RP	FRANKLIN	39	11
NORTH DUQUOIN ST.			CONTRACT NO. 99396	


HORIZONTAL CURVE DATA

$\Delta = 58^{\circ}00'$ PC STA. = 31+93.49
 $D = 16^{\circ}30'$ PT STA. = 35+45.01
 $R = 348.45'$ SE TRANSITION BEGIN STA. = 31+12.49
 $T = 193.15'$ SE REVERSED CROWN STA. = 31+38.49
 $L = 351.52'$ SE FULL 4% STA. = 32+07.49 TO 35+31.01
 SE REVERSED CROWN STA. = 36+00.01
 SE TRANSITION END STA. = 36+26.01




BENCH MARKS

BMS - FL 447.97
 Top Mag Nail set vertically in top 6" x 8" wood post @ S. end guardrail on W. side DuQuoin St.
 See Pg. 22 Bk. 577




ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00059-00-RP	FRANKLIN	39	12
NORTH DUQUOIN ST.		CONTRACT NO. 99396		




HORIZONTAL CURVE DATA

$\Delta = 58^{\circ}00'$ PC STA. = 31+93.49
 $D = 16^{\circ}30'$ PT STA. = 35+45.01
 $R = 348.45'$ SE TRANSITION BEGIN STA. = 31+12.49
 $T = 193.15'$ SE REVERSED CROWN STA. = 31+38.49
 $L = 351.52'$ SE FULL 4% STA. = 32+07.49 TO 35+31.01
 SE REVERSED CROWN STA. = 36+00.01
 SE TRANSITION END STA. = 36+26.01





BENCH MARKS

BM10 - EL. 462.85
 Chisled "□" on top conc. curb walk @
 Beg. of overpass bridge to I-57
 left side DuQuoin St.
 See Pg. 22 Bk. 577






VERTICAL CURVE #7
 $L = 200'$
 PC STA. 34+00 EL. 455.41
 PVI STA. 35+00 EL. 459.67
 PT STA. 36+00 EL. 461.18
 $g7 = +4.26\%$
 $g8 = +1.51\%$

VERTICAL CURVE #8
 $L = 100'$
 PC STA. 36+00 EL. 461.18
 PVI STA. 36+50 EL. 461.93
 PT STA. 37+00 EL. 462.17
 $g8 = +1.51\%$
 $g9 = +0.49\%$




BLR 10-6 P.C.C. PAVEMENT SPECIAL, 8"		SUB-BASE --- GRANULAR MATERIAL, TYPE A, 4"		LOCATION	CONCRETE SIDEWALK TO BE REMOVED	P.C. CONCRETE SIDEWALK 4"	LOCATION	DRIVEWAY PAVEMENT TO BE REMOVED	P.C. CONCRETE DRIVEWAY PAVEMENT, 6"
STATION TO STATION	SQ. YDS.	STATION TO STATION	SQ. YDS.		SQ. FT.	SQ. FT.		SQ. YDS.	SQ. YDS.
2+30.7 - 6+25	1,394.28	2+30.7 - 6+25	1,588.56	①	1,018.16	1,260.49	⊠	50.14	37.20
SHEET TOTAL	1,394.28	SHEET TOTAL	1,588.56	②	74.36	118.46	⊠	52.33	37.24
COMBINATION CURB & GUTTER REMOVAL		COMB. CONCRETE CURB & GUTTER TYPE B6.18		③	-	620.21	⊠	-	15.33
STATION TO STATION	FT.	STATION TO STATION	FT.	④	77.44	63.09	SHT. TOTAL	102.47	89.77
2+30.7 - 5+24	368.75	2+30.7 - 6+25	807.00	⑤	40.47	45.89	INLETS TO BE REMOVED		
SHEET TOTAL	368.75	SHEET TOTAL	807.00	⑥	44.31	51.75	LOCATIONS		
PAVEMENT REMOVAL		TREE REMOVAL OVER 15 INCH		⑦	39.00	47.03	2+40.31	18.14', RIGHT	
STATION TO STATION	SQ. YDS.	STATION	IN. DIA.	TOTAL	1,293.74	2,159.89	2+76.39	17.46', LEFT	
2+30.7 - 6+25	1,293.28	3+30.7, 29.7' LT.	27			2+99.75		23.32', RIGHT	
SHEET TOTAL	1,293.28	4+78.5, 21.6' LT.	20			SHT. TOTAL		3 EACH	
		5+49.2, 25' LT.	21						
		SHEET TOTAL	68						







BLR 10-6 P.C.C. PAVEMENT SPECIAL, 8"	SUB-BASE --- GRANULAR MATERIAL, TYPE A, 4"	LOCATION	P.C. CONCRETE SIDEWALK 4"	LOCATION	DRIVEWAY PAVEMENT TO BE REMOVED	P.C. CONCRETE DRIVEWAY PAVEMENT, 6"
STATION TO STATION	SQ. YDS.	STATION TO STATION	SQ. YDS.		SQ. YDS.	SQ. YDS.
6+25 - 10+85	1,451.66	6+25 - 10+85	1,669.68	①	41.90	29.88
SHEET TOTAL	1,451.66	SHEET TOTAL	1,669.68	②	53.66	41.39
COMBINATION CURB & GUTTER REMOVAL		COMB. CONCRETE CURB & GUTTER TYPE B6.18		③	-	15.34
STATION TO STATION	FT.	STATION TO STATION	FT.	④	-	15.34
6+25 - 10+85	28.88	6+25 - 10+85	905.62	TOTAL	95.56	101.95
SHEET TOTAL	28.88	SHEET TOTAL	905.62	SHT. TOTAL		

PAVEMENT REMOVAL		TREE REMOVAL OVER 15 INCH	
STATION TO STATION	SQ. YDS.	STATION	IN. DIA.
6+25 - 10+85	1,144.08	6+57.38, 23.3'LT	26
SHEET TOTAL	1,144.08	7+05.46, 21.9'LT	27
		7+67.41, 20.9'LT	34
		8+23.27, 24.1'LT	28
		SHEET TOTAL	115





ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00059-00-RP	FRANKLIN	39	15
NORTH DuQUOIN ST.			CONTRACT NO. 99396	




BLR 10-6 P.C.C. PAVEMENT SPECIAL, 8"		SUB-BASE --- GRANULAR MATERIAL, TYPE A, 4"		LOCATION	P.C. CONCRETE SIDEWALK 4"	LOCATION	DRIVEWAY PAVEMENT TO BE REMOVED	P.C. CONCRETE DRIVEWAY PAVEMENT, 6"
STATION TO STATION	SQ. YDS.	STATION TO STATION	SQ. YDS.		SQ. FT.		SQ. YDS.	SQ. YDS.
10+85 - 16+00	1,619.62	10+85 - 16+00	1,871.50	①	62.20	Ⓐ	54.47	41.45
SHEET TOTAL	1,619.62	SHEET TOTAL	1,871.50	②	129.97	Ⓑ	35.76	20.09
PAVEMENT REMOVAL		COMB. CONCRETE CURB & GUTTER TYPE B6.18		③	959.86	Ⓒ	83.44	61.53
STATION TO STATION	SQ. YDS.	STATION TO STATION	FT.	④	1285.64	Ⓓ	25.02	20.42
10+85 - 16+00	1,246.68	10+85 - 16+00	1,046.27	⑤	106.11			
SHEET TOTAL	1,246.68	SHEET TOTAL	1,046.27	TOTAL	2,543.78	SHT. TOTAL	198.69	143.49



TREE REMOVAL 6 INCH TO 15 INCH	
STATION	IN. DIA.
11+38.92, 18.1'LT	9" TWIN
SHEET TOTAL	18"





BLR 10-6 P.C.C. PAVEMENT SPECIAL, 8"		SUB-BASE --- GRANULAR MATERIAL, TYPE A, 4"		LOCATION	P.C. CONCRETE SIDEWALK 4"	LOCATION	DRIVEWAY PAVEMENT TO BE REMOVED	P.C. CONCRETE DRIVEWAY PAVEMENT, 6"	TREE REMOVAL OVER 15 INCH		TREE REMOVAL 6 INCH TO 15 INCH	
STATION TO STATION	SQ. YDS.	STATION TO STATION	SQ. YDS.		SQ. FT.		SQ. YDS.	SQ. YDS.	STATION	IN. DIA.	STATION	IN. DIA.
16+00 - 21+25	1,728.38	16+00 - 21+25	1,986.83	①	198.16	◇	-	47.20	16+07, 26.0' RT	40	17+15, 19.4' LT	13
SHEET TOTAL	1,728.38	SHEET TOTAL	1,986.83	②	2,146.93	◇	65.70	33.44	16+12, 26.0' RT	43	17+27, 19.0' LT	13
PAVEMENT REMOVAL		COMB. CONCRETE CURB & GUTTER TYPE B6.18		③	308.79	◇	-	20.42	20+94, 23.3' RT	34	17+89, 18.0' LT	9
STATION TO STATION	SQ. YDS.	STATION TO STATION	FT.	④	41.45	SHT. TOTAL	65.70	101.06	16+35, 20.0' LT	31	18+13, 17.3' LT	13
16+00 - 21+25	1,354.74	16+00 - 21+25	1,073.57	⑤	97.71				16+98, 16.0' LT	15		
SHEET TOTAL	1,354.74	SHEET TOTAL	1,073.57	⑥	134.33				17+54, 19.4' LT	18		
				TOTAL	2,927.37				17+80, 18.2' LT	16		
									17+97, 21.7' LT	16		
									18+28, 21.0' LT	29		
									SHEET TOTAL	48		
									SHEET TOTAL	242		








BLR 10-6 P.C.C. PAVEMENT SPECIAL, 8"	SUB-BASE --- GRANULAR MATERIAL, TYPE A, 4"	LOCATION	P.C. CONCRETE SIDEWALK 4"	LOCATION	DRIVEWAY PAVEMENT TO BE REMOVED	P.C. CONCRETE DRIVEWAY PAVEMENT, 6"	TREE REMOVAL OVER 15 INCH	PIPE CULVERT REMOVAL
STATION TO STATION	SQ. YDS.	STATION TO STATION	SQ. YDS.	STATION	SQ. YDS.	SQ. YDS.	STATION	IN. DIA.
21+25 - 26+00	1,497.77	21+25 - 26+00	1,695.95	①	-	15.34	23+39.54, 18.6' LT	25
SHEET TOTAL	1,497.77	SHEET TOTAL	1,695.95	②	63.98	45.51	SHEET TOTAL	25
PAVEMENT REMOVAL		COMB. CONCRETE CURB & GUTTER TYPE B6.18		③	115.06	87.29		
STATION TO STATION	SQ. YDS.	STATION TO STATION	FT.	④				
21+25 - 26+00	1,137.45	21+25 - 26+00	823.20	⑤				
SHEET TOTAL	1,137.45	SHEET TOTAL	823.20	⑥				
AGGREGATE SHOULDERS TYPE A, 6"		SHEET TOTAL	823.20	TOTAL		2,709.59		
STATION TO STATION	TONS							
LT 25+51 - 26+00	7.47							
RT 25+56 - 26+00	6.73							
SHEET TOTAL	14.20							

STATION TO STATION	SQ. YDS.	STATION TO STATION	FT.
21+25 - 26+00	1,137.45	21+25 - 26+00	823.20
SHEET TOTAL	1,137.45	SHEET TOTAL	823.20

STATION	IN. DIA.	STATION TO STATION	FT.
23+39.54, 18.6' LT	25	(LT.) 21+88 - 22+29	41.0
SHEET TOTAL	25	(LT.) 22+57 - 22+87	30.0
		(LT.) 23+78 - 24+55	77.0
		SHEET TOTAL	148.0





HORIZONTAL CURVE DATA

$\Delta = 34^{\circ}34'$ PC STA. = 26+00
 $D = 16^{\circ}30'$ PT STA. = 28+09.40
 $R = 348.45'$ SE TRANSITION BEGIN STA. = 25+19
 $T = 108.04'$ SE REVERSED CROWN STA. = 25+45
 $L = 209.49'$ SE FULL 4% STA. = 26+14 TO 27+95.4
 SE REVERSED CROWN STA. = 28+64.4
 SE TRANSITION END STA. = 28+90.4



BLR 10-6 P.C.C. PAVEMENT SPECIAL, 8"		SUB-BASE --- GRANULAR MATERIAL, TYPE A, 4"		LOCATION	DRIVEWAY PAVEMENT TO BE REMOVED	P.C. CONCRETE DRIVEWAY PAVEMENT, 6"	LOCATION	P.C. CONCRETE SIDEWALK 4"
STATION TO STATION	SQ. YDS.	STATION TO STATION	SQ. YDS.		SQ. YDS.	SQ. YDS.		SQ. FT.
26+00 - 31+00	1,330.91	26+00 - 31+00	1,330.91	①	6.18	15.96	①	616.41
SHEET TOTAL	1,330.91	SHEET TOTAL	1,330.91	②	-	32.79	TOTAL	616.41
PAVEMENT REMOVAL		AGGREGATE SHOULDERS TYPE A, 6"		③	6.61	16.11		
STATION TO STATION	SQ. YDS.	STATION TO STATION	TONS	④	-	25.00		
26+00 - 31+00	1,123.86	LT 26+00 - 31+00	78.92	SHT. TOTAL	12.79	89.86		
SHEET TOTAL	1,123.86	RT 26+00 - 31+00	61.60					
		SHEET TOTAL	140.52					

- PROPOSED AGGREGATE SHOULDER
- EXISTING DRIVEWAY PAVEMENT REMOVAL
- PROPOSED SIDEWALK
- PROPOSED DRIVEWAY PAVEMENT

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00059-00-RP	FRANKLIN	39	19
NORTH DUQUOIN ST.			CONTRACT NO. 99396	

HORIZONTAL CURVE DATA


$\Delta = 58^{\circ}00'$ PC STA. = 31+93.49
 $D = 16^{\circ}30'$ PT STA. = 35+45.01
 $R = 348.45'$ SE TRANSITION BEGIN STA. = 31+12.49
 $T = 193.15'$ SE REVERSED CROWN STA. = 31+38.49
 $L = 351.52'$ SE FULL 4% STA. = 32+07.49 TO 35+31.01
SE REVERSED CROWN STA. = 36+00.01
SE TRANSITION END STA. = 36+26.01



BLR 10-6 P.C.C. PAVEMENT SPECIAL, 8"		SUB-BASE --- GRANULAR MATERIAL, TYPE A, 4"	
STATION TO STATION	SQ. YDS.	STATION TO STATION	SQ. YDS.
31+00 - 34+00	799.96	31+00 - 34+00	799.96
SHEET TOTAL	799.96	SHEET TOTAL	799.96
PAVEMENT REMOVAL		AGGREGATE SHOULDERS TYPE A, 6"	
STATION TO STATION	SQ. YDS.	STATION TO STATION	TONS
31+00 - 34+00	689.85	LT 31+00 - 34+00	45.37
SHEET TOTAL	689.85	RT 31+00 - 34+00	47.96
		SHEET TOTAL	93.33


 PROPOSED AGGREGATE SHOULDER

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00059-00-RP	FRANKLIN	39	20
NORTH DUQUOIN ST.			CONTRACT NO. 99396	



HORIZONTAL CURVE DATA



$\Delta = 58^{\circ}00'$ PC STA. = 31+93.49
 $D = 16^{\circ}30'$ PT STA. = 35+45.01
 $R = 348.45'$ SE TRANSITION BEGIN STA. = 31+12.49
 $T = 193.15'$ SE REVERSED CROWN STA. = 31+38.49
 $L = 351.52'$ SE FULL 4% STA. = 32+07.49 TO 35+31.01
 SE REVERSED CROWN STA. = 36+00.01
 SE TRANSITION END STA. = 36+26.01





BLR 10-6 P.C.C. PAVEMENT SPECIAL, 8"		SUB-BASE --- GRANULAR MATERIAL, TYPE A, 4"	
STATION TO STATION	SQ. YDS.	STATION TO STATION	SQ. YDS.
34+00 - 36+99.04	798.20	34+00 - 36+99.04	798.20
SHEET TOTAL	798.20	SHEET TOTAL	798.20
PAVEMENT REMOVAL		AGGREGATE SHOULDERS TYPE A, 6"	
STATION TO STATION	SQ. YDS.	STATION TO STATION	TONS
34+00 - 36+99.04	705.61	LT 34+00 - 36+99.04	41.31
SHEET TOTAL	705.61	RT 34+00 - 36+99.04	49.40
		SHEET TOTAL	90.71

PROPOSED AGGREGATE SHOULDER

F. A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAU 9452	08-00059-00-RP	FRANKLIN	39	21
NORTH DUQUOIN STREET			CONTRACT NO. 99396	



PAINT PAVEMENT MARKING LINE-4" (TYP.)
 NORTH DUQUOIN STREET (STA. 2+20 to 25+32)
 DASHED YELLOW CENTERLINE
 578 L.F.




PAINT PAVEMENT MARKING LINE-4" (TYP.)
 NORTH DUQUOIN STREET (STA. 25+32 to 36+99)
 DASHED YELLOW CENTERLINE
 291 L.F.





PAINT PAVEMENT MARKING LINE-4" (TYP.)
 NORTH DUQUOIN STREET (STA. 25+32 to 36+99)
 SOLID WHITE LINE, BOTH SIDES
 2,334 L.F.

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-0059-00-RP	FRANKLIN	39	22
NORTH DUQUOIN ST.		CONTRACT NO. 99396		




SCALE: 1"=400'




- LEGEND**
-  WORK ZONE WITH A MINIMUM OF 1 LANE TRAFFIC TO BE MAINTAINED
 -  TYPE III BARRICADE WITH "ROAD CLOSED" SIGN
 -  TYPE III BARRICADE WITH "ROAD CLOSED LOCAL TRAFFIC ONLY" SIGN
 -  WARNING SIGN

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00059-00-RP	FRANKLIN	39	23
NORTH DuQUOIN ST.			CONTRACT NO. 99396	




2
+
00




3
+
00

Cut = 4.49 sq. yd.
Fill = 0.24 sq. yd.




2
+
50

Cut = 3.28 sq. yd.
Fill = 0.20 sq. yd.




3
+
50

Cut = 6.97 sq. yd.
Fill = 0.10 sq. yd.




2
+
75.62




4
+
00


Cut = 6.46 sq. yd.
Fill = 0.24 sq. yd.




4
+
40



5
+
06




4
+
50




5
+
50

Cut = 5.22 sq. yd.
Fill = 0.13 sq. yd.

Cut = 4.52 sq. yd.
Fill = 0.28 sq. yd.









5
+
00




5
+
87



Cut = 5.69 sq. yd.
Fill = 0.02 sq. yd.

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00059-00-RP	FRANKLIN	39	25
NORTH DUQUOIN ST.			CONTRACT NO. 99396	







Cut = 3.83 sq. yd.
Fill = 0.77 sq. yd.




Cut = 3.81 sq. yd.
Fill = 0.76 sq. yd.










Cut = 5.99 sq. yd.
Fill = 0.13 sq. yd.




Cut = 3.63 sq. yd.
Fill = 0.87 sq. yd.








11
+
73




12
+
50

Cut = 6.39 sq. yd.
Fill = 0.44 sq. yd.




12
+
00

Cut = 5.86 sq. yd.
Fill = 0.25 sq. yd.




13
+
00

Cut = 4.22 sq. yd.
Fill = 0.77 sq. yd.




12
+
34




13
+
50

Cut = 5.17 sq. yd.
Fill = 0.19 sq. yd.




13
+
56




14
+
50

Cut = 3.51 sq. yd.
Fill = 0.41 sq. yd.




14
+
00

Cut = 3.68 sq. yd.
Fill = 0.74 sq. yd.




15
+
00

Cut = 3.67 sq. yd.
Fill = 0.49 sq. yd.




14
+
45




15
+
50

Cut = 3.12 sq. yd.
Fill = 0.81 sq. yd.




16
+

16
+






16
+

17
+









16
+

17
+




17
+


17
+



ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00059-00-RP	FRANKLIN	39	32
NORTH DUQUOIN ST.			CONTRACT NO. 99396	




20
+
55.65




21
+
50

Cut = 2.03 sq. yd.
Fill = 0.35 sq. yd.




20
+
57




22
+
00

Cut = 2.76 sq. yd.
Fill = 0.31 sq. yd.




21
+
00

Cut = 1.79 sq. yd.
Fill = 0.05 sq. yd.






22
+
19


ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00059-00-RP	FRANKLIN	39	33
NORTH DUQUOIN ST.			CONTRACT NO. 99396	




Cut = 1.66 sq. yd.
Fill = 0.46 sq. yd.









Cut = 3.83 sq. yd.
Fill = 0.27 sq. yd.









Cut = 1.66 sq. yd.
Fill = 0.51 sq. yd.









Cut = 2.03 sq. yd.
Fill = 0.27 sq. yd.







ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00059-00-RP	FRANKLIN	39	35
NORTH DuQUOIN ST.			CONTRACT NO. 99396	



ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00059-00-RP	FRANKLIN	39	36
NORTH DuQUOIN ST.		CONTRACT NO. 99396		




ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00059-00-RP	FRANKLIN	39	37
NORTH DuQUOIN ST.			CONTRACT NO. 99396	




ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00059-00-RP	FRANKLIN	39	38
NORTH DUQUOIN ST.			CONTRACT NO. 99396	

34
+
00




Cut = 1.06 sq. yd.
Fill = 0.37 sq. yd.

35
+
00




Cut = 0.60 sq. yd.
Fill = 0.52 sq. yd.

34
+
50



Cut = 0.66 sq. yd.
Fill = 0.52 sq. yd.

35
+
50



Cut = 0.56 sq. yd.
Fill = 0.59 sq. yd.

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.U. 9452	08-00058-00-RP	FRANKLIN	39	39
NORTH DuQUOIN ST.			CONTRACT NO. 99396	

