

ENTRANCE SCHEDULE						
LOCATION (STATION, DIRECTION)	ENTRANCE TYPE	EXST. SURFACE TYPE	WIDTH (FEET)	LENGTH (FEET)	AGGREGATE SURFACE COURSE, TYPE A, 8" (SQ YD)	
NORTH DAVIDSON AVE.						
114+83.73	RT	FE	GRASS	16	25	60
120+25.71	LT	CE	AGG.	28	35	124
<b>TOTAL</b>						184

PAVEMENT MARKING SCHEDULE							
LOCATION (FROM STATION TO STATION)	DESCRIPTION	4"			12"		LETTERS & SYMBOLS (WHITE) (SQ FT)
		WHITE SOLID (FEET)	YELLOW SKIP DASH (FEET)	YELLOW DOUBLE SOLID (FEET)	DIAGONAL YELLOW (FEET)	STOP BAR WHITE (FEET)	
107+60.04 TO 108+86.10	CENTERLINE			253			
108+86.10 TO 110+83.47	CENTER ISLAND			790			
108+86.10 TO 110+83.47	CENTER ISLAND HATCHING				24		
110+83.47 TO 112+00.00	CENTERLINE			233			
112+00.00 TO 124+05.32	CENTERLINE		300				
107+60.00	STOP BAR					14	
107+60.06 TO 108+76.48	LEFT TURN LANE	116					
107+76.91	LEFT TURN ARROW						8.8
108+43.98	LEFT TURN ARROW						8.8
<b>TOTAL</b>		116	300	1276	24	14	17.6

SIGN SCHEDULE					
LOCATION (STATION, OFFSET)	REMOVE SIGN PANEL	SIGN PANEL	TELESCOPING STEEL SIGN SUPPORT	MUTCD DESIGNATION	
	TYPE 1 (SQ. FT.)	TYPE 1 (SQ. FT.)	(FOOT)		
NORTH DAVIDSON AVE.					
123+96	3' RT	10			R11-2
107+75	26' RT		5	15	R2-1
124+00	16' LT		5	15	R2-1
<b>TOTAL</b>		10	10	30	

EARTHWORK				
LOCATION	EARTH EXCAVATION (C) CU. YD.	EMBANKMENT (F) ADJUSTED 12% FOR COMPACTION CU. YD.	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CU. YD.	
				STA. 107+60 TO STA. 110+00
STA. 110+00 TO STA. 112+50	353.2	114.8	+238	
STA. 112+50 TO STA. 115+00	482.6	1.9	+481	
STA. 115+00 TO STA. 117+50	433.9	0.2	+434	
STA. 117+50 TO STA. 120+00	315.5	45.7	+270	
STA. 120+00 TO STA. 122+50	151.6	1345.3	-1194	
STA. 122+50 TO STA. 124+50	41.8	224.3	-183	
<b>TOTAL</b>		2053	2019	+33

V:\Shores\Clients\40039-Mt. Vernon\40039-300 Davidson Avenue North\Drafting\Sheet Files\NOTES\_S00\_SCHEDULES.dwg, Pg.7 = SCHEDULE, 12/17/2009 10:07:55 AM

FILE NAME = 40039-300	USER NAME = Meyer, Tim	DESIGNED - MSF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 1:1	CHECKED - DLK	REVISED -					8749	09-00130-00-RP	JEFFERSON	30	7
PLOT DATE = 12/17/2009	DATE - 12/09/09	REVISED -		SCALE: NA	SHEET NO. 7 OF 30 SHEETS	STA. NA	TO STA. NA	CONTRACT NO. 99411				

FED. ROAD DIST. NO. 9 | ILLINOIS | APR 2009