



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 24, 2021

SUBJECT FAP Route 352 (IL 137/Sheridan Rd.)  
Project NHPP-PISC(989)  
Section 2020-078-RS&SW  
Lake County  
Contract No. 62L56  
Item No. 51, March 5, 2021 Letting  
Addendum B

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revise the Schedule of Prices
2. Revise page i of the Table of Contents to the Special Provisions
3. Revised pages 4 of the Special Provisions
4. Revised sheets 6, 7 and 23 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

## TABLE OF CONTENTS

LOCATION OF PROJECT .....	1
DESCRIPTION OF PROJECT .....	1
MAINTENANCE OF ROADWAYS .....	2
CLEANING EXISTING DRAINAGE STRUCTURES .....	2
COMPLETION DATE PLUS WORKING DAYS.....	3
CONTRACTOR COOPERATION .....	3
BIKE PATH REMOVAL.....	4
WASHOUT BASIN .....	4
TRAFFIC CONTROL PLAN.....	4
ADJUSTMENTS AND RECONSTRUCTIONS .....	5
CONSTRUCTION LAYOUT SPECIAL FOR RESURFACING WITH ADA AND STAND ALONE ADA (D-1) .....	6
CURB OR COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT (D-1) .....	8
DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (DISTRICT 1) .....	9
FRICTION AGGREGATE (D-1) .....	11
GROUND TIRE RUBBER (GTR) MODIFIED ASPHALT BINDER (D-1).....	14
HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D-1) .....	15
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (MODIFIED FOR I-FIT) (D-1) .....	25
PUBLIC CONVENIENCE AND SAFETY (DIST 1) .....	28
STATUS OF UTILITIES (D-1).....	28
MULCH.....	32
TEMPORARY INFORMATION SIGNING.....	33
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY) .....	34
MAINTENANCE OF EXISTING TRAFFIC SIGNAL AND FLASHING BEACON INSTALLATION.....	35
DETECTOR LOOP REPLACEMENT AND/OR INSTALLATION (ROADWAY GRINDING, RESURFACING, & PATCHING OPERATIONS) .....	38
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC) .....	41
REBUILD EXISTING HANDHOLE.....	48
REBUILD EXISTING DOUBLE HANDHOLE.....	49
REMOVE AND RELOCATE SIGN PANEL AND POLE ASSEMBLY .....	49
RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON.....	50
CLASS D PATCHES, 9 INCH (SPECIAL) .....	50
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE).....	51

Revised 2/24/2021

**BIKE PATH REMOVAL**

This work shall consist of the removal of the existing bike path at the locations shown in the plans and as directed by the Engineer. This work shall conform to Articles 440.03 and 440.06 of the Standard Specifications.

This work will be paid for at the contract unit price per square yard for BIKE PATH REMOVAL.

**WASHOUT BASIN**

Description: This work shall consist of construction and maintaining a washout basin for concrete trucks and other construction vehicles per the details shown on the plans.

Method of Measurement: This work will be measured for at the contract lump sum price for WASHOUT BASIN which price shall include general maintenance and removal of all construction debris, restoration of the site upon completion, and all incidentals required to complete this item of work.

Basis of Payment: This work will be paid for at the contract lump sum price for WASHOUT BASIN.

**TRAFFIC CONTROL PLAN**

Effective: September 30, 1985

Revised: January 1, 2007

Traffic Control shall be according to the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the District One Bureau of Traffic at least 72 hours in advance of beginning work.

Revised 2/24/2021