

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	URBAN 80% FED 20% STATE TOTAL QUANTITIES	URBAN 1000 WILL CO.	URBAN 1000 KENDALL CO.	CULVERT REPLACEMENT X078-2A KENDALL CO.	CODE NO	ITEM	UNIT	URBAN 80% FED 20% STATE TOTAL QUANTITIES	URBAN 1000 WILL CO.	URBAN 1000 KENDALL CO.	CULVERT REPLACEMENT X078-2A KENDALL CO.
20200100	EARTH EXCAVATION	CU YD	206		206		44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	102	54	48	
20201006	GRADING AND SHAPING SHOULDERS	UNIT	254	106	148		44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	532	135	397	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	267			267	48101200	AGGREGATE SHOULDERS, TYPE B	TON	811	811		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	119			119	50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1			1
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	64		64		50200100	STRUCTURE EXCAVATION	CU YD	273			273
25000310	SEEDING, CLASS 4	ACRE	0.01		0.01		50300005	CONCRETE STRUCTURES	CU YD	44.7			44.7
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1		1		50300300	PROTECTIVE COAT	SQ YD	11			11
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1		1		50800105	REINFORCEMENT BARS	POUND	3260			3260
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1		1		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	490			490
25100630	EROSION CONTROL BLANKET	SQ YD	64		64		51500100	NAME PLATES	EACH	1			1
28000300	TEMPORARY DITCH CHECKS	EACH	2		2		54010606	PRECAST CONCRETE BOX CULVERT 6' X 6'	FOOT	35			35
28000400	PERIMETER EROSION BARRIER	FOOT	420		420		54003000	CONCRETE BOX CULVERTS	CU YD	44.7			44.7
28100107	STONE RIPRAP, CLASS A4	SQ YD	20			20	63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	240		240	
28200200	FILTER FABRIC	SQ YD	46			46	* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	12		12	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17	6	11		* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4		4	
40600300	AGGREGATE (PRIME COAT)	TON	81	28	53		63200307	STEEL PLATE BEAM GUARD RAIL REMOVAL, ATTACHED TO STRUCTURE	FOOT	12		12	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	13	5	8		63200310	GUARDRAIL REMOVAL	FOOT	388		388	
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3	3	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	107	12	95		67100100	MOBILIZATION	L SUM	1	0.5	0.5	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	423	151	272		70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.5	0.5	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3365	1179	2186		70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.5	0.5	
44000100	PAVEMENT REMOVAL	SQ YD	156		156		70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	40055	14032	26023		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3450	1435	2015	
44000189	HOT-MIX ASPHALT SURFACE REMOVAL, 10"	SQ YD	755	269	486		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	41942	9542	32400	
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	99	72	27		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1118		1118	
							70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	192		192	
							70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	126		126	
							78200410	GUARDRAIL MARKERS, TYPE A	EACH	42		42	
							X0320044	TEMPORARY CLEAR WATER DIVERSION	L SUM	1		1	
							X0545006	BOX CULVERT REMOVAL	L SUM	1		1	
							XX007025	COARSE AGGREGATE BACKFILL (SPECIAL)	CU YD	715		715	

*SPECIALTY ITEMS

Rev.