

INDEX OF SHEETS

- 1. TITLE SHEET
- 2. GENERAL NOTES
- 3. SUMMARY OF QUANTITIES
- 4.-7. DISTRICT ONE STANDARD TRAFFIC SIGNAL DESIGN DETAILS
- 8. TRAFFIC SIGNAL MODIFICATION PLAN
U.S. ROUTE 12 (RAND ROAD) AT MILLER ROAD
- 9. SCHEDULE OF QUANTITIES, CABLE PLAN AND PHASE DESIGNATION DIAGRAM
U.S. ROUTE 12 (RAND ROAD) AT MILLER ROAD
- 10. TRAFFIC SIGNAL MODIFICATION PLAN
U.S. ROUTE 12 (RAND ROAD) AT OLD RAND ROAD/RAVINIA TER.
- 11. SCHEDULE OF QUANTITIES, CABLE PLAN AND PHASE DESIGNATION DIAGRAM
U.S. ROUTE 12 (RAND ROAD) AT OLD RAND ROAD/RAVINIA TER.
- 12. TRAFFIC SIGNAL MODIFICATION PLAN
U.S. ROUTE 12 (RAND ROAD) AT KMART
- 13. SCHEDULE OF QUANTITIES, CABLE PLAN AND PHASE DESIGNATION DIAGRAM
U.S. ROUTE 12 (RAND ROAD) AT KMART
- 14. TRAFFIC SIGNAL MODIFICATION PLAN
U.S. ROUTE 12 (RAND ROAD) AT ILLINOIS ROUTE 22
- 15. SCHEDULE OF QUANTITIES, CABLE PLAN AND PHASE DESIGNATION DIAGRAM
U.S. ROUTE 12 (RAND ROAD) AT ILLINOIS ROUTE 22
- 16. TRAFFIC SIGNAL MODIFICATION PLAN
U.S. ROUTE 12 (RAND ROAD) AT ELA ROAD
- 17. SCHEDULE OF QUANTITIES, CABLE PLAN AND PHASE DESIGNATION DIAGRAM
U.S. ROUTE 12 (RAND ROAD) AT ELA ROAD
- 18. TRAFFIC SIGNAL MODIFICATION PLAN
U.S. ROUTE 12 (RAND ROAD) AT HOME DEPOT DRIVE
- 19. SCHEDULE OF QUANTITIES, CABLE PLAN AND PHASE DESIGNATION DIAGRAM
U.S. ROUTE 12 (RAND ROAD) AT HOME DEPOT DRIVE
- 20. TRAFFIC SIGNAL MODIFICATION PLAN
U.S. ROUTE 12 (RAND ROAD) AT PHEASANT RIDGE RD/DEERPATH RD.
- 21. SCHEDULE OF QUANTITIES, CABLE PLAN AND PHASE DESIGNATION DIAGRAM
U.S. ROUTE 12 (RAND ROAD) AT PHEASANT RIDGE RD/DEERPATH RD.
- 22. TRAFFIC SIGNAL MODIFICATION PLAN
U.S. ROUTE 12 (RAND ROAD) AT OLD RAND ROAD (S. JCT.)
- 23. SCHEDULE OF QUANTITIES, CABLE PLAN AND PHASE DESIGNATION DIAGRAM
U.S. ROUTE 12 (RAND ROAD) AT OLD RAND ROAD (S. JCT.)
- 24.-25. INTERCONNECT PLAN U.S. ROUTE 12 (RAND ROAD)
- 26A MAST ARM MOUNTED STREET NAME SIGN
U.S. ROUTE 12 (RAND ROAD) AT OLD RAND ROAD/RAVINIA TER.

GENERAL NOTES:

- 1. ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2007 (HEREINAFTER REFERRED TO AS THE "STANDARD SPECIFICATIONS"); THE LATEST "SUPPLEMENTAL SPECIFICATIONS" AND "RECURRING SPECIAL PROVISIONS"; THE LATEST EDITION OF THE "ILLINOIS MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS"; THE DETAILS IN THE PLANS AND THE SPECIAL PROVISIONS INCLUDED IN THE CONTRACT DOCUMENTS.
- 2. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED AS THE LATEST STANDARD OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION.
- 3. THE CONTRACTOR SHALL NOTIFY J.U.L.I.E. (1-800-892-0123) AT LEAST 10 DAYS PRIOR TO CONSTRUCTION OF THE PROPOSED IMPROVEMENTS. ALL UTILITIES MUST BE NOTIFIED AND STAKED PRIOR TO CONSTRUCTION.
- 4. THE CONTRACTOR SHALL FAMILIARIZE HIMSELF WITH THE PLANS AND SHALL NOTIFY THE ENGINEER AT ONCE OF ANY DISCREPANCIES.
- 5. THE CONTRACTOR IS REQUIRED TO ATTEND AN ILLINOIS DEPARTMENT OF TRANSPORTATION (IDOT) PRECONSTRUCTION MEETING AND SHALL INFORM THE IDOT TRAFFIC ENGINEER BEFORE WORK COMMENCES.
- 6. THE CONTRACTOR SHALL KEEP PUBLIC STREET PAVEMENTS CLEAN OF DIRT AND DEBRIS.
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE IN PROVIDING SAFE AND HEALTHFUL CONDITIONS THROUGHOUT THE CONSTRUCTION OF THE PROPOSED IMPROVEMENTS.
- 8. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UNDERGROUND AND SURFACE UTILITIES EVEN THOUGH THEY MAY NOT BE SHOWN ON THE PLANS. ANY UTILITY THAT IS DAMAGED DURING CONSTRUCTION SHALL BE RESTORED TO A CONDITION EQUAL TO THAT EXISTING BEFORE THE DAMAGE INCURRED. THIS WORK SHALL BE AT THE CONTRACTOR'S EXPENSE.
- 9. THE TRAFFIC CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "ECONOLITE" TO MATCH THE EXISTING ADJACENT SYSTEM.
- 10. RESTORATION OF THE WORK AREA SHALL BE INCIDENTAL TO THE RELATED PAY ITEMS AND SHALL BE REPLACED IN KIND. ALL DAMAGE TO MOWED LAWNS SHALL BE REPLACED WITH AN APPROVED SOD, AND ALL DAMAGE TO UNMOWED FIELDS SHALL BE SEEDED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS 252 AND 250, RESPECTIVELY.
- 11. CONTROLLER CABINETS SHALL BE PLACED SO THAT a) THE DOORS OPEN AWAY FROM THE CURB OR TRAVEL WAY., b) AND THE TRAFFIC MOVEMENTS AT THE INTERSECTION ARE VISIBLE FROM THE CONTROLLER.
- 12. UNINTERRUPTIBLE POWER SUPPLIES SHALL BE PLACED ON THE SIDE OF THE CONTROLLER CABINET NEAREST TO THE ENTRY OF THE ELECTRIC SERVICE CONDUIT.

PREPARED BY:

CEMCON, Ltd.
Consulting Engineers, Land Surveyors & Planners
 2280 White Oak Circle, Suite 100
 Aurora, Illinois 60504-9675
 Ph: 630.862.2100 Fax: 630.862.2199
 E-Mail: cadd@cemcon.com Website: www.cemcon.com

FILE NAME = MICROST\352056\ 02-GENNOTES.DGN	USER NAME = JLA	DESIGNED - KK	REVISED -
		DRAWN - JLA	REVISED -
	PLOT SCALE = 1"=20'	CHECKED - BPT	REVISED -
	PLOT DATE = 12-10-08	DATE - 12-10-08	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

GENERAL NOTES			
U.S. ROUTE 12 (RAND ROAD)			
MILLER ROAD THROUGH OLD RAND ROAD (S. JCT.)			
SCALE: N.T.S.	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
334	2008-069 TS	LAKE	26	2
CONTRACT NO. 60F62				
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				