

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QTY.	100% STATE URBAN	
				ROADWAY 1000-2A	BX CULV. 1007
20200100	EARTH EXCAVATION	CU YD	116		116
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	115		115
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	44	44	
25000310	SEEDING, CLASS 4	ACRE	0.10	0.10	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1	1	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1	1	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1	1	
25100630	EROSION CONTROL BLANKET	SQ YD	44	44	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1	1	
28000300	TEMPORARY DITCH CHECKS	EACH	2	2	
28000400	PERIMETER EROSION BARRIER	FOOT	60	60	
28100107	STONE RIPRAP, CLASS A4	SQ YD	26		26
28200200	FILTER FABRIC	SQ YD	48		48
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	140	140	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	140		140
50300300	PROTECTIVE COAT	SQ YD	11		11
50800105	REINFORCEMENT BARS	POUND	1975		1975
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	106		106
51500100	NAME PLATES	EACH	1		1
54003000	CONCRETE BOX CULVERTS	CU YD	25.7		25.7
54010703	PRECAST CONCRETE BOX CULVERT 7'x3'	FOOT	92		92
67100100	MOBILIZATION	L SUM	1	1	
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1986	1986	
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	26	26	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	418	418	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	206	206	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4	
* 78200200	BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	17	17	
* 78200500	BARRIER WALL MARKERS	EACH	42	42	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	40	40	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3	3	
* 81800320	AERIAL CABLE, 3-1/C NO. 4 WITH MESSENGER WIRE	FOOT	510	510	
* 83057350	LIGHT POLE, WOOD, 60 FOOT, CLASS 4	EACH	1	1	
84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	4	4	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	50	50	
X0323002	TEMPORARY ELECTRIC SERVICE CONNECTION	EACH	1	1	
X0323003	TEMPORARY ELECTRIC SERVICE INSTALLATION	EACH	1	1	
X0324304	REMOVAL OF TEMPORARY WOOD POLE, SALVAGE	EACH	4	4	
X0325265	REMOVE ELECTRIC SERVICE	EACH	1	1	
X0325553	TEMPORARY WOOD POLE, 60 FT., CLASS 4, 20 FT. MAST ARM	EACH	3	3	
X0326319	TEMPORARY LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400W, TYPE II DISTRIBUTION	EACH	3	3	
* X0325867	COMBINATION POLE MOUNTED ELECTRIC SERVICE BOX	EACH	1	1	
* X0325878	TRAFFIC SIGNAL WOOD POLE, 60 FT., CLASS 4	EACH	4	4	
<del>70106800</del>	CHANGEABLE MESSAGE SIGN	CAL MD	<del>3</del>	<del>3</del>	
* X8410118	MAINTENANCE OF TEMPORARY LIGHTING SYSTEM	L SUM	1	1	
* XX006937	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	2	2	
* XX007025	COARSE AGGREGATE BACKFILL (SPECIAL)	CU YD	310		310
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1

\* SPECIALTY ITEMS  
 X0323988 TEMPORARY SOIL RETENTION SYSTEM

SQ FT 245 245